


# Instruction Manual MICROCROSS FERRULE CRIMP TOOLS

Part No. 62200-4400 & 62201-8000

For MicroCross<sup>™</sup> Ferrules P.N.'s 79901-1116, 73772-0001, 73772-0002, 73772-0003, 73772-0004 & 88789-9376



\*DESCRIPTION \*OPERATION \*MAINTENANCE

Doc. No.

622004410

Release Date

1997/09/24

Revision:

C

Revision Date 2000/09/28

#### **WARNING**

NEVER

OPERATE, SERVICE OR ADJUST THIS DEVICE WITHOUT PROPER INSTRUCTION AND WITHOUT FIRST READING AND UNDERSTANDING THE INSTRUCTIONS IN THIS MANUAL

**WORK SAFELY AT ALL TIMES** 

## FOR SERVICE, CONTACT YOUR LOCAL MOLEX SALES OFFICE

MOLEX INCORPORATED TOOLING GROUP 1150 E. DIEHL ROAD NAPERVILLE, ILLINOIS 60532 (630) 969-4550 FAX: (630) 505-0049

## 62200-4400 EVC FERRULE CRIMP TOOL & 62201-8000 DVI FERRULE CRIMP TOOL

#### **TABLE OF CONTENTS**

#### **SECTION**

- 1 General Description, Installation & Operation
- 2 Maintenance, Spare Parts, Perishable Parts & Problem Checklist
- 3 Parts List and Assembly Drawing

#### **APPENDIX**

- A Product Specifications and Application Specifications
- **B** Terms and Conditions

#### **SECTION 1**

## GENERAL DESCRIPTION, INSTALLATION & OPERATION

| 1.1 | DESCRIPTION              |   | age<br>5 |
|-----|--------------------------|---|----------|
| 1.2 | FEATURES                 |   | 5        |
| 1.3 | TECHNICAL SPECIFICATIONS |   | 5        |
| 1.4 | DELIVERY CHECK           | • | 5        |
| 1.5 | TOOLS                    |   | 5        |
| 1.6 | INSTALLATION             |   | 6        |
| 1.7 | SET UP                   |   | 6        |
| 1.8 | OPERATION                | _ | 8        |

#### 1. GENERAL DESCRIPTION

#### 1.1 TOOL DESCRIPTION

The 62200-4400 EVC MicroCross Ferrule Crimp Tool & the 62201-8000 DVI MicroCross Tool are designed to crimp the Molex Ferrules (see below for Part No.'s) to the cable assembly. There are (6+) die sets included with this tool, one set for each ferrule. This tooling works in conjunction with the Molex 11-31-6356 Manual Press (not included with tool kit). The operator takes a partially completed harness, closes the EMI Shield and places the appropriate ferrule over the end of the shield. Then the operator loads this assembly into the crimp tooling and crimps the ferrule by activating the press.

Note: The correct set of dies must be used with the ferrule being crimped, if not, it may result in damage to the tool. The list below shows the die set to use for each ferrule.

| <b>Ferrule</b> 79901-1116     | <b>Die Set</b> 62200-4402 |
|-------------------------------|---------------------------|
| 73772-0001<br>(.289321 Cable) | 62200-4403                |
| 73772-0001<br>(.246288 Cable) | 62200-6700                |
| 73772-0002                    | 62200-4431                |
| 73772-0003                    | 62200-4436                |
| 73772-0004                    | 62200-6800                |
| 88789-9376<br>(.189246)       | 62201-7900                |

#### 1.2 FEATURES

- \* Unique tool configuration performs high strength hex crimp.
- \* Die sets are quickly and easily installed or changed
- \* Crimp height adjustment on press to avoid over or under crimping.
- \* Tooling allows user to crimp both large and small diameters of ferrule in one step.

#### 1.3 TECHNICAL SPECIFICATIONS

#### 1.3.1 Dimensions

Height

| Width | 12.7cm (5.0in) |
|-------|----------------|
| Depth | 9.5cm (3.75in) |

#### **1.3.2 Weight** 2.25kg (5.0lbs)

#### 1.3.3 Production Rate

An operator can expect to produce approximately 300 finished assemblies per hour depending on operator skiill.

3.4cm (1.38in)

#### 1.4 DELIVERY CHECK

Carefully remove the Crimp Tooling from its shipping container and check to determine if parts are included (See appropriate Parts Lists in Section 3)

#### 1.5 TOOLS

The following may be needed to operate or adjust this tool:

| •                      | Qty. |
|------------------------|------|
| Metric Hex Wrench Set  | 1    |
| Micrometer or Calipers | 1    |
| Set of Feeler Gauges   | 1    |

#### 1.6 INSTALLATION

- Determine what ferrule and cable assembly is to be crimped and locate the correct die set.
- 2. Install the two (2) upper dies in the upper tooling holder.

NOTE: The dies are keyed and can only be installed one way. (See Fig. 1-1)

- Slide the tooling holder (62200-4418) upward, over the bottom of the press ram until it comes to a stop (See Fig. 1-1). Note: slightly lowering the press ram may assist in installing the tooling holder.
- 4. Push the latch (11-31-7151) slightly backward away from the ram.
- The tooling holder will now slide up the ram an additional 4.0MM approx.
- Release the latch so the upper tooling will stay in place on the press.
- Install the (2) lower dies in the lower tooling holder and tighten with set screw. Note: The dies are keyed and can only be installed one way.
- 8. Place the lower tooling on the Press Base. Install (2) M5 screws (See Fig. 1- 2).

Do not tighten the screws at this time.

#### **1.7 SET UP**

WARNING: Pull force of completed assembly is very sensitive to Setup and cable diameter.
Therefore, great care must be taken in completing the instructions in this section.




Fig. 1-1
DIE SET KEYS

#### 1.7.1 Lower Tooling Positioning

Once the lower tooling is loosely in position, it must be precisely set according to the ferrule to be crimped.

- Using Table 1.1, select the "A" dimension for the ferrule and die set to be used.
- Refer to Fig. 1-3 and slide the lower tooling back or forward to meet the required "A" dimension. Use calipers or gauge blocks.
- 3. The figures given here are a starting point and may possibly have to be further adjusted. To check this alignment, take several plain ferrules and crimp them. Then inspect them per Fig. 1-3.
- 4. Readjust as required to achieve a good crimp.
- 5. Tighten the two (2) M5 Screws.




Fig. 1-2
MOUNTING LOWER TOOLING

**TABLE 1-1** 

| Ferrule No. | Die Set No. | "A"                    |
|-------------|-------------|------------------------|
| 79901-1116  | 62200-4402  | 0.620 in.<br>(15.75mm) |
| 73772-0001  | 62200-4403  | 0.620 in.<br>(15.75mm) |
| 73772-0002  | 62200-4431  | 0.620 in.<br>(15.75mm) |
| 73772-0003  | 62200-4436  | 0.625 in.<br>(15.87mm) |
| 73772-0004  | 62200-6800  | 0.620 in.<br>(15.87mm) |
| 73772-0001  | 62200-6700  | 0.620 in.<br>(15.75mm) |
| 88789-9376  | 62201-7900  | 0.620 in.<br>(15.75mm) |




Fig. 1-3
CRIMP DIE ALIGNMENT

#### 1.7.2 Crimp Height Adjustment

(See Fig. 1-6 and also Press Instruction Manual, Part No. 11-32-8186) Lower the Press Ram slightly to expose the Adjustment Locking Screw. Loosen this screw until the Crimp Height Adjusting Knob moves freely. To increase the crimp height, turn the height adjusting knob to the right (toward the "+" sign). To decrease the crimp height, turn the crimp height adjusting knob to the left (toward the "-" sign). Be sure to retighten the locking screw before continuing to use the press. For proper crimp height, the closed die gap should be set per TABLE 2.

**TABLE 2** 

| Ferrule No. | Die No.    | "B"                   |
|-------------|------------|-----------------------|
| 73772-0001  | 62200-4403 | 0.025 in.<br>(0.63mm) |
| 73772-0002  | 62200-4431 | 0.025 in.<br>(0.63mm) |
| 73772-0003  | 62200-4436 | 0.070 in.<br>(1.78mm) |
| 73772-0004  | 62200-6800 | 0.080in.<br>(2.03mm)  |
| 73772-0001  | 62200-6700 | 0.057 in.<br>(1.45mm) |
| 88789-9376  | 62201-7900 | 0.039in.<br>(1.0mm)   |

Use feeler gauges to measure "B" as shown in Fig. 1-4.




Fig. 1-4
SHUT HEIGHT MEASUREMENT

#### 1.8 OPERATION

**CAUTION**: Cable diameter is critical to a good crimp so be sure the correct diameter cable is used for the selected ferrule.

- 1. Snap the EMI Shield closed and place correct ferrule over the back of the EMI Shield as far as it will go.
- 2. With the ram in the up position, place a cable assembly (with ferrule fit over EMI Shield) into the lower tooling.
- 3. Slowly lower the ram by pulling the press handle forward and down to crimp ferrule to the cable and EMI Shield. Note: The press handle cannot be returned to the up position until it has been lowered to the full down position.
- 4. Return the press handle to the up position.

**NOTE:** In case of a jam or some other problem, the press ram can be returned to the up position




Fig.1-5
FULL STROKE RATCHET RELEASE

on the upper left of the press frame (See Fig. 1-5).

5. Remove completed cable assembly with the crimped ferrule.




Fig. 1-6
TERMINATION DEPTH ADJUSTMENT

#### **SECTION 2**

## MAINTENANCE, PERISHABLE PARTS, SPARE PARTS & PROBLEM CHECKLIST

| 2.1 | MAINTENANCE       | ⊃age<br>11 |
|-----|-------------------|------------|
| 2.2 | PERISHABLE PARTS  | 11         |
| 2.3 | SPARE PARTS       | 11         |
| 2.4 | PROBLEM CHECKLIST | 12         |

## 2. MAINTENANCE, PERISHABLE PARTS, SPARE PARTS & PROBLEM CHECKLIST

#### 2.1 MAINTENANCE

#### 2.1.2 Cleaning

Approximately once a day, depending on usage, a soft brush should be used to remove any plating dust or other debris from the tooling.

The use of compressed air to clean the dies is not recommended as it can cause debris to wedge in the tooling and/or come flying out at the operator.

#### 2.1.2 Lubrication

There is nothing on the EVC Ferrule Crimp Tool that needs lubrication. However, the Molex Manual Press needs regular lubrication. Please consult the Press Instruction Manual (P.N. 11-32-8186) for that schedule.

#### 2.2 PERISHABLE PARTS

These are parts that contact the product and wear over time. The customer is responsible for maintaining a set of these parts and Molex recommends that they keep at least one set on hand at all times.

| Molex Order No. | Description         |
|-----------------|---------------------|
| 62200-4402      | Die Ass'y. (Ferrule |
|                 | #79901-1116)        |
| 62200-4403      | Die Ass'y. (Ferrule |
|                 | #73772-0001 .289 -  |
|                 | .312 Cable)         |

| 62200-4431 | Die Ass'y. (Ferrule         |
|------------|-----------------------------|
|            | #73772-0002)                |
| 62200-4436 | Die Ass'y. (Ferrule         |
|            | #73772-0003)                |
| 62200-6700 | Die Ass'y. (Ferrule         |
|            | <b>#73772-0001</b> , .246 · |
|            | .288 Cable)                 |
| 62200-6800 | Die Ass'y. (Ferrule         |
|            | #73772-0004                 |
| 62201-7900 | Die Ass'y. (Ferrule         |
|            | #88789-9376                 |

Please consult the Press Manual for the perishable parts list for the press.

#### 2.3 SPARE PARTS

These are parts that are available to support the tooling in service. They are moving or otherwise functioning that could be damaged or malfunction. It is suggested that the customer may want to keep some or all of these parts on hand to reduce down time. These parts are identified in the Parts List in Appendix A.

#### **PROBLEM CHECKLIST**

#### **PROBLEM**

#### Crimp is not to specifications (Too lose or too tight)

2. Ferrule sticks in lower tooling after crimping.

#### **CAUSE**

- 1. Press shut height is incorrectly set.
- 2. Worn surface on lower tooling

#### **SOLUTION**

- 1. Readjust to proper crimp height (See Section 1.7.1)
- 2. Inspect and replace defective tooling.

#### **SECTION 3**

#### PARTS LISTS AND ASSEMBLY DRAWINGS

The following pages contain the MicroCross Ferrule Crimp Tool Parts Lists and Assembly Drawings. There are several things that will help the reader better understand and use this material.

- 1. The "Item" number in the Parts List matches the number in the bubble on the Assembly Drawing.
  - 2. The "Order No." is the number to use when ordering that particular item.
  - 3. "RSP" appearing at the end of the Description column means this item is a Recommended Spare Part.
  - 4. The "Req'd." number is the quantity of that item required per assembly. It is also the quantity Molex recommends the user keep on hand if this a Perishable Part or a Recommended Spare Part
  - 5. An asterisk beside the item number bubble on the Assembly Drawing indicates a Recommended Spare Part.

#### PARTS LIST 62200-4400 (EVC)

| Item | Order No.  | Description           | Req'd. |
|------|------------|-----------------------|--------|
| 1    | 62200-4401 | Assembly, Fixture     | 1      |
| 2    | 62200-4402 | Assembly, Ferrule Die | 1      |
| 3    | 62200-4003 | Assembly, Ferrule Die | 1      |
| 4    | 62200-4431 | Assembly, Ferrule Die | 1      |
| 5    | 62200-4436 | Assembly, Ferrule Die | 1      |
| 6    | 62200-6700 | Assembly, Ferrule Die | 1      |
| 7    | 62200-6800 | Assembly, Ferrule Die | 1      |
| 8    | 62200-4410 | Manual, Instruction   | 1      |
|      |            |                       |        |

#### PARTS LIST 62201-8000 (DVI)


| Item | Order No.  | Description           | Req'd. |
|------|------------|-----------------------|--------|
| 1    | 62200-4401 | Assembly, Fixture     | 1      |
| 2    | 62201-7900 | Assembly, Ferrule Die | 1      |

#### ADDITIONAL DIE ASSEMBLIES REQUIRED FOR DVI


| Item | Order No.  | Description           | Req'd. |
|------|------------|-----------------------|--------|
|      | 62200-4431 | Assembly, Ferrule Die | 1      |
|      | 62200-6700 | Assembly, Ferrule Die | 1      |
|      |            |                       |        |

#### PARTS LIST 62200-4401


| Item | Order No.  | Description           | Req'd. |
|------|------------|-----------------------|--------|
| 1    | 62200-4417 | Fixture, Tooling      | 1      |
| 2    | 62200-4418 | Tooling, Holder       | 1      |
| 3    | 62200-4419 | Retainer, Wire        | 1      |
| 4    | 62200-4420 | Base, Wire Retainer   | 1      |
| 5    | 62200-4421 | Pad, Pressure         | 1      |
| 6    | 62200-4422 | Gib, Pad              | 2      |
| 7    | 62200-4429 | Block, Stop           | 1      |
| 8    | 63700-2080 | Spring, Compression   | 2      |
| 9    | 62200-4425 | Stop, Pad             | 2      |
| 10   |            | Dowel                 | 2      |
| 11   | 62200-4427 | Holder, Lower Tooling | 1      |
| 12   |            | Dowel                 | 2      |
| 13   | 62200-4430 | Stop, Upper Die       | 1      |
| 14   | 11-31-7151 | Latch                 | 1      |
| 15   | 11-31-7152 | Spring                | 1      |
|      |            |                       |        |
|      |            |                       |        |



62200-4400 FIXTURE AND EVC DIE ASSEMBLY



62201-8000 FIXTURE AND DVI DIE ASSEMBLY



62200-4401 ASSEMBLY, CRIMP FIXTURE

#### PARTS LIST 62200-4402

| Item | Order No.  | Description           | Req'd |
|------|------------|-----------------------|-------|
| 31   | 62200-4409 | Die, Upper Left Half  | 1`    |
| 32   | 62200-4410 | Die, Lower Left Half  | 1     |
| 33   | 62200-4411 | Die, Lower Right Half | 1     |
| 34   | 62200-4412 | Die, Upper Right Half | 1     |
|      |            |                       |       |

#### PARTS LIST 62200-4403

| ltem | Order No.  | Description           | Req'd. |
|------|------------|-----------------------|--------|
| 41   | 62200-4413 | Die, Upper Right Half | 1      |
| 42   | 62200-4414 | Die, Lower Right Half | 1      |
| 43   | 62200-4415 | Die, Upper Left Half  | 1      |
| 44   | 62200-4416 | Die, Lower Left Half  | 1      |
|      |            |                       |        |

#### PARTS LIST 62200-4431

| Item | Order No.  | Description           | Req'd. |
|------|------------|-----------------------|--------|
| 51   | 62200-4432 | Die, Upper Left Half  | 1      |
| 52   | 62200-4433 | Die, Lower Left Half  | 1      |
| 53   | 62200-4434 | Die, Lower Right Half | 1      |
| 54   | 62200-4435 | Die, Upper Right Half | 1      |
|      |            |                       |        |

#### PARTS LIST 62200-4436

| Item | Order No.  | Description           | Req'd. |
|------|------------|-----------------------|--------|
| 61   | 62200-4437 | Die, Upper Left Half  | 1      |
| 62   | 62200-4438 | Die, Lower Left Half  | 1      |
| 63   | 62200-4439 | Die, Upper Right Half | 1      |
| 64   | 62200-4440 | Die, Lower Right Half | 1      |

#### PARTS LIST 62200-6700


| Item | Order No.  | Description           | Req'd. |
|------|------------|-----------------------|--------|
| 71   | 62200-4413 | Die, Upper Right Half | 1      |
| 72   | 62200-4414 | Die, Lower Right Half | 1      |
| 73   | 62200-6715 | Die, Upper Left Half  | 1      |
| 74   | 62200-6716 | Die, Lower Left Half  | 1      |

#### PARTS LIST 62200-6800


| Item | Order No.  | Description           | Req'd. |
|------|------------|-----------------------|--------|
| 81   | 62200-6837 | Die, Upper Left Half  | 1      |
| 82   | 62200-6838 | Die, Lower Left Half  | 1      |
| 83   | 62200-4439 | Die, Upper Right Half | 1      |
| 84   | 62200-4440 | Die, Lower Right Half | 1      |

#### PARTS LIST 62201-7900


| ltem | Order No.  | Description      | Req'd. |
|------|------------|------------------|--------|
| 91   | 62201-7901 | Die, Upper Left  | 1      |
| 92   | 62201-7902 | Die, Lower Left  | 1      |
| 93   | 62201-7903 | Die, Upper Right | 1      |
| 94   | 62201-7904 | Die, Lower Right | 1      |




62200-4402 ASSEMBLY, FERRULE CRIMP DIE (FOR FERRULE #79901-1116)





62200-4403 ASSEMBLY, FERRULE CRIMP DIE (FOR FERRULE #73772-0001)




62200-4431 ASSEMBLY, FERRULE CRIMP DIE (FOR FERRULE #73772-0002)









62201-7900 ASSEMBLY, FERRULE CRIMP DIE (FOR FERRULE # 88789-9376)

#### **APPENDIX A**

## PRODUCT SPECIFICATIONS AND APPLICATION SPECIFICATIONS

**NOTE:** The documents included in this section are uncontrolled and therefore may not be the latest revision. Should you desire the latest revision, please contact your local Molex sales representative and ask for the specific document number.





LANGUAGE ENGLISH

#### 1.0 Scope

This specification covers the Molex MicroCross™ - EVC and P&D system. This system includes cable plugs and receptacles which have been adopted by the Video Electronics Standards Association, VESA, as the Enhanced Video Connector, EVC, and the Plug and Display, P&D, connector.

The Enhanced Video Connector standard covers a plug and receptacle connector system for analog video signals. The Plug and Display standard covers a plug and receptacle for digital video signals, as well as a receptacle which supports both analog and digital video signals.

This specification covers the combined EVC and P&D, cable to board, I/O connector system with requirements as set forth by Molex Inc.

#### 2.0 Product Description

The MicroCross™ system is designed to meet the industry's requirements for computer monitors and integrated multimedia functions. This is achieved by utilizing two different sets of contacts as shown in Figure 1 below:




Figure 1: Two sets of contacts

|    | REV  | F    | F     | F     | F                  | F    | F    | F  | F     | F                               | F      | F     | F          | F           | F             | F          | F           | F   | F                    | F    | F   | F      | F    | F   |
|----|--|------|-------|-------|--------------------|------|------|----|-------|---------------------------------|--------|-------|------------|-------------|---------------|------------|-------------|-----|----------------------|------|-----|--------|------|-----|
|    | SHT  | 1    | 2     | 3     | 4                  | 5    | 6    | 7  | 8     | 9                               | 10     | 11    | 12         | 13          | 14            | 15         | 16          | 17  | 18                   | 19   | 20  | 21     | 22   | 23  |
|    |  | REV  | ISE ( | ON F  | o o                | NLY  |      |    | TIT   | TITLE MicroCross™ - EVC and P&D |        |       |            |             |               |            |             |     |                      |      |     |        |      |     |
|    | FINAL RELEASE PER EC# U81070 SCARTH 97/10/15 |      |       |       |                    |      |      |    |       |                                 |        | 1/0   | Plu<br>Con | g ar<br>nec | nd R<br>tor ( | ece<br>Sys | epta<br>tem | cle |                      |      |     |        |      |     |
|    | REV  |      |       | )ESC  | RIP                | TION |      |    | 1     |                                 |        |       |            |             | INFO          |            |             |     |                      |      |     |        |      |     |
|    |  |      |       |       |                    |      |      |    | 10101 |                                 | 10. Al | 10 01 | OOLL       | - 110       | 00.0          | 7360       | 44111       |     | T WRITTEN PERMISSION |      |     |        |      |     |
|    | DESI   | GN C | CON   | rro   | L                  | S    | ΓΑΤΙ | JS | WRI   | TTEN                            | BY:    | CHE   | CKED       | BY:         | API           | PROV       | 'ED B       | Y:  | DAT                  | E: Y | R/N | 10 / [ | YAC  | #   |
|    |  | UD   | T     |       |                    |      | M    |    | SC    | ART                             | H.     | NEI   | LIG.       | AN          | N             | ELLI       | GAN         | ı   |                      | 9    | 7/1 | 0/1    | 5    |     |
| DO | CUMENT                                       | NO.  |       |       |                    |      |      |    |       |                                 |        |       |            |             |               |            |             | F   | ILE                  | NAM  | E   | SI     | HT N | 10. |
|    | PS-71182                                     |      |       |       | PS71182.SAM 1 OF 2 |      |      |    |       |                                 | 23     |       |            |             |               |            |             |     |                      |      |     |        |      |     |
|    |  | ES   | S-400 | 000-3 | 3996               | RE   | V. A | SF | HEET  | 3                               | 95/M   | IAR/  | 10         | EC          | U5-0          | 926        | D           | CBF | RD03                 | 3.SA | M   |        |      |     |





LANGUAGE ENGLISH

1. General purpose signals:

Contacts: 30 circuits on a 0.075 inch grid

Signals: Can include power, grounds, digital signal sets, and low frequency analog signals.

2. MicroCross<sup>TM</sup>:

a) EVC plug, EVC receptacle, and P&D - A/D (Analog/Digital) receptacle Contacts: 4 circuits on a 0.100 inch grid with a crossing ground plane in between

Signals: High frequency, 75 ohm, analog video

b) P&D plug and P&D - D (Digital) receptacle

Contacts: A single key on the P&D plug and corresponding slot on the P&D

receptacle.

Signals: The key is used for mechanical polarization only, it does not carry any

electrical signals.

Additional general specifications are:

#### Plug:

-LFH (Low Force Helix) style contacts

-fully shielded RFI/EMI can

-grounding detents on mating shell

-solder tails for cable termination

-positive retention jackscrew: thread 4-40 UNC-2A

#### Receptacle:

-high cycle, dual beam, LFH shrouded contacts

-polarization achieved by a "D" shaped housing/shield

-single piece shield with integral ground leg

-shield protrudes for ESD considerations

-solder tails for thru hole board mount

-plastic retention pegs

-jackposts: thread 4-40 UNC-2A&B

#### Intermating:

The EVC and P&D connectors are physically very similar but carry different signal sets. The differences between these signal sets require that certain mating combinations be allowed while others be excluded. A matrix of mating configurations and the type of video signal carried between connectors is shown in Figure 2.

|    |        | REVISE ON PC ONLY       | TITLE    |              | MicroCross™           |      |                    |        |    |
|----|--------|-------------------------|----------|--------------|-----------------------|------|--------------------|--------|----|
|    | F      | SEE SHEET 1             | <u>.</u> |              | I/O Plug ar<br>Connec |      |                    |        |    |
| }  |        |                         | THIS D   | OCUMENT COM  | NTAINS INFORMA        | TION | THAT IS PROPRIETAR | Y TO   | 1  |
|    | REV    | DESCRIPTION             | MOLEXII  | NC. AND SHOU | LD NOT BE USED        | WITH | OUT WRITTEN PERM   | ISSION |    |
| DO | CUMENT | NO.                     | T        |              |                       |      | FILE NAME          | SHEE   | ΞΤ |
|    |        | PS-71182                |          |              |                       |      | PS71182.SAM        | 2      |    |
|    |        | ES-40000-3996 REV. A SH | HEET 4   | 95/MAR/10    | EC U5-0926            | DC   | BRD03.SAM          |        |    |





LANGUAGE ENGLISH




Figure 2: Possible mating configurations.

The table below contains a summary of which mating configurations are possible.

|          | EVC Receptacle                    | P&D - A/D Receptacle | P&D - D Receptacle  |
|----------|-----------------------------------|----------------------|---|
| EVC Plug | Yes - Analog video                | Yes - Analog Video   | No - Plug groundplane stops on receptacle housing preventing mating |
| P&D Plug | No - Shield shape prevents mating | Yes - Digital Video  | Yes - Digital Video   |

|    | R        | EVISE ON PC ONLY     | TITLE          | MicroCross™ - E`<br>I/O Plug and F |                    |        |
|----|----------|----------------------|----------------|------------------------------------|--------------------|--------|
|    | F        | SEE SHEET 1          |                | Connector                          |                    |        |
|    |          |                      | THIS DOCUME    | NT CONTAINS INFORMATION            | THAT IS PROPRIETAR | Y TO   |
|    | REV      | DESCRIPTION          | MOLEX INC. AND | SHOULD NOT BE USED WIT             | HOUT WRITTEN PERM  | ISSION |
| DO | CUMENT N | 10.                  |                |                                    | FILE NAME          | SHEET  |
|    |          | PS-71182             |                |                                    | PS71182.SAM        | 3      |
|    |          | FS-40000-3996 REV. A | SHEET 4 95/MA  | R/10 EC U5-0926 D                  | CBRD03.SAM         |        |






LANGUAGE

**ENGLISH** 

#### 2.1 Product Name and Drawing Numbers

#### 2.1.1 EVC Receptacle

The EVC receptacle is for systems which use analog video only. It will only mate to the EVC plug.



#### **EVC Receptacle Sales Drawings:**

DescriptionSales Drawing NumberRight AngleSDA-71182-2\*\*\*VerticalSDA-71182-3\*\*\*JackpostsSD-71781-\*\*\*\*

|     | F SEE SHEET 1 | TITLE                |  |   | - EVC and P&D |                      |        |  |
|-----|---------------|----------------------|--|---|---------------|----------------------|--------|--|
|     |               |                      | I/O Plug and Receptacle Connector System |   |               |                      |        |  |
|     |               |                      | THIS DO                                  | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO |               |                      |        |  |
|     | REV           | DESCRIPTION          | MOLEX IN                                 | C. AND SHOUL  | D NOT BE USED | WITHOUT WRITTEN PERM | ISSION |  |
| DOC | CUMENT        | NO.                  |  | · · · · · · · · · · · · · · · · · · ·                     |               | FILE NAME            | SHEET  |  |
|     |               | PS-71182             |  |   |               | PS71182.SAM          | 4      |  |
|     |               | ES-40000-3996 REV. A | SHEET 4 9                                | 5/MAR/10  | EC U5-0926    | DCBRD03.SAM          |        |  |






LANGUAGE

**ENGLISH** 

#### 2.1.2 EVC Plug

The EVC plug is used for analog video. It will mate to either the EVC or P&D - A/D receptacles.



#### **EVC Plug Sales Drawings:**

| Description         | Sales Drawing Number |
|---------------------|----------------------|
| Sub-assembly        | SDA-71754-2000       |
| 10 ckt Molded Stick | SDA-73623-1***       |
| 2 ckt Molded Stick  | SDA-71197-9***       |
| Ground Plane        | SD-71198-100*        |
| EMI Shield Kit      | SDMS-71755-100*      |
| Crimp Ferrules      | SD-73772-000         |
| Boots               | SD-73784-001         |
| Jackscrew with cap  | SD-71757-0002        |

|     | REVISE ON PC ONLY |                        | TITLE MicroCross™ - EVC and P&D                              |  |  |  |  |
|-----|-------------------|------------------------|--|--|--|--|--|
|     | F SEE SHEET 1     |                        | I/O Plug and Receptacle<br>Connector System                  |  |  |  |  |
|     |                   |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO    |  |  |  |  |
|     | REV               | DESCRIPTION            | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |  |  |  |  |
| DOC | CUMENT            | NO.                    | FILE NAME SHEET  |  |  |  |  |
|     |                   | PS-71182               | PS71182.SAM 5  |  |  |  |  |
|     |                   | ES-40000-3996 REV. A S | SHEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM                     |  |  |  |  |






LANGUAGE ENGLISH

#### 2.1.3 P&D - A/D (Analog/Digital) Receptacle

The P&D-A/D receptacle supports analog video through the MicroCross™ section and digital video through the general circuit pins. It mates with either the EVC or P&D plug.



#### P&D-A/D Receptacle Sales Drawings:

| <u>Description</u> | Sales Drawing Number |
|--------------------|----------------------|
| Right Angle        | SD-73712-001         |
| Vertical           | SD-73712-002         |
| Jackposts*         | SD-71781-****        |

\*Note: The jackposts are the same for all versions of the receptacle.

|    | REVISE ON PC ONLY              |                         | TITLE MicroCross™ - EVC and P&D  |         |            |    |             |       |
|----|--------------------------------|-------------------------|--|---------|------------|----|-------------|-------|
|    | F SEE SHEET 1  REV DESCRIPTION |                         | I/O Plug and Receptacle Connector System  THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |         |            |    |             |       |
|    |                                |                         |  |         |            |    |             | I .   |
| DO | CUMENT N                       | Ю.                      |  |         |            |    | FILE NAME   | SHEET |
|    | PS-71182                       |                         |  |         |            |    | PS71182.SAM | 6     |
|    |                                | ES-40000-3996 REV. A SI | HEET 4 95  | /MAR/10 | EC U5-0926 | DC | BRD03.SAM   |       |






LANGUAGE ENGLISH

#### 2.1.4 P&D Plug

The P&D plug is used for digital video and so does not contain the MicroCross™ section. Instead, it has a key in the MicroCross™ area to ensure proper mating. This plug will mate to either of the P&D receptacles.



#### P&D-D Plug Sales Drawings:

<u>Description</u> <u>Sales Drawing Number</u> Sub-assembly with key ..... SD-73814-001

 Crimp Ferrules\*\*
 SD-73772-000

 Boots\*\*
 SD-73784-001

 Jackscrew with cap\*\*
 SD-71757-0002

\*\*Note: These components are the same for both the EVC and P&D-D plugs.

|    | REVISE ON PC ONLY |                        | TITLE  | MicroCross™ - E  |             |       |  |
|----|-------------------|------------------------|--|------------------|-------------|-------|--|
|    | F SEE SHEET 1     |                        | I/O Plug and Receptacle Connector System   |                  |             |       |  |
|    | REV               | DESCRIPTION            | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |                  |             |       |  |
| DO | CUMENT            | NO.                    |  |                  | FILE NAME   | SHEET |  |
|    |                   | PS-71182               |  |                  | PS71182.SAM | 7     |  |
|    |                   | ES-40000-3996 REV. A S | SHEET 4 95/MAR   | V10 EC U5-0926 E | CBRD03.SAM  |       |  |






LANGUAGE ENGLISH

### 2.1.5 P&D - D (Digital) Receptacle

The P&D-D receptacle supports digital video only. Instead of the MicroCross™ section, it has a slot that allows it to mate with the P&D plug key but will not mate with the EVC plug ground plane.



# P&D-D Receptacle Sales Drawings:

DescriptionSales Drawing NumberRight AngleSD-73712-003VerticalSD-73712-004Jackposts\*SD-71781-\*\*\*\*

\*Note: The jackposts are the same for all versions of the receptacle.

|     |               | REVISE ON PC ONLY       | TITLE                                    | •         | MicroCross™     |      |                    |        |   |
|-----|---------------|-------------------------|--|-----------|-----------------|------|--------------------|--------|---|
|     | F SEE SHEET 1 |                         | I/O Plug and Receptacle Connector System |           |                 |      |                    |        |   |
|     |               |                         | THIS DOCL                                | JMENT COI | NTAINS INFORMAT | TION | THAT IS PROPRIETAR | Y TO   |   |
|     | REV           | DESCRIPTION             | MOLEX INC.                               | AND SHOU  | LD NOT BE USED  | WITH | OUT WRITTEN PERM   | ISSION |   |
| DOC | CUMENT        | NO.                     |  |           |                 |      | FILE NAME          | SHEET  | Γ |
|     |               | PS-71182                |  |           |                 |      | PS71182.SAM        | 8      |   |
|     |               | ES-40000-3996 REV. A SI | HEET 4 95/I                              | MAR/10    | EC U5-0926      | DC   | BRD03.SAM          |        |   |







LANGUAGE

**ENGLISH** 

# 2.2 Dimensions, Materials, Plating, and Markings 2.2.1 Board Layout





|     |               | REVISE ON PC ONLY       | TITLE                                       |         | MicroCross™    |      |                    |       |
|-----|---------------|-------------------------|---|---------|----------------|------|--------------------|-------|
|     | F SEE SHEET 1 |                         | I/O Plug and Receptacle<br>Connector System |         |                |      |                    |       |
|     |               |                         | 7   |         |                |      | THAT IS PROPRIETAR | I     |
|     | REV           | DESCRIPTION             | MOLEX INC. AN                               | D SHOUL | LD NOT BE USED | WITH | OUT WRITTEN PERM   | SSION |
| DOC | CUMENT        | NO.                     |   |         |                |      | FILE NAME          | SHEET |
|     |               | PS-71182                |   |         |                |      | PS71182.SAM        | 9     |
|     |               | ES-40000-3996 REV. A SH | HEET 4 95/M/                                | AR/10   | EC U5-0926     | DC   | BRD03.SAM          |       |





LANGUAGE

**ENGLISH** 

2.2.2 Materials

Housings:

High temp glass-filled thermoplastic, black, UL94 V-0 rated. Terminal Sticks: High temp glass-filled thermoplastic, black, UL94 V-0 rated.

Terminals:

Copper alloy.

2.2.3 Plating

Terminals:

Selective Gold (Au) in contact area:

Thickness: 30 microinch / 0.76 micrometer minimum; Selective Tin-Lead (Sn-Pb) Alloy in pc tail area: Thickness: 150 microinch / 1.3 micrometer minimum;

Nickel (Ni) overall.

Shields:

Bright Tin (Sn) overall:

Thickness: 150 microinch / 1.3 micrometer minimum;

Nickel (Ni) over Copper Flash (Cu) overall.

Keys:

Selective Gold (Au) in contact area:

Thickness: 4 microinch / 0.10 micrometer minimum;

Nickel (Ni) overall.

2.2.4 Markings

All assemblies will contain circuit identification markings as well as the Molex abbreviation 'MX' on the front of the shell. The first five digits of the part number also appears on all housings when possible. Refer to the appropriate sales drawings for specific marking information.

2.3 Safety Agency Approvals

UL File Number ..... E29179 CSA File Number ...... LR19980

|    |               | REVISE ON PC ONLY      | TITLE                                       |                          |                        |        |  |  |
|----|---------------|------------------------|---|--------------------------|------------------------|--------|--|--|
|    | F SEE SHEET 1 | SEE SHEET 1            | I/O Plug and Receptacle<br>Connector System |                          |                        |        |  |  |
|    |               | THIS DOCUM             | ENT CONTAINS INFORMA                        | ATION THAT IS PROPRIETAR | RY TO                  |        |  |  |
|    | REV           | DESCRIPTION            | MOLEX INC. AN                               | D SHOULD NOT BE USE      | O WITHOUT WRITTEN PERM | ISSION |  |  |
| DO | CUMENT        | NO.                    |   |                          | FILE NAME              | SHEET  |  |  |
| }  |               | PS-71182               |   |                          | PS71182.SAM            | 10     |  |  |
|    |               | ES-40000-3996 REV. A S | SHEET 4 95/MA                               | AR/10 EC U5-0926         | DCBRD03.SAM            |        |  |  |



LANGUAGE

**ENGLISH** 

- 3.0 Applicable Documents and Specifications
  - 3.1 All documents referenced shall be of the latest revision. The order of precedence detailing requirements of this specification is as follows:
    - 1. Product Drawings
    - 2. This specification
    - 3. VESA standards:

Enhanced Video Connector

- -Pinout & Signal Standards
- -Physical Connector

Plug and Display

4. Reference Documents

### 3.2 Reference Documents

- 3.2.1 EIA RS-364-(06,09,13,17,18,20,21,23,27,28,31,32,41,46,65,67,70,90) Electronic Industries Association, Recommended Standard
- 3.2.2 IEC-801-2 International Electrotechnical Commission, Electrostatic Discharge Requirements
- 3.2.3 MIL STD-202: Test methods for electronics and electrical component parts
- 3.2.4 Molex PS-71754-9999 Application Specification, EVC Plug Cable Assembly
- 3.2.5 Molex PS-73814-9999 Application Specification, P&D Plug Cable Assembly
- 3.2.6 Molex ES-71754-9998 Termination Specification, EVC Cable Assemblies
- 3.2.7 Molex ES-73814-9998 Termination Specification, P&D Cable Assemblies
- 3.2.8 UL 94: Tests for flammability of plastics materials

### 4.0 Ratings

4.1 Voltage

40 Volts AC (RMS)

### 4.2 Current

1.5 Amps per circuit.

30 °C maximum temperature rise and 55 °C maximum ambient per EIA-364-70.

### 4.3 Temperature

Operating:

- 20 °C to + 85 °C

Nonoperating: - 20 °C to + 85 °C

|    | RI       | EVISE ON PC ONLY       | TITLE          |  |                      |       |  |  |
|----|----------|------------------------|----------------|--|----------------------|-------|--|--|
|    | F        | SEE SHEET 1            |                | I/O Plug and Receptacle<br>Connector System  |                      |       |  |  |
|    | סביע     | DEL DECORIDE ON        |                | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |                      |       |  |  |
|    | REV      | DESCRIPTION            | MOLEX INC. AND | SHOOLD NOT BE USED W   | TIHOUI WRII IEN PERM | 2210N |  |  |
| DO | CUMENT N | 0.                     |                |  | FILE NAME            | SHEET |  |  |
|    |          | PS-71182               |                |  | PS71182.SAM          | 11    |  |  |
|    |          | ES-40000-3996 REV. A S | SHEET 4 95/MAF | R/10 EC U5-0926  | DCBRD03.SAM          |       |  |  |





LANGUAGE ENGLISH

# 5.0 Performance

### 5.1 Electrical Performance

| ITEM                               | TEST CONDITION   | REQUIREMENT  |
|------------------------------------|--|--|
| Contact Resistance                 | Bulk resistance measured between plug solder tails and receptacle solder tails   | 20 milliohm maximum initial  |
| Shell Resistance                   | Bulk resistance measured between ground leg on receptacle shield and the overall cable braid beyond plug crimp ferrule                 | 50 milliohm maximum initial  |
| Insulation Resistance              | 500 Volts DC for 1 minute<br>Unmated and Unmounted<br>per EIA 364-21, Method C   | 1Gigaohm Minimum   |
| Dielectric Withstanding<br>Voltage | 500 Volts DC for 1 minute<br>Unmated and Unmounted<br>per EIA 364-20, Method C   | No Breakdown   |
| Impedance                          | TDR method normalized to<br>1 ns risetime (General and MicroCross™ Lines)<br>or 500 ps risetime (Differential Lines)<br>per EIA 364-67 | General Signal Lines: 65 +/- 10 Ohms MicroCross™ Lines: 75 +/- 10% Ohms Differential Lines: 105 +/- 10% Ohms |
| Bandwidth                          |  | General Signal Lines: 0.8 GHz minimum MicroCross™ Lines: 2.4 GHz minimum Differential Lines: 2.4 GHz minimum |
| Crosstalk                          | Measure NEXT and FEXT at<br>1V / 500 ps (General and Differential Lines)<br>or 1V / 1 ns (MicroCross™ Lines)<br>per EIA 364-90         | 5% Maximum   |

|     |               | REVISE ON PC ONLY       | TITLE MicroCross™ - EVC and P&D                           | *     |  |  |  |
|-----|---------------|-------------------------|---|-------|--|--|--|
|     | F SEE SHEET 1 |                         | I/O Plug and Receptacle<br>Connector System               |       |  |  |  |
|     |               | DEV DECORPTION          | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO |       |  |  |  |
| Ĺ   | REV           | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISS | SION  |  |  |  |
| DOG | CUMENT        | NO.                     | FILE NAME   | SHEET |  |  |  |
|     |               | PS-71182                | PS71182.SAM   | 12    |  |  |  |
|     |               | ES-40000-3996 REV. A SH | HEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM                   |       |  |  |  |





LANGUAGE

**ENGLISH** 

# 5.2 Mechanical Performance

| ITEM                            | TEST CONDITION   | REQUIREMENT   |  |  |
|---------------------------------|--|---|--|--|
| Mating Force                    | One pair per EIA 364-13  | 10.0 lbf (4.5 kgf) maximum  |  |  |
| Unmating Force                  | Mated pair per EIA 364-13  | 2.2 lbf (1.0 kgf) minimum<br>8.8 lbf (4.0 kgf) maximum  |  |  |
| Plug Stick Retention            | Sticks are tested as a group<br>Either the three 10 ckt sticks or<br>MicroCross™ section                                   | 20.0 lbf (9.0 kgf) minimum  |  |  |
| Receptacle Contact<br>Retention | Individual contact   | 1.0 lbf (0.45 kgf) minimum  |  |  |
| P&D Plug Key<br>Retention       | Individual key   | 10.0 lbf (4.5 kgf) minimum  |  |  |
| Durability                      | 500 cycles per EIA 364-09  | Contact Resistance: 10 milliohm max (change from initial)   |  |  |
|                                 | at 500 +/- 50 cycles per hour  | Shell Resistance: 50 milliohm max (change from initial)   |  |  |
| Vibration                       | Contact Resistance: 10 million  15 minutes / axis (change from initial)  Shell Resistance: 50 million                      |   |  |  |
|                                 | per EIA 364-28, Method 5A  | (change from initial) No discontinuities greater than 1 microsecond   |  |  |
| Shock<br>(Mechanical)           | Per EIA 364-27, Condition A  | Contact Resistance: 10 milliohm max (change from initial) Shell Resistance: 50 milliohm max (change from initial) No discontinuities greater than 1 microsecond |  |  |
| Cable Pullout Force             | Cable subjected to 25.0 lbf (11.3 kgf) static load for one minute while monitoring continuity                              | No discontinuities greater than 1 microsecond   |  |  |
| Board Insertion Force           |  | 10.0 lbf (4.5 kgf) maximum  |  |  |
| Cable Flex                      | 100 cycles in each of two planes<br>Dimension X=3.7x Cable Diameter<br>per EIA 364-41, Condition 1                         | No discontinuities greater than 1 microsecond on contacts or shields  |  |  |
| Normal Force                    | For reference only   | .050" pitch terminals: 75 grams typical 90 grams typical 100 grams typical 100 grams typical  |  |  |
| Thread Torque                   | Mounted to panel; Test to failure; Tighten jackposts with torque gage until threads are stripped and jackpost turns freely | 5.0 in-lbs minimum  |  |  |

|    |               | REVISE ON PC ONLY      | TITLE   | · · · · · · · · · · · · · · · · · · ·       |                   |        |  |  |
|----|---------------|------------------------|---|---|-------------------|--------|--|--|
|    | F SEE SHEET 1 |                        |   | I/O Plug and Receptacle<br>Connector System |                   |        |  |  |
|    |               |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO |   |                   |        |  |  |
|    | REV           | DESCRIPTION            | MOLEX INC. AND  | SHOULD NOT BE USED WITH                     | HOUT WRITTEN PERM | ISSION |  |  |
| DO | CUMENT        | NO.                    |   |   | FILE NAME         | SHEET  |  |  |
|    |               | PS-71182               |   |   | PS71182.SAM       | 13     |  |  |
| L  |               | ES-40000-3996 REV. A S | HEET 4 95/MA  | R/10 EC U5-0926 D                           | CBRD03.SAM        |        |  |  |





LANGUAGE

ENGLISH

## 5.3 Environmental Performance

| ITEM                                      | TEST CONDITION   | REQUIREMENT  |
|---|--|--|
| Thermal Shock                             | 10 cycles of:  -55 °C for 30 minutes +25 °C for 30 minutes +85 °C for 30 minutes +25 °C for 30 minutes   | Contact Resistance: 10 milliohm max (change from initial)  Shell Resistance: 50 milliohm max (change from initial) |
|   | Mated/Unmated per EIA 364-32, Condition 1  |  |
| Humidity<br>(Steady State)                | 90 - 95% Humidity at 40 +/- 2 °C for 240 hours   | Contact Resistance: 10 milliohm max (change from initial)  |
|   | Unmated per EIA 364-31, Method II, Condition B   | Shell Resistance: 50 milliohm max (change from initial)  |
| Humidity<br>(Cyclic)                      | Mated per EIA 364-31 Condition A - Insulator Integrity Testing Condition C - Mated Environmental Testing | Contact Resistance: 10 milliohm max (change from initial)  |
|   | Both Tests: Method III, omit 7A and 7B   | Shell Resistance: 50 milliohm max (change from initial)  |
| Thermal Aging                             | 105 °C for 250 hours   | Contact Resistance: 10 milliohm max (change from initial)  |
|   | Mated per EIA 364-17, Condition 4, Method 4.   | Shell Resistance: 50 milliohm max (change from initial)  |
| Corrosive Environment (Flowing Mixed Gas) | Mated: 20 days total<br>Unmated: 1 day total   | Contact Resistance: 10 milliohm max (change from initial)  |
|   | Per EIA 364-65, Class II exposure  | Shell Resistance: 50 milliohm max (change from initial)  |
| Temperature Rise                          | Per EIA 364-70   | 30 °C maximum temperature rise   |
| Cold Resistance                           | -25 °C for 96 hours  | Contact Resistance: 10 milliohm max (change from initial)  |
|   |  | Shell Resistance: <b>50</b> milliohm max (change from initial)   |
| Resistance to Solder<br>Heat              | Dip connector solder tails to board for 10 seconds<br>Solder Temp = 260 +/- 5 °C                         | No visual damage to insulator  |
| Solderability                             | Per MIL-STD-202, Method 208  | 95% minimum coverage   |
| Electrostatic Discharge                   | Test unmated from 1 kV to 8 kV in 1 kV steps using 8mm ballprobe per IEC 801-2                           | No evidence of discharge to any of the 34 contacts   |

|    | F             | REVISE ON PC ONLY      |  | TITLE MicroCross™ - EVC and P&D I/O Plug and Receptacle |                       |     |             |       |
|----|---------------|------------------------|--|---|-----------------------|-----|-------------|-------|
|    | F SEE SHEET 1 |                        |  |   | I/O Plug ar<br>Connec |     |             |       |
|    | REV           | DESCRIPTION            | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |   |                       |     |             |       |
| DO | CUMENT        | NO.                    |  |   |                       | T   | FILE NAME   | SHEET |
|    |               | PS-71182               |  |   |                       |     | PS71182.SAM | 14    |
|    |               | ES-40000-3996 REV. A S | HEET 4   | 95/MAR/10   | EC U5-0926            | DCE | BRD03.SAM   |       |





LANGUAGE ENGLISH

### 6.0 Packaging

6.1 Receptacles:

All receptacles are packaged in trays. Refer to appropriate sales drawings for specific packaging information.

6.2 Plugs:

Plug components are packaged separately. Sticks are packaged in trays, groundplanes are on reels, and all other components are packaged in boxes. Refer to appropriate sales drawings for specific packaging information.

- 7.0 Gages and Fixtures
- 8.0 Other Information
  - 8.1 Test Sequences


|    | R        | EVISE ON PC ONLY     | TITLE          | ···   |                     |       |  |  |
|----|----------|----------------------|----------------|---|---------------------|-------|--|--|
|    | F        | F SEE SHEET 1        |                | I/O Plug and Receptacle<br>Connector System               |                     |       |  |  |
|    |          |                      | THIS DOCUMEN   | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO |                     |       |  |  |
|    | REV      | DESCRIPTION          | MOLEX INC. AND | SHOULD NOT BE USED WIT                                    | THOUT WRITTEN PERMI | SSION |  |  |
| DO | CUMENT N | 0.                   |                |   | FILE NAME           | SHEET |  |  |
|    | _        | PS-71182             |                |   | PS71182.SAM         | 15    |  |  |
|    |          | ES-40000-3996 REV. A | SHEET 4 95/MAR | /10 EC U5-0926 E  | DCBRD03.SAM         |       |  |  |





LANGUAGE ENGLISH

### Group 1: Mated Environmental




|     | REVISE ON PC ONLY |                        | TITLE MicroCross™ - EVC and P&D I/O Plug and Receptacle Connector System |              |               |                        |       |
|-----|-------------------|------------------------|--|--------------|---------------|------------------------|-------|
|     | F SEE SHEET 1     |                        |  |              |               |                        |       |
|     |                   |                        | _  |              |               | ION THAT IS PROPRIETAR |       |
|     | REV               | DESCRIPTION            | MOLEX  | NC. AND SHOU | D NOT BE USED | WITHOUT WRITTEN PERM   | SSION |
| DOC | CUMENT            | NO.                    |  |              |               | FILE NAME              | SHEET |
|     |                   | PS-71182               |  |              |               | PS71182.SAM            | 16    |
|     |                   | ES-40000-3996 REV. A S | HEET 4   | 95/MAR/10    | EC U5-0926    | DCBRD03.SAM            |       |





LANGUAGE ENGLISH

Group 2: Unmated Environmental



|     |               | REVISE ON PC ONLY      | TITLE          |                      | - EVC and P&D               |         |
|-----|---------------|------------------------|----------------|----------------------|-----------------------------|---------|
|     | F SEE SHEET 1 |                        |                |                      | id Receptacle<br>tor System |         |
|     | REV           | DESCRIPTION            |                |                      | TION THAT IS PROPRIETAR     |         |
|     | KEV           | DESCRIPTION            | MOLEX INC. AND | SHOOLD NOT BE USED ( | WITHOUT WRITTEN PERIVI      | 1331014 |
| DOC | CUMENT        | NO.                    |                |                      | FILE NAME                   | SHEET   |
|     |               | PS-71182               |                |                      | PS71182.SAM                 | 17      |
|     |               | ES-40000-3996 REV. A S | HEET 4 95/MAR  | /10 EC U5-0926       | DCBRD03.SAM                 |         |






LANGUAGE

**ENGLISH** 

### Group 3: Corrosive Environment




|     | F        | REVISE ON PC ONLY    | TITLE          | ,                         |                      |       |  |  |  |  |
|-----|----------|----------------------|----------------|---------------------------|----------------------|-------|--|--|--|--|
|     | F        | SEE SHEET 1          |                | I/O Plug and<br>Connector |                      |       |  |  |  |  |
|     |          |                      | THIS DOCUME    | NT CONTAINS INFORMATIO    | N THAT IS PROPRIETAR | Y TO  |  |  |  |  |
|     | REV      | DESCRIPTION          | MOLEX INC. AND | SHOULD NOT BE USED WI     | THOUT WRITTEN PERMI  | SSION |  |  |  |  |
| DOC | CUMENT I | NO.                  |                |                           | FILE NAME            | SHEET |  |  |  |  |
|     |          | PS-71182             |                |                           | PS71182.SAM          | 18    |  |  |  |  |
|     |          | ES-40000-3996 REV. A | SHEET 4 95/MA  | R/10 EC U5-0926 I         | DCBRD03.SAM          |       |  |  |  |  |





LANGUAGE ENGLISH

Group 4: Mated Mechanical




|    |        | REVISE ON PC ONLY       | TITLE     |            | MicroCross™           |        |                   |       |
|----|--------|-------------------------|-----------|------------|-----------------------|--------|-------------------|-------|
|    | F      | SEE SHEET 1             |           |            | I/O Plug ar<br>Connec |        |                   |       |
|    |        |                         | THIS DOO  | UMENT CO   | NTAINS INFORMAT       | TION T | HAT IS PROPRIETAR | Y TO  |
| L  | REV    | DESCRIPTION             | MOLEX INC | . AND SHOU | LD NOT BE USED        | WITH   | OUT WRITTEN PERMI | SSION |
| DO | CUMENT | NO.                     |           |            |                       |        | FILE NAME         | SHEET |
|    |        | PS-71182                |           |            |                       |        | PS71182.SAM       | 19    |
|    |        | ES-40000-3996 REV. A SI | HEET 4 95 | /MAR/10    | EC U5-0926            | DC     | BRD03.SAM         |       |





LANGUAGE ENGLISH

## Group 5: Mechanical Mate / Unmate Forces




|    | F        | REVISE ON PC ONLY      | TITLE    |              |                       |       |                                       |        |  |  |
|----|----------|------------------------|----------|--------------|-----------------------|-------|---------------------------------------|--------|--|--|
|    | F        | F SEE SHEET 1          |          |              | I/O Plug ar<br>Connec |       |                                       |        |  |  |
|    | REV      | DECOURTION             |          |              |                       |       | HAT IS PROPRIETAR<br>UT WRITTEN PERMI |        |  |  |
|    | L KEV    | DESCRIPTION            | MOLEXING | J. AND SHOUL | ים אסו פב טאבט י      | WITHO | UI WKII IEN PERIVI                    | 331014 |  |  |
| DO | CUMENT I | NO.                    |          |              |                       |       | FILE NAME                             | SHEET  |  |  |
|    |          | PS-71182               |          |              |                       |       | PS71182.SAM                           | 20     |  |  |
|    |          | ES-40000-3996 REV. A S | HEET 4 9 | 5/MAR/10     | EC U5-0926            | DCE   | BRD03.SAM                             |        |  |  |





LANGUAGE ENGLISH

# Group 6: Individual Contact Normal Forces



### Group 7: Miscellaneous Mechanical

RECEPTACLE PC BOARD INSERTION FORCES

CONTACT AND STICK RETENTION

RECEPTACLE THREAD TORQUE

CABLE PULL OUT FORCE


|    | RI        | EVISE ON PC ONLY     | TITLE          | · · · · · · · · · · · · · · · · · · ·       |                      |       |  |  |  |
|----|-----------|----------------------|----------------|---|----------------------|-------|--|--|--|
|    | F         | F SEE SHEET 1        |                | I/O Plug and Receptacle<br>Connector System |                      |       |  |  |  |
|    |           |                      | THIS DOCUME    | NT CONTAINS INFORMATIO                      | N THAT IS PROPRIETAR | Y TO  |  |  |  |
|    | REV       | DESCRIPTION          |                | SHOULD NOT BE USED WIT                      |                      |       |  |  |  |
| DO | CUMENT NO | Ο.                   |                |   | FILE NAME            | SHEET |  |  |  |
|    |           | PS-71182             |                |   | PS71182.SAM          | 21    |  |  |  |
|    |           | ES-40000-3996 REV. A | SHEET 4 95/MAI | R/10 EC U5-0926 [                           | DCBRD03.SAM          |       |  |  |  |






LANGUAGE ENGLISH

## Group 8: Insulator Integrity



### Group 9: Cable Flexing



|     |        | REVISE ON PC ONLY      | TITLE  |           |            | - EVC and P&D               |          |       |
|-----|--------|------------------------|--------|-----------|------------|-----------------------------|----------|-------|
|     | F      | SEE SHEET 1            |        |           |            | nd Receptacle<br>tor System |          |       |
|     | REV    | DESCRIPTION            |        |           |            | TION THAT IS PROP           |          |       |
| DOC | CUMENT | NO.                    |        |           |            | FILE NA                     | ME       | SHEET |
|     |        | PS-71182               |        |           |            | PS71182.                    | SAM      | 22    |
|     |        | ES-40000-3996 REV. A S | HEET 4 | 95/MAR/10 | EC U5-0926 | DCBRD03.SAI                 | <b>Л</b> |       |





LANGUAGE ENGLISH

Group 10: Miscellaneous Environmental

TEMPERATURE RISE

COLD RESISTANCE

SOLDERABILITY

RESISTANCE TO SOLDER HEAT

ELECTROSTATIC DISCHARGE

|    |        | REVISE ON PC ONLY      | TITLE                                       | MicroCross™ - E                                    |             |       |  |  |
|----|--------|------------------------|---|--|-------------|-------|--|--|
|    | F      | SEE SHEET 1            | I/O Plug and Receptacle<br>Connector System |  |             |       |  |  |
|    | REV    | DESCRIPTION            |   | NT CONTAINS INFORMATION<br>SHOULD NOT BE USED WITH |             |       |  |  |
| DO | CUMENT | NO.                    |   |  | FILE NAME   | SHEET |  |  |
|    |        | PS-71182               |   |  | PS71182.SAM | 23    |  |  |
|    |        | ES-40000-3996 REV. A S | HEET 4 95/MAP                               | R/10 EC U5-0926 D                                  | CBRD03.SAM  |       |  |  |

### I. SCOPE

### I.I Content

This specification covers the requirements of weld and solder terminations for EVC cable assemblies.

# 1.2 Reference Specifications

ES-79170-0001\_\_\_ "An Introduction To Resistance Welding For Wire Termination"

PS-71754-9999\_\_\_ "Application Specification - EVC Plug Cable Assemblies"

SMES-152 \_\_\_\_ "Solderability Specifications"

For application tooling requirements, refer to the Molex Operating and Service Manual included with Molex Application Tools

# 2. REQUIREMENTS:

### 2.1 Cable

ES-71754-9998

Cable shall conform to Molex Specifications E-73716-001, E-73716-002, E-73716-003, and E-73716-004 where applicable.


Note: Contact Molex for all other cables.

| DRWG. NO. |   |  |   |   |   |   |   |   |     |     |     | R         |             | CE I |    |  |  |  |   |  |  | DRWG.NO7 |
|-----------|---|--|---|---|---|---|---|---|-----|-----|-----|-----------|-------------|------|----|--|--|--|---|--|--|----------|
| ¦         | REV.  | В  | В | В | А | В | Α | Α | Α   | А   | В   |           |             |      |    |  |  |  | Γ |  |  | 75,      |
|           | SHT.  | 1  | 2 | 3 | 4 | 5 | 6 | 7 | 8   | 9   | 10  |           |             |      |    |  |  |  |   |  |  | 4-9      |
|           |   | S71754.S01 \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ |   |   |   |   |   |   |     | TEM | REV | <b>'.</b> | E           | }    | 99 |  |  |  |   |  |  |          |
|           | THIS DRAWING CONTAINS INFORMATION THAT IS PROPIETARY TO MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION. |  |   |   |   |   |   |   | SHT |     | OF  | 10        | $^{\infty}$ |      |    |  |  |  |   |  |  |          |




### 3. TERMINATION PROCEDURES

3.1 Wire Stripping Detail 28 and 30 AWG - Finished Strip Length



- (i) Conductors must be tightly wound
- (ii) Nicking of conductors is NOT acceptable

# 3.2 Welding/Soldering Detail of .075 Inch & Contacts






### 3. TERMINATION PROCEDURES (Cont'd)


3.3 Soldering procedure (Microcross only)

Coaxial Microcross Wire Stripping Detail - Finished Strip Lenath.



# 3.4 Assembly procedure (.050 pitch Microcross)


A. Orient stripped coaxialwire in pre-formed ground plane. Form ground blade enough to retain wire.



## 3. TERMINATION PROCEDURES (Cont'd)

## 3.5 Soldering Braid to Ground Detail

A. Using the chart below, solder the braid to the ground blade through each slot. The solder bead should be greater than 180 degrees around the perimeter of the form. The bead should be contained within the slot.



## Note:

I. Solder heat should be sufficient enough to provide a good solder fillet between ground blade and braid, but no scorching of dielectric is allowed. Do not apply solder iron tip directly on braid.

| DE SE |                          | Soldering Par   | ameters  |      |   | DRWG.   |
|-------|--------------------------|---|--|------|---|---------|
| ES.   |                          | Temperature   | 675° F. MAX                                    |      |   | KG. NO. |
| -7    |                          | Dwell Time  | II SECONDS MAX/                                | SLOT |   | 5-7     |
| 175   | REV.                     | Applied Solder Volume   | T.B.D.   |      |   | 1754    |
| 4-9   | SHT.                     |   |  |      |   | 4-9     |
| 99    | FILE NAME<br>ES71754.S04 | V = Ø REVISE  | ONLY ON CAD SYSTEM                             | REV. | Α | 99      |
| 8     |                          | THIS DRAWING CONTAINS INFORMATION MOLEX INC. AND SHOULD NOT BE USED WIT | THAT IS PROPIETARY TO HOUT WRITTEN PERMISSION. | SHT. | 4 | 8       |



LISLE, ILL.


MOLEX INCORPORATED 60532 U.S.A.

# TERMINATION SPECIFICATION EVC CABLE ASSEMBLIES

# 3. TERMINATION PROCEDURES (Cont'd)

# 3.6 Soldering Ground Blade Sub-Assembly Signals


A. Assemble ground blade to .050 pitch contact stick. Solder coaxial signals to top of corresponding signal contact tail.



| E3-11154-9 | REV.        | REFERENCE DOCUMEN<br>NON - CONTROLLED   | T    |   | DRWG.NO.<br>ES-71754-9 |
|------------|-------------|---|------|---|------------------------|
| 6 A        | ES71754.S05 | ♥=0 REVISE ONLY ON CAD SYSTEM   | REV. | В | 999                    |
| α          |             | THIS DRAWING CONTAINS INFORMATION THAT IS PROPIETARY TO MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION. | SHT. | 5 | 8                      |

### 4. WELD INSPECTION CRITERIA

- 4.1 There must be no visible separation between the conductors and the contacts.
- 4.2 The conductor must be centered on the contacts. Alignment between the conductor and the contact must be within 10°. Any portion of the conductors extending beyond a .005" boundary of each edge of the contact, is cause for rejection.



- 4.3 The conductor must not be smashed onto the contact. The overall diameter of the conductor bundle after termination should be at least 60% of the original diameter.
- 4.4 The finished weld should be free of deep electrode indentations, electrode deposits, pits, cracks, strand separation or abnormal discoloration around the weld.

NOTE: Surface appearance is not always a good indicator of weld quality. Insufficient heating or inadequate penetration, for example, usually leave no visible effects on the work piece.

4.5 Cracks, spitting (forcible ejection of material from the weld), and voids are not permitted.

DRWG, NO. ES-71754-9998 -71754-9998 **REFERENCE DOCUMENT** REV. NON - CONTROLLED SHT. FILE NAME ES71754.506 REVISE ONLY ON CAD SYSTEM REV. THIS DRAWING CONTAINS INFORMATION THAT IS PROPIETARY TO MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION. SHT.

# 4. WELD INSPECTION CRITERIA (Cont'd)

- 4.6 Spikes on the top surface of the wire (evidence of "tip pickup" or welding of the electrode) are cause for rejection.
- 4.7 PEEL TEST
  The peelstrength of each conductor bundle must be greater than 75% of the tensile strength of the undisturbed bundle.

$$A_p - (3 \times S_d) \ge 0.75 \times T_w$$


where:

 $A_p$  = the average peeltest value

 $S_d$  = the standard deviation of these values

Tw = the tensile strength of the wire


i.e. The mean tensile strength of the samples must be at least 3 standard deviations greater than 75% of the wire's original tensile strength.



MOLEX INCORPORATED U.S.A.

# TERMINATION SPECIFICATION EVC CABLE ASSEMBLIES


## 4. WELD INSPECTION CRITERIA (Cont'd)





# 5. SOLDER INSPECTION CRITERIA

5.1 Inpect solder joints per Molex Specification SMES-152.





MOLEX INCORPORATED LISLE, ILL. 60532 U.S.A.

# TERMINATION SPECIFICATION EVC CABLE ASSEMBLIES

| А | 07/05/96 | РАМ | FIRST RELEASE U70012    |
|---|----------|-----|-------------------------|
| В | 97/03/05 | BMS | REVISED PER EC # U70490 |
|   |          |     |                         |
|   |          |     |                         |

REFERENCE DOCUMENT

| DRWG. NO.<br>ES- |             |                               |   | NON - CON                                       | TROLLEC | )        | DRWG, NO.   |
|------------------|-------------|-------------------------------|---|---|---------|----------|-------------|
| 7                | ļ<br>————   |                               |   | DRAWN BY  | MURPH   | <u> </u> | 1-7         |
| 754              | REV.        |                               |   | APPROVED BY                                     | NELLIG  | AN       | 75          |
| 9-1              | SHT.        |                               |   | DATE  | 12/12/9 | 95       | 4-9         |
| 998              | ES71754.S10 | <b>♥</b> = 0 <b>▼</b> :       | = ∅ REVISE O  | NLY ON CAD SYSTE                                | M REV.  | В        | 999         |
| 8                |             | THIS DRAWIN<br>MOLEX INC. AND | NG CONTAINS INFORMATION THE SHOULD NOT BE USED WITHOU | HAT IS PROPIETARY TO<br>DUT WRITTEN PERMISSION. | SHT.    | 10       | $^{\infty}$ |





LANGUAGE

**ENGLISH** 

### SOLDERABILITY SPECIFICATIONS

#### 1.0 SCOPE

This standard covers the dip and meniscograph solderability test methods and performance requirements of Preplated material used in the fabrication of terminals, and Preplated and Postplated terminals intended for soldering into plated or etched electrical circuits by automatic equipment.

#### 2.0 PURPOSE

To establish standard test method and evaluation procedures for determining the ability of plated surfaces to accept molten solder. An accelerated aging sequence is included to simulate a minimum of 6 months natural aging under a combination of various storage conditions that have different deleterious effects.

### 3.0 REFERENCE DOCUMENTS

ANSI/J-STD-002

Solderability Tests for Component Leads, Terminations,

Lugs, Terminals and Wires

ASTM-B545

Electrodeposited Coatings of Tin

EIA-364 TP-52

EIA-364 TP-52 Test Procedures for Solderability of Contact

Terminations Use in Connector/Sockets

FED SPEC QQ-S-571

"Solder; Tin Alloy; Tin-Lead Alloy; and Lead Alloy"

IEC-68-2-20

Basic Environmental Testing Procedures

Part T: Soldering Part 2: Tests

JIS-C-0050

Basic Environmental Testing Procedures

Part 2: Tests

Part T: Soldering

MIL-F-14256

"Flux, Soldering, Liquid (Rosin Base)"

MIL-STD-202

Method 208 Solderability

MIL-STD-883 MIL-STD-883 Method 2003 Solderability Method 2022 Meniscograph Solderability

[A summary comparison of worldwide solderability specifications appears in Appendix A.]

|     | REV                   | В            |           |             |              |                 |                  |                   |            | ╛   |
|-----|-----------------------|--------------|-----------|-------------|--------------|-----------------|------------------|-------------------|------------|-----|
|     | SHT                   | 1-13         |           |             |              |                 |                  |                   |            |     |
|     | REVISE ON PC ONLY     |              |           | TITLE       | SOLDERAE     | BILITY SPEC     | FICATIONS        |                   |            |     |
|     |                       | Revised      |           | ed          |              |                 |                  |                   |            | Q/  |
|     | В                     | B ECN# U4-03 | -0368     |             |              |                 |                  |                   | <u>_</u> 9 |     |
|     |                       |              | 94/06/15  | JEL         | THIS DOCK    | JMENT CONTAINS  | INFORMATION TH   | AT IS PROPRIETARY | ′TO        |     |
|     | REV                   |              | DESCRIP   | TION        | MOLEX INC.   | AND SHOULD NO   | T BE USED WITHOU | JT WRITTEN PERMIS | SSION      | _   |
|     | DES                   | IGN CON      | TROL      | STATUS      | WRITTEN BY:  | CHECKED BY:     | APPROVED BY:     | Date: YR / MO     | / DAY      |     |
|     | International-Lisie M |              | J. Lopata | J. Lopata   | B. Cronin    | 93 / 05         | / 06             |                   |            |     |
| DOC | CUMENT                | NO.          |           |             |              |                 |                  | FILE NAME         | SHT        | NO. |
|     | SMES-152              |              |           |             |              |                 | ES1521           | 1 0               | F 13       |     |
|     |                       |              | BORDI     | ER FILENAME | : DCBRD05.WI | K1 [40000 - 399 | 7] REV.A PAGE    | 5                 |            |     |





LANGUAGE

**ENGLISH** 

### 4.0 DEFINITIONS

### 4.1 SOLDERABILITY

The property of metal to be wetted by solder.

### 4.2 SPECIMEN

Component under evaluation.

### 4.3 WETTING

A condition whereby a relatively uniform, smooth, unbroken and adherent film of solder has formed to the surface tested.

### 4.4 POROSITY

A condition of a solder coating with a spongy and uneven surface appearance that may contain a concentration of small pinholes and pits. See Figure 2.

### 4.5 NON WETTING

A condition whereby a surface has contacted molten solder, but the solder has not adhered to all of the surface; surface tested remains exposed. See Figure 3.

### 4.6 PIN HOLES

Small holes occurring as imperfections that penetrate entirely through the solder layer See Figure 4.

### 4.7 DEWETTING

A condition whereby the molten solder has coated the surface tested and then receded leaving irregularly shaped mounds of solder separated by areas covered with a thin solder film; base metal is not exposed. See Figure 5.

### 4.8 FOREIGN MATERIAL

A lumpy, irregular coating which has covered, or partially covered, particles of material located on, but different than, the specimen material or coating. See Figure 6.

|    | REVISE ON PC ONLY |               | TITLE  | SOLDERABILITY SPECIFI             | CATIONS         | <del></del> |              |
|----|-------------------|---------------|--|-----------------------------------|-----------------|-------------|--------------|
|    | В                 | SEE SHEET 1   |  |                                   |                 |             | Q            |
|    |                   | ·             | THIS   | DOCUMENT CONTAINS INFORMATION THA | TIS PROPRIETARY | TO          | 90           |
|    | REV DESCRIPTION   |               | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |                                   |                 |             | <b>'</b> i   |
| DC | CUMENT            | NO.           |  |                                   | FILE NAME       | SHEE        | <del>-</del> |
| ł  | SMES-152          |               | 1  |                                   |                 | SHEE        | 1            |
|    |                   | <del></del>   |  |                                   | ES1522          | 2           |              |
|    |                   | · BORDER FILE | VAME: DCBR   | 006.WK1 [40000 - 3997] REV A PAG  | Ee              |             |              |





LANGUAGE

**ENGLISH** 

#### 5.1 EQUIPMENT

#### 5.1.1 SOLDER POT

A solder pot of sufficient size to contain at least 1000 grams of solder shall be used. The apparatus shall be capable of maintaining the solder at the temperature specified in 5.3.4.

### 5.1.2 SOLDER MENISCUS FORCE MEASURING DEVICE (MENISCOGRAPH)

A solder meniscus force measuring device, meniscograph, which includes a temperature controlled solder pot containing approximately 750 grams of solder shall be used. This apparatus shall be capable of maintaining the solder at the temperature specified in 5.3.4. The meniscograph apparatus also includes a strip chart recorder which records the force curve for the specimen tested.

#### 5.1.3 DIPPING DEVICE

A mechanical dipping device capable of controlling the rates and angle of immersion of the specimen, and providing a dwell time (time of total immersion to the required depth) in the solder bath as specified in 5.3.4 shall be used.

A mechanical dipping device is incorporated in the meniscograph, and is preset to produce an immersion and removal rate as specified in 5.3.4. The specimen dwell time is operator controlled to the time specified in 5.3.4.

#### 5.1.4 OPTICAL EQUIPMENT

An optical system capable of providing magnification between 10X and 20X shall be used.

### 5.1.5 CONTAINER AND COVER

A nonmetallic container of sufficient size to allow the suspension of the specimens 38mm (1.5 inches) above the boiling distilled water shall be used (a 2,000ml beaker is one size that has been used satisfactorily for smaller components). The cover shall be one or more stainless steel plates and shall be capable of covering approximately 7/8ths (88%) of the open area of the container so that a more constant temperature may be obtained. A suitable method of suspending the specimens shall be improvised. Perforations or slots in the plates are permitted for this purpose.

|    | REVISE ON PC ONLY |             | TITLE      | SOLDERABILITY SPECIFICATIONS                           |       |          |
|----|-------------------|-------------|------------|--|-------|----------|
|    | В                 | SEE SHEET 1 |            |  | (     | S        |
|    |                   |             | THIS       | DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO   | )     | P        |
|    | REV               | DESCRIPTION | MOLE       | ( INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSK | INC   | <u> </u> |
| DC | CUMENT            | NO.         |            | FILE NAME  | SHEET | Γ        |
|    | SMES-152          |             |            | ES1523   | 3     |          |
|    |                   | BORDER FILE | NAME: DCBF | RD06.WK1 [40000-3997] REV.A PAGE 6                     |       |          |





LANGUAGE

ENGLISH

### 5.2 MATERIALS

#### 5.2.1 FLUX

The flux shall conform to type R or RMA of MIL-F-14256, "Flux, Soldering, Liquid (Rosin Base)".

# 5.2.1.1 TYPE R (NON-ACTIVATED) Used for postplated product.

# 5.2.1.2 TYPE RMA (MILDLY—ACTIVATED)

Used for preplated product with bare edges.

#### 5.2.2 SOLDER

The solder shall conform to type S, composition Sn60 or Sn63, of Federal Specification QQ-S-571, "Solder; Tin Alloy; Lead-Tin Alloy; and Lead Alloy".

### 5.3 PROCEDURE

The test procedure shall be performed on a number of terminations. During handling, care shall be exercised to prevent the surface to the tested from being abraded or contaminated by grease, perspirants, etc. The test procedure shall consist of the following operations:

- a. Proper preparation of the terminations, see 5.3.1.
- b. Aging of specimens, see 5.3.2 and Table 1.
- c. Application of flux and immersion of the terminations into molten solder and solder temperatures, see 5.3.3 and 5.3.4.
- d. Examination of the tested portions of the terminations upon completion of the solder dip process, see 5.4.1 or interpretation of the recordings upon completion of the meniscograph solder dip process, see 5.4.2.

|    | REVISE ON PC ONLY |             | TITLE      | SOLDERABILITY SPEC                 | IFICATIONS          |       |
|----|-------------------|-------------|------------|------------------------------------|---------------------|-------|
|    | В                 | SEE SHEET 1 |            |                                    |                     |       |
|    |                   |             | THIS       | DOCUMENT CONTAINS INFORMATION      | THAT IS PROPRIETARY | то    |
|    | REV               | DESCRIPTION | MOLE       | K INC. AND SHOULD NOT BE USED WITH | HOUT WRITTEN PERMIS |       |
| DC | CUMENT            | NO.         |            |                                    | FILE NAME           | SHEET |
|    | S                 | MES-152     |            |                                    | ES1524              | 4     |
|    |                   | BORDER EILE | NAME: DORE | RD06 WK1 [40000 - 3997] REV.A [    | PAGE 6              |       |

# molex

### **ENGINEERING STANDARD**

molex

LANGUAGE ENGLISH

5.3.1 PREPARATION OF TERMINATIONS

No wiping, cleaning, scraping or abrasive cleaning of the terminations shall be performed. Any special preparation of the terminations, such as bending or re-orientation prior to the test, shall be specified.

#### 5.3.2 AGING

### 5.3.2.1 STEAM

Prior to the application of flux and subsequent solder dips, specimens assigned to Categories 2 or 3 shall be subjected to aging exposure of the surfaces to steam in the container specified in 5.1.5. The specimens shall be suspended so that no portion of the specimen is less than 38mm (1.5 inches) above the boiling distilled water with the cover specified in 5.1.5. See Table 1 for categories and duration of steam exposure. If necessary, additional hot distilled water may be gradually added in small quantities so that the water will continue to boil and the temperature will remain essentially constant.

#### 5.3.2.2 DRY HEAT

Prior to the application of flux and subsequent solder dips, specimens assigned to Category 4 shall be subjected to aging exposure in at 155  $\pm$  5°C dry heat. See Table 1 for duration of dry heat exposure.

#### 5.3.3 APPLICATION OF FLUX

Flux, type R or RMA, shall be used as specified in 5.2.1. Specimens shall be immersed in the flux which is at room ambient temperature, to the minimum depth necessary to cover the surface to be tested. The specimens shall be immersed in the flux for a period of 5 to 10 seconds.

|    | RE                                     | EVISE ON PC ONLY | TITLE     | SOLDERABILITY SPECIFICATIONS                              |                 |
|----|--|------------------|-----------|---|-----------------|
|    | В                                      | SEE SHEET 1      |           | ·   | \(\mathcal{U}\) |
|    |  |                  | THIS      | S DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO    | P               |
|    | REV                                    | DESCRIPTION      | MOLE      | EX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |                 |
| DO | DOCUMENT NO.                           |                  |           | FILE NAME SI  | HEET            |
|    | SI                                     | MES-152          |           | ES1525  | 5               |
|    | ······································ | BORDER FILEN     | NAME: DCB | RD06,WK1 [40000-3997] REV.A PAGE 6                        |                 |



}

# **ENGINEERING STANDARD**

molex

LANGUAGE

**ENGLISH** 

# TABLE 1: AGING CATEGORIES FOR COMPONENT LEADS AND TERMINATIONS

Category 1: No Steam Aging Requirements

Minimum Coating Durability

Intended for surfaces which will be soldered within a short period of time (e.g. up to 6 months) from the time of testing and are likely to experience a minimum of thermal exposures prior to soldering (see below).

Category 2: 1 Hour ± 5 Minutes Steam Aging

Typical Coating Durability (for non-tin and non-tin lead finishes) Intended for surfaces finished with other than Sn or Sn/Pb coatings which will be soldered after an extended time from the time of testing and which may see limited thermal exposures prior to soldering (see below).

Category 3: 8 Hours ± 15 Minutes Steam Aging

Typical Coating Durability (default for tin and tin-lead finishes) Intended for surfaces finished with Sn or Sn/Pb coatings which will be soldered after an extended storage (e.g. greater than 4 months) from the time of testing and/or which see multiple thermal exposures prior to soldering (see below).

Category 4: 16 Hours ± 15 Minutes Dry Heat

Intended for surafces finished with Sn or Sn/Pb coatings which will be soldered after an extended time from the time of testing and which may see limited thermal exposure prior to soldering.

The accelerated steam aging of solderable coatings has been, and continues to be, the subject of intense investigation. Compared to other aging methods, steam aging satisfactorily accelerates the degradation of tin and tin/lead surfaces in a manner similar to natural aging. The degradation mechanisms of surface oxidation and Cu-Sn intermetallic growth are both enhanced by the heat and humidity of steam. Properly applied tin and tin-lead coatings can withstand the steam aging environment well beyond the 8 hours specified and may survive natural aging well beyond 12 months. Due to the combined effects of specific geometry, storage environment, and material systems, it is not possible to accurately predict storage life. As a result, this specification indicates a storage life overlap for coating durability Category 1 and Category 3, and an open ended limit for coating durability Category 3. For coatings other than tin or tin-lead, Category 2 data does not exist to support steam aging longer than the 1 hour specified.

Humidity aged samples experience a primary aging mechanism of both oxidation of the Sn/Pb surface and  $\mathrm{Cu_6Sn_5}$  intermetallic growth. The primary aging mechanism for dry aged samples tends to be only intermetallic growth.

|    | R                            | EVISE ON PC ONLY | TITLE SOLDERABILITY SPECIFICATIONS   |          |
|----|------------------------------|------------------|--|----------|
|    | В                            | SEE SHEET 1      |  | ( n      |
| DO | REV DESCRIPTION DOCUMENT NO. |                  | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION | <b>₩</b> |
|    |                              | MES-152          | FILE NAME SHE  | ΕT       |
|    |                              |                  | ES1526 6  AME: DCBRD06.WK1 [40000 – 3997] REV.A PAGE 6   |          |

molex

### **ENGINEERING STANDARD**



LANGUAGE

ENGLISH

### 5.3.4 SOLDER DIP

The dross and burned flux shall be skimmed from the surface of the molten solder as specified in 5.2.2 (may not require a separate operation in wave flow pots). The molten solder shall be maintained at a uniform temperature of  $245 \pm 5^{\circ}$ C. The surface of the molten solder shall be skimmed again just prior to immersing the specimens in the solder. The parts shall be attached to a dipping device (see 5.1.3) and the flux—covered specimen immersed ONCE in molten solder to the same depth and the same manner as described in 5.3.3. The immersion and removal rates shall be  $25 \pm 6$  mm/sec (1  $\pm$  .25 inch per second) and the dwell time in the solder bath shall be  $5 \pm 0.5$  seconds, unless otherwise specified. After the dipping process, the part shall be allowed to cool in air. Residual flux shall be removed from the specimen by rinsing in isopropyl alcohol. If necessary, a soft damp cloth or cotton swab moistened with clean 91% isopropyl alcohol shall be used to remove all remaining flux.

#### 5.3.5 EXAMINATION OF SPECIMENS

After each dip coated specimen has been thoroughly cleaned of flux, the entire specimen shall be examined using a magnification between 10X and 20X, see 5.1.4.

#### 5.4 FAILURE CRITERIA

#### 5.4.1 SOLDER DIP METHOD

The criteria for acceptable solderability during evaluation of the specimen are:

- a. The total surface area of the dipped part of the specimen is at least 95% wetted.
- b. That pinholes, voids, porosity, nonwetting or dewetting are not concentrated in one area and do not exceed 5% of the total metallized area.
- c. That there shall be no solder bridging between any metallized area and any other metallized area not connected to it by design. In the event that the solder dipping has caused bridging, the test shall be considered a failure provided that a local application of heat (i.e. gas, soldering iron or redipping) results in solder pullback and no wetting of the dielectric area as indicated by microscopic examinations at a magnification of between 10X and 20X.

The area of the surface to be tested as specified in 5.3.3 shall include all sides of the specimen surface. In case of dispute, the percentage of coverage with pin holes or voids shall be determined by actual measurement of these areas, as compared to the total area.

d. New solder should not be easily lifted nor peeled from the surface of the tested sample with a razor blade.

|    | RE     | VISE ON PC ONLY | TITLE      | SOLDERABILITY SPECIFICATIONS                         | _                           |
|----|--------|-----------------|------------|--|-----------------------------|
|    | В      | SEE SHEET 1     |            |  | $\mathcal{J}_{\mathcal{I}}$ |
| Ì  |        | 022 01.221      |            | DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY T  |                             |
|    | REV    | DESCRIPTION     | MOLE       | KINC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISS | SION                        |
| DC | CUMENT | NO.             |            | FILE NAME  | SHEET                       |
|    | S      | MES-152         |            | ES1527   | 7                           |
|    |        | BORDER FILE     | VAME: DCBF | RD06.WK1 [40000-3997] REV.A PAGE 6                   |                             |



\_\_\_\_\_

LANGUAGE


ENGLISH

### 5.4.2 MENISCOGRAPH

The criteria for acceptable solderability using the Meniscograph has not been established. This method should be used for evaluation only.

### 5.4.2.1 MENISCOGRAPH

The criteria for acceptable solderability during evaluation of the recordings are subject to much debate. Possible interpretations of the Meniscograph Curves are shown in Figure 1.



# TYPICAL WETTING CURVES FIGURE 1

### 5.4.3 VISUAL INSPECTION

To be used in conjunction with the meniscograph or to be used if the wetting curve was not generated, see 5.4.1.

|       | REVISE ON PC ONLY | TITLE SOLDERABILITY SPECIFICATIONS                           |   |       |  |  |
|-------|-------------------|--|---|-------|--|--|
| В     | SEE SHEET 1       |  |   | {     |  |  |
|       |                   | THIS DOCUM   | MENT CONTAINS INFORMATION THAT IS PROPRIETARY | то  9 |  |  |
| RE    | DESCRIPTION       | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |   |       |  |  |
| DOCUM | NT NO.            |  | FILE NAME                                     | SHEET |  |  |
|       | SMES-152          | ES1528   |   |       |  |  |

| ma | lav |
|----|-----|
| ЩO | IQV |
|    | /   |



LANGUAGE

**ENGLISH** 

# 6.0 DETAILS TO BE SPECIFIED

The following information must be specified on the Engineering drawings:

- a. Area of examination
- b. Flux used (if other than Type R)
- c. Immersion time in solder (if other than 5.0±0.5 secs)
- d. Aging Category (if other than Category 1)
- e. Solder temperature (if other than 245°±5°C)
- f. Pass/fail criteria (if other than specifications listed in 5.4)

|    | REVISE ON PC ONLY |              | TITLE     | SOLDERABILITY SPECIFIC              | ATIONS         | _     |
|----|-------------------|--------------|-----------|-------------------------------------|----------------|-------|
|    | B SEE SHEET 1     |              |           |                                     |                | 5     |
|    |                   |              |           | DOCUMENT CONTAINS INFORMATION THAT  |                |       |
|    | REV               | DESCRIPTION  | MOLEX     | INC. AND SHOULD NOT BE USED WITHOUT | WRITTEN PERMIS | SION  |
| DO | CUMENT            | NO.          |           | F                                   | ILE NAME       | SHEET |
|    | S                 | MES-152      |           |                                     | ES1529         | 9     |
|    |                   | BORDER FILEN | AME: DCBR | D06.WK1 [40000-3997] REV.A PAGE     | 6              |       |





LANGUAGE


**ENGLISH** 



POROSITY FIGURE 2



NONWETTING FIGURE 3



PINHOLES FIGURE 4



DEWETTING FIGURE 5



FOREIGN MATERIAL FIGURE 6

|         | REVISE ON PC ONLY |             | TITLE  | SOLDERABILITY SPECIFICATIONS                              |      |    |  |
|---------|-------------------|-------------|--|---|------|----|--|
|         | В                 | SEE SHEET 1 |  |   | •    | S  |  |
|         |                   |             | THIS   | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO |      |    |  |
|         | REV               | DESCRIPTION | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |   |      |    |  |
| DC      | DOCUMENT NO.      |             |  | FILE NAME   | SHEE | ET |  |
| <u></u> | SMES-152          |             |  | ES15210   | 10   | 1  |  |
|         |                   | BORDER FILE | VAME: DCBR   | D06.WK1 [40000-3997] REV.A PAGE 6                         |      |    |  |

molex

## **ENGINEERING STANDARD**

molex

LANGUAGE

ENGLISH

# APPENDIX A

|    | RE     | EVISE ON PC ONLY | TITLE      | SOLDERABILITY SPECIFICATIONS                           |         |
|----|--------|------------------|------------|--|---------|
|    | в      | SEE SHEET 1      |            |  | <u></u> |
|    |        |                  | THIS       | DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO   | Y       |
|    | REV    | DESCRIPTION      | MOLEX      | INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |         |
| DC | CUMENT | NO.              |            | FILE NAME  | SHEET   |
|    | S      | MES-152          |            | ES15211  | 11      |
|    |        | BORDER FILE      | NAME: DCBR | D06.WK1 [40000-3997] REV.A PAGE 6                      |         |

molex

# **ENGINEERING STANDARD**

molex

LANGUAGE

ENGLISH

|                       | SMES-152<br>Solderability<br>Rev. B  | MIL-STD-202<br>Method 208<br>Rev. G<br>Notice 93/7/12 | ILC-68-2-20<br>Solderability<br>Rev. 1992  | ANSI - J - STD - 002<br>Solderability<br>Rev. April 1992   |
|-----------------------|--|---|--|--|
| Flux Type             | NNL -F - 14256<br>Type R or RMA  | MIL-F-14256<br>Type R                                 | 25% Rosin in 75% isopropanal<br>or eltyl alcohol; Non-Activated<br>flux up to 0.5% chloride added.   | MIL-1-14256  Type R or RMA or Type LR3CN per IPC-51-818-25% WW rosin in solvent of 99% isopropyt alcohol with a specific gravity of 0.843+0.005 @ 25-C |
| Flux Owell            | 5-10 seconds   | 5-10 seconds  | Not Specified  | 5-10 seconds   |
| Flux Drain            | Not Specified  | 10 to 20 seconds                                      | 1 min 5 seconds  | 5-20 seconds   |
| Solder Type           | Sn60 or Sn63 Type S<br>Fed Spec 00-5-571   | Sn60 or Sn63 Type S<br>Fed Spec 00-S-571              | 59-61% Sn Containment List   | Sn60 or Sn63<br>Fed Spec (10-5-57)   |
| Solder<br>Temperature | 245.15.0   | 245·15·C  | 235·15·C   | 245·15·C   |
| Solder Dwell          | 5.0±0.5 seconds  | 5.0+0.5 seconds                                       | 2.0±0.5 seconds or<br>5.0±0.5 seconds or longer<br>based on thermat capacily   | 5.0 seconds or longer by agreement   |
| Immersion Rate        | 2516 mm/sec  | 25.6 mm/sec   | 25 <sup>1</sup> 2.5 mm/sec   | 2516 nm/sec  |
| Sleam Aging           | Calegory 1: None<br>Calegory 2: 1 hr±5 min<br>Calegory 3: 8 hrs±15 min.<br>Calegory 4: 16 hrs dry heal | 8 hrs:30 min  | None<br>Ageing 1a: 1 hr<br>Ageing 1b: 4 hrs<br>Ageing 2: 10 days SS humidity<br>Ageing 3: 16 hrs dry heat                                  | None<br>1 hr 5 min.<br>8 hrs 15 min.   |
| Failure Criteria      | 95% min new coverage.<br>5% max pintroles and<br>voids not in one concentrated<br>area.                | 5% max dewelled nonwelled or with pinholes            | Smooth and bright solder with<br>no more than small amounts of<br>pin holes, wetted, or dewetted<br>areas not in one concentrated<br>area. | 95% min new coverage anionalies other than pin holes, dewelling and norwelling are not cause for rejection.  |
| Rinse                 | Isopropyl Alcohol  | Isopropyl Alcohol                                     | Isopropanol or Ethyl Alcohol   | Isopropył Ak. ohol. Note on<br>Salety Data Sheel   |

|    | R               | EVISE ON PC ONLY | TITLE  | SOLDERABILITY SPECIFICATIONS                         |                 |  |  |
|----|-----------------|------------------|--|--|-----------------|--|--|
|    | В               | SEE SHEET 1      |  |  | \( \int \int \) |  |  |
|    |                 |                  | THIS   | DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO | رو              |  |  |
| L  | REV DESCRIPTION |                  | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |  |                 |  |  |
| DC | CUMENT          | NO.              |  | FILE NAME SH   | EET             |  |  |
|    | S               | MES-152          |  | ES15212  | 12              |  |  |
|    |                 | BORDER FILE      | NAME: DCBR   | RD06.WK1 [40000-3997] REV.A PAGE 6                   |                 |  |  |



# **ENGINEERING STANDARD**



LANGUAGE

ENGLISH

|                    | MIL-STD-883D<br>Method 2003.7   | ASTM B-678<br>Solderability<br>Rev. 1986   | EIA—364 TP—52<br>Solderability<br>Rev. Aug. 1993  | JIS-C-0050<br>Solderability<br>Rev. April 1992  |
|--------------------|---|--|---|---|
| Flux Type          | MIL - STD- 14256<br>Type R (RMA optional)   | 25 mass % WW rosin 99<br>mass% Isopropyl Alcohol<br>(mildly or activated if<br>specified)                                      | 25% WW rosin in 99% isopropyl 25% rosin in 75% isopropanal alcohol with a Specific Gravily or ethyl alcohol; non-activate of 0.838 0.005 Class 1: Type R Class 2: Type RA (Alpha 611) | 25% rosin in 75% isopropanal<br>or ettyl alcohol; non-activated<br>has up to 0.5% choloide added                        |
| Flux Dwell         | 5-10 seconds  | Nol Specified  | 5-10 seconds  | Not Specified   |
| Flux Orain         | 10-60 seconds   | 30-60 seconds  | 5-20 seconds  | 60+5 seconds  |
| Solder Type        | Sn60 or Sn63 1ype S<br>Fed Spec 00-5-571  | 60 mass % lin 40 mass %<br>lead (alloy grade 60A)  | 60/40 SnPb+Containment List   | 59-61% Sn Contaminant list<br>H60A, H60S, H63A per<br>JIS-7-3282  |
| Solder Temperature | 245·•5·C  | 245**5°C   | 245·+5·C  | 235 15 C  |
| Solder Dwell       | 5:0.5°C seconds or 7:0.5 seconds  | 5.0.5 seconds  | 4-5 seconds   | 2.0±0.5 seconds or<br>5.0±0.5 seconds or longer<br>based on thermal capacity  |
| Immersion Rate     | 25±5 mm/sec   | 2515 mm/sec  | 25·6 mm/sec   | 2512.5 mm/sec   |
| Steam Aging        | 8·0.5 hrs   | 24 hrs   | Calegory1: None<br>Calegory 2 - 1 hr15 min.<br>Calegory 3: 8 hrs15 min.<br>Calegory 4: 16 hrs11 hr.   | None<br>1 hr<br>4 hrs<br>10 days SS humidily<br>16 hrs dry heal   |
| Failure Criteria   | 95% new solder coating pinholes, voids, porosity, nonwelling or dewelling. 5% max lotal area. | Adherent, bright, smooth and uniform over at least 95% of tested area. 5% may contain pinholes, dewelted areas, and roughness. | 95% min new coverage pinholes acceptable but not concentrated in an area smaller than 5%, acceptable pinholes, dewetting, nonwetting  | Snooth and bright with no<br>more than small amount of<br>pinholes, wetled or dewetted<br>areas not concentrated in one |
| Rinse              | Isopropyi Alcohoi   | Isopropyl Alcohol  | _   | Isopropend or Ethyl Alcohol   |
|                    |   |  |   |   |

|    | F      | EVISE ON PC ONLY | TITLE      | SOLDERABILITY SPECIFICATIONS                     |         | 1  |
|----|--------|------------------|------------|--|---------|----|
|    | В      | SEE SHEET 1      |            |  |         | 5  |
|    |        |                  | THIS       | DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETAL | RY TO   | ته |
|    | REV    | DESCRIPTION      | MOLEX      | INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERM | IISSION | ļ. |
| DC | CUMENT | NO.              |            | FILE NAME  | SHEE    | T  |
|    | S      | MES-152          |            | ES15213  | 13      |    |
|    |        | BORDER FILEN     | VAME: DCBR | D06.WK1 [40000-3997] REV.A PAGE 6                |         |    |





LANGUAGE ENGLISH

#### 1.0 Scope

This specification covers the Molex MicroCross™ - Digital Visual Interface (DVI) system which includes cable plugs and board mount receptacles (Right Angle and Vertical).

The Digital Visual Interface connector system supports both analog and digital video transmission.

This specification covers the DVI cable to board, I/O connector system with requirements as set forth by Molex Incorporated.

#### 2.0 Product Description

The MicroCross™ DVI system is designed to meet the industry's requirements for analog and digital computer monitors. There are (2) different receptacle connectors which correspond to the video support present on the host system (mother board/graphics cards). The DVI-D (Digital) receptacle connector supports hosts systems that transmit digital video. The DVI-I (Intergrated) receptacle connector supports host systems that are enabled to transmit both analog and digital video. This is achieved by utilizing two different sets of contacts as shown in Figure 1 below:




Figure 1: Two sets of contacts (DVI-I Shown)

| П |     | REV             | G             | G        | G          | O    | G    | O    | G  | G                   | G     | G    | G     | G     | G    | G          | G            | G            | G          | G            | G         | G      | G             | G     |
|---|-----|-----------------|---------------|----------|------------|------|------|------|----|---------------------|-------|------|-------|-------|------|------------|--------------|--------------|------------|--------------|-----------|--------|---------------|-------|
|   |     | SHT             | 1             | 2        | 3          | 4    | 5    | 6    | 7  | 8                   | 9     | 10   | 11    | 12    | 13   | 14         | 15           | 16           | 17         | 18           | 19        | 20     | 21            | 22    |
|   |     |                 | REV           | ISE (    | ON P       | CO   | NLY  |      |    | TIT                 | LE    |      |       |       |      | Mic        | roC          | ross         | TM _       | - DV         | 1         |        |               | Ī     |
|   |     | G               | Р             |          | RE<br>C# U |      | 2001 |      | 2  |                     |       |      |       |       | I/C  | Piu<br>Cor | ig a<br>nned | nd F<br>ctor | Rec<br>Sys | epta<br>stem | icle<br>1 |        |               |       |
|   | ŀ   | DE) /           | V DESCRIPTION |          |            |      |      |      |    |                     |       |      |       |       |      |            |              |              | AT IS      |              |           |        | -             |       |
|   | ļ   | REV DESCRIPTION |               |          |            |      |      | IVIO |    | NC. A               | כ טאי | пооц | ח ועכ | אם וו | USE  | וואא ט     | HOU          | JT WF        | (IIIE      | NPE          | KIVIISS   | SION   |               |       |
| П | İ   | DESI            | GN C          | CON      | ΓRΟΙ       | -    | ST   | ΓΑΤι | JS | WRI                 | TTEN  | BY:  | CHE   | CKED  | BY:  | API        | PROV         | ED B         | Υ:         | DA.          | TE: Y     | /R/N   | /O / E        | DAY   |
| L |     |                 | UD            | <u>T</u> |            |      |      | М    |    | SCH                 | MID   | GA   | NEI   | LLIG  | AN   | 1          | VELS         | SON          |            |              | 99        | a / 07 | <u>/ / 05</u> |       |
|   | DOC | UMENT I         | NO.           |          |            |      |      |      |    |                     |       |      |       |       |      |            |              |              | F          | FILE         | NAM       | E      | SH            | IT NO |
|   |     | <u> </u>        | PS-           | 7432     | 0-00       | 1    |      |      |    | PS74320.LWP 1 OF 22 |       |      |       |       |      |            |              |              |            |              |           |        |               |       |
|   |     |                 | ES            | 3-400    | 000-3      | 3996 | RE   | V. A | SH | IEET                | 3 9   | 95/M | AR/1  | 0     | EC l | J5-09      | 926          | DC           | BR         | D03.         | SAM       |        |               |       |





LANGUAGE ENGLISH

1. General purpose signals:

Terminals: 24 circuits on a 0.075 inch/1.91 mm grid

Signals: Includes power, grounds, digital and video signals, analog synch lines and DDC

(Display Data Channel) signals.

| Pin | Signal Assignment       | Pin | Signal Assignment        | Pin | Signal Assignment        |
|-----|-------------------------|-----|--------------------------|-----|--------------------------|
| 1   | T.M.D.S. Data2-         | 9   | T.M.D.S. Data1-          | 17  | T.M.D.S. Data 0-         |
| 2   | T.M.D.S. Data2+         | 10  | T.M.D.S. Data1+          | 18  | T.M.D.S. Data 0+         |
| 3   | T.M.D.S. Data2/4 Shield | 11  | T.M.D.S. Data 1/3 Shield | 19  | T.M.D.S. Data 0/5 Shield |
| 4   | T.M.D.S. Data 4-        | 12  | T.M.D.S. Data 3-         | 20  | T.M.D.S. Data 5-         |
| 5   | T.M.D.S. Data 4+        | 13  | T.M.D.S. 3+              | 21  | T.M.D.S. Data 5+         |
| 6   | DDC Clock               | 14  | +5 V Power               | 22  | T.M.D.S. Clock Shield    |
| 7   | DDC Data                | 15  | Ground (for +5V)         | 23  | T.M.D.S. Clock+          |
| 8   | No Connect              | 16  | Hot Plug Detect          | 24  | T.M.D.S. Clock-          |

Table 1: Digital-Only Connector Pin Assignments
Source: Digital Visual Interface Specification, Revision 1.0

#### 2. MicroCross<sup>TM</sup>:

a) Plug and Receptacle - I - Intergrated analog/digital - see figure 3, sheet 4

Terminals: 4 circuits on a 0.100 inch/2.54 mm grid with a crossing ground plane in between.

Signals: High frequency, 75 ohm, analog video

b) Plug and Receptacle - D - Digital Version

Terminals: A single key on the plug and corresponding slot on the receptacle.

Signals: The key is used for mechanical polarization only, it does not carry any

electrical signals.

|     |        | REVISE ON PC ONLY      | TITLE MiroCross™ - DVI                                       |  |  |  |  |  |  |
|-----|--------|------------------------|--|--|--|--|--|--|--|
|     | G      | SEE SHEET 1            | I/O Plug and Receptacle<br>Connector System                  |  |  |  |  |  |  |
|     |        |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO    |  |  |  |  |  |  |
|     | REV    | DESCRIPTION            | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |  |  |  |  |  |  |
| DOC | CUMENT | NO.                    | FILE NAME SHEET  |  |  |  |  |  |  |
|     |        | PS-74320-001           | PS74320.LWP 2  |  |  |  |  |  |  |
|     |        | ES-40000-3996 REV. A S | SHEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM                     |  |  |  |  |  |  |





LANGUAGE ENGLISH

| Pin | Signal Assignment        | Pin | Signal Assignment                               | Pin | Signal Assignment        |
|-----|--------------------------|-----|---|-----|--------------------------|
| 1   | T.M.D.S. Data 2-         | 9   | T.M.D.S. Data 1-                                | 17  | T.M.D.S. Data 0-         |
| 2   | T.M.D.S. Data 2+         | 10  | T.M.D.S. Data 1+                                | 18  | T.M.D.S. Data 0+         |
| 3   | T.M.D.S. Data 2/4 Shield | 11  | T.M.D.S. Data 1/3 Shield                        | 19  | T.M.D.S. Data 0/5 Shield |
| 4   | T.M.D.S. Data 4-         | 12  | T.M.D.S. Data 3-                                | 20  | T.M.D.S. Data 5-         |
| 5   | T.M.D.S. Data 4+         | 13  | T.M.D.S. Data 3+                                | 21  | T.M.D.S. Data 5+         |
| 6   | DDC Clock                | 14  | +5V Power                                       | 22  | T.M.D.S. Clock Shield    |
| 7   | DDC Data                 | 15  | Ground<br>(return for +5V, HSync,<br>and VSync) | 23  | T.M.D.S. Clock+          |
| 8   | Analog Vertical Sync     | 16  | Hot Plug Detect                                 | 24  | T.M.D.S. Clock-          |
| C1  | Analog Red               | C2  | Analog Green                                    | C3  | Analog Blue              |
| C4  | Analog Horizontal Sync   | C5  | Analog Ground<br>(analog R, G, & B return)      |     |                          |

Table 2: Combined Analog and Digital Connector Pin Assignments
Source: Digital Visual Interface, Revision 1.0

#### Additional general specifications are:

#### Plug:

- -LFH (Low Force Helix) style contacts
- -fully shielded RFI/EMI can
- -grounding detents on mating shell
- -solder tails for cable termination
- -positive retention jackscrew: thread 4-40 UNC-2A

#### Receptacle:

- -high cycle, dual beam, LFH shrouded contacts
- -polarization achieved by a "D" shaped housing/shield
- -single piece shield with integral ground leg
- -shield protrudes for ESD considerations
- -solder tails for thru hole board mount
- -plastic retention pegs
- -jackposts: # 4-40 UNC-2A&B threads. The recommended application torque setting is 4 lbf in maximum. To prevent stripping the shield threads while installing the jackposts, it is recommended the jackposts are started by hand or with a lower initial torque driver setting. The engaged threads are rated to hold a minimum of 5 lbf in of torque.

|     |        | REVISE ON PC ONLY       | TITLE  |                     |                               |       |  |  |  |  |
|-----|--------|-------------------------|--|---------------------|-------------------------------|-------|--|--|--|--|
|     | G      | SEE SHEET 1             |  | I/O Plug a<br>Conne | and Receptacle<br>ctor System |       |  |  |  |  |
|     |        |                         | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO    |                     |                               |       |  |  |  |  |
|     | REV    | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |                     |                               |       |  |  |  |  |
| DOC | CUMENT | NO.                     |  |                     | FILE NAME                     | SHEET |  |  |  |  |
|     |        | PS-74320-001            |  |                     | PS74320.LWP                   | 3     |  |  |  |  |
|     |        | ES-40000-3996 REV. A SI | HEET 4 95/MAR/10   | EC U5-0926          | DCBRD03.SAM                   |       |  |  |  |  |






LANGUAGE ENGLISH

# 2.1 Product Drawing Numbers

### 2.1.1 Receptacle:

The DVI receptacle is for systems which support digital video (DVI-D) or both analog and digital video (DVI-I).






Figure 2: Right Angle DVI-D version (Digital)

Figure 3: Right Angle DVI-I version Intergrated(Analog/Digital)



Figure 4: Jackpost

#### Receptacle Sales Drawings:

| •                                       | <b>5</b>             |
|---|----------------------|
| <u>Description</u>                      | Sales Drawing Number |
| Right Angle DVI-I version               | SD-74320-001         |
| Vertical DVI-I version                  | SD-74320-002         |
| Right Angle DVI-D version               | SD-74320-003         |
| Vertical DVI-I version                  |                      |
| Right Angle DVI-D/ATX Forklock version. | SD-74320-009         |
| Vertical DVI-A version                  |                      |
| Right Angle DVI-A version               |                      |
| Right Angle DVI-I/ATX Forklock version  | SD-74320-009         |
| Jackposts                               |                      |

|     |        | REVISE ON PC ONLY       | TITLE MiroCross™ - DVI                                       |      |
|-----|--------|-------------------------|--|------|
|     | G      | SEE SHEET 1             | I/O Plug and Receptacle<br>Connector System                  |      |
|     |        |                         | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO    | ,    |
|     | REV    | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION | N    |
| DOC | CUMENT | NO.                     | FILE NAME SI   | IEET |
|     |        | PS-74320-001            | PS74320.LWP  | 4    |
|     |        | ES-40000-3996 REV. A SH | SHEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM                     |      |





LANGUAGE ENGLISH

#### 2.1.2 DVI Plug

The DVI plug is for systems which use analog or digital video. The analog DVI plug shown below supports analog video transmission from the host to the display.




Figure 5:
Analog Version

### **DVI Plug Sales Drawings (Analog version)**:

| <u>Description</u>            | Sales Drawing Number |
|-------------------------------|----------------------|
| Plug Subassembly              |                      |
| EMI Can Kit                   | SD-88789-9333        |
| (Kit includes upper and lower | shields)             |
| Crimp Ferrule                 | SD-73772-000         |
| Boot                          |                      |
| Jackscrew with cap            | SD-88780-6005        |

|     |        | REVISE ON PC ONLY      | TITLE                                       | ···            |                         |         |  |
|-----|--------|------------------------|---|----------------|-------------------------|---------|--|
|     | G      | SEE SHEET 1            | I/O Plug and Receptacle<br>Connector System |                |                         |         |  |
|     |        |                        | THIS DOCUMENT CON                           | ITAINS INFORMA | TION THAT IS PROPRIETAR | RY TO   |  |
|     | REV    | DESCRIPTION            | MOLEX INC. AND SHOU                         | LD NOT BE USED | WITHOUT WRITTEN PERM    | IISSION |  |
| DOC | CUMENT | NO.                    |   |                | FILE NAME               | SHEET   |  |
|     |        | PS-74320-001           |   |                | PS74320.LWP             | 5       |  |
|     |        | ES-40000-3996 REV. A S | HEET 4 95/MAR/10                            | EC U5-0926     | DCBRD03 SAM             |         |  |





LANGUAGE ENGLISH

#### 2.1.3

The digital DVI plug shown below supports digital video transmission from the host to the display.




Figure 6: Digital Version

# **DVI Plug Sales Drawings (Digital Version)**:

| Description                          | Sales Drawing Number |
|--------------------------------------|----------------------|
| Plug Subassembly                     | SD-74323-003         |
| EMI Can Kit                          |                      |
| (Kit includes upper and lower shield | s)                   |
| Crimp Ferrule                        | SD-73772-000         |
| Boot                                 |                      |
| Jackscrew with cap                   |                      |

|    | REVISE ON PC ONLY   |              | TITLE MiroCross™ - DVI                                       |      |  |
|----|---|--------------|--|------|--|
|    | G   | SEE SHEET 1  | I/O Plug and Receptacle<br>Connector System                  |      |  |
|    |   |              | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO    | 5    |  |
|    | REV   | DESCRIPTION  | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION | ИС   |  |
| DO | CUMENT  | NO.          | FILE NAME SI   | HEET |  |
|    | -   | PS-74320-001 | PS74320.LWP  | 6    |  |
|    | ES-40000-3996 REV. A SHEET 4 95/MAR/10 FC U5-0926 DCBRD03 SAM |              |  |      |  |





LANGUAGE ENGLISH

# 2.2 Dimensions, Materials, Plating, and Markings 2.2.1 Board Layout




Figure 7: Recommended PCB Layout for Right Angle DVI-I Receptacle




Figure 8: Recommended PCB Layout for Vertical DVI-I Receptacle

|     |        | REVISE ON PC ONLY       | TITLE MiroCross™ - DVI I/O Plug and Receptacle Connector System |                 |         |                   |        |
|-----|--------|-------------------------|---|-----------------|---------|-------------------|--------|
|     | G      | SEE SHEET 1             |   |                 |         |                   |        |
|     |        |                         | THIS DOCUMENT   | ONTAINS INFORMA | T NOITA | HAT IS PROPRIETAR | Y TO   |
|     | REV    | DESCRIPTION             | MOLEX INC. AND SH   | OULD NOT BE USE | D WITH  | OUT WRITTEN PERM  | ISSION |
| DOC | CUMENT | NO.                     |   |                 |         | FILE NAME         | SHEET  |
|     |        | PS-74320-001            |   |                 |         | PS74320.LWP       | 7      |
|     |        | ES-40000-3996 REV. A SH | HEET 4 95/MAR/10  | EC U5-0926      | DCE     | BRD03.SAM         |        |





LANGUAGE ENGLISH




Figure 9: Recommended PCB Layout for Right Angle DVI-D Receptacle




Figure 10: Recommended PCB Layout for Vertical DVI-D Receptacle

|     |        | REVISE ON PC ONLY       | TITLE MiroCross™ - DVI                                       |   |  |  |
|-----|--------|-------------------------|--|---|--|--|
|     | G      | SEE SHEET 1             | I/O Plug and Receptacle<br>Connector System                  |   |  |  |
|     | -      |                         | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO    |   |  |  |
|     | REV    | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |   |  |  |
| DOC | CUMENT | NO.                     | FILE NAME SHEE   | T |  |  |
|     |        | PS-74320-001            | PS74320.LWP 8  |   |  |  |
|     |        | ES-40000-3996 REV. A SH | HEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM                      |   |  |  |





LANGUAGE ENGLISH




Figure 11: Recommended PCB Layout for Right Angle DVI-D/ATX Fork Lock Receptacle

#### 2.2.3 Panel cut-out




Figure
12: Recommended Panel Cutout for Receptacle Connector

|     | RE        | VISE ON PC ONLY         | TITLE                                       | 1           |                |      |                    |        |
|-----|-----------|-------------------------|---|-------------|----------------|------|--------------------|--------|
|     | G         | SEE SHEET 1             | I/O Plug and Receptacle<br>Connector System |             |                |      |                    |        |
|     | DE1/      |                         | 1   |             |                |      | THAT IS PROPRIETAR |        |
|     | REV       | DESCRIPTION             | MOLEX IN                                    | C. AND SHOU | JLD NOT BE USE | WITH | IOUT WRITTEN PERM  | ISSION |
| DOC | CUMENT NO |                         |   |             |                |      | FILE NAME          | SHEET  |
|     | PS        | S-74320-001             |   |             |                |      | PS74320.LWP        | 9      |
|     | E         | ES-40000-3996 REV. A \$ | SHEET 4 95                                  | MAR/10      | EC U5-0926     | DCI  | BRD03.SAM          |        |





LANGUAGE ENGLISH

# 2.2.4 Recommended Spacing for Two or More Connectors on a P.C.B.




Figure 13: Spacing for Two or More DVI Connectors with Cable Assembly Applications




Figure 14: Spacing for Two or More DVI Connectors with Adapter Assembly Applications

| Adapter Combination          | Width of Adapter  | Dim. 'A'     | Dim. 'B'    |
|------------------------------|-------------------|--------------|-------------|
| DVI-A (plug) to VGA (rec.)   | 1.614/(41.0) max. | .525/(13.34) | .120/(3.05) |
| DVI-D (plug) to DFP (rec.)   |                   |              | , ,         |
| DVI-D (plug) to P&D-D (rec.) | 1.890/(48.0) max. | .800/(20.32) | .120/(3.05) |
| DVI-D (plug) to DVI-I (rec.) | 1.693/(43.0) ref. | .600/(15.24) | .117/(2.97) |

Table 3: Possible Combinations for Adapter and Cable Applications for P.C.B. Layout

|    |          | REVISE ON PC ONLY      |   | TITLE MiroCross™ - DVI |                |      |                    |        |
|----|----------|------------------------|---|------------------------|----------------|------|--------------------|--------|
|    | G        | SEE SHEET 1            | I/O Plug and Receptacle<br>Connector System |                        |                |      |                    |        |
|    |          |                        | THIS D                                      | OCUMENT CO             | NTAINS INFORMA | TION | THAT IS PROPRIETAR | Y TO   |
|    | REV      | DESCRIPTION            | MOLEX I                                     | NC. AND SHOU           | ILD NOT BE USE | WITH | OUT WRITTEN PERM   | ISSION |
| DO | CUMENT I | NO.                    |   |                        |                |      | FILE NAME          | SHEET  |
|    |          | PS-74320-001           |   |                        |                |      | PS74320.LWP        | 10     |
|    |          | ES-40000-3996 REV. A S | HEET 4                                      | 95/MAR/10              | EC U5-0926     | DCI  | BRD03.SAM          |        |





LANGUAGE ENGLISH

#### 2.2.4 Materials

Housings: High temp glass-filled thermoplastic, black or white/natural, UL94 V-0 Tail Aligner: High temp glass-filled thermoplastic, black or white/natural, UL94 V-0

Receptacle Terminals: Copper alloy.

Plug Terminals: Brass.

Receptacle Ground Terminal: Copper Alloy

Plug Key: Copper Alloy Plug Ground Blade: Brass

Shields: Steel

#### 2.2.4 Plating

Terminals (0.075inch/1.91mm and 0.050inch/2.54mm grid):
Option #1 -Select gold flash in contact area and 100 microinch / 2.50 micrometer minimum select tin/lead in solder tail area over 50 microinch / 1.27 micrometer nickel overall.

Option #2 - 30 microinch / 0.75 micrometer minimum select gold and 100 microinch / 2.50 micrometer minimum select tin/lead in solder tail area over 50 microinch / 1.27 micrometer nickel overall.

#### Microcross Ground:

30 microinch / 0.75 micrometer minimum select gold in contact area and; 100 microinch / 2.50 micrometer minimum select tin-lead in solder tail area over 50 microinch / 1.27 micrometer minimum nickel overall.

#### Key:

Select gold flash over 40 microinch / 1.00 micrometer nickel overall.

#### Ground Blade:

Select gold flash over 50 microinch / 1.27 micrometer nickel overall in contact area and 150 microinch / 3.75 micrometer tin/lead solder area.

#### Shields:

150 microinch / 3.75 micrometer minimum bright tin over; 50 microinch / 1.27 micrometer nickel; over copper flash overall.

|     | REVISE ON PC ONLY |                        | TITLE MiroCross™ - DVI                                       |    |  |
|-----|-------------------|------------------------|--|----|--|
|     | G                 | SEE SHEET 1            | I/O Plug and Receptacle<br>Connector System                  |    |  |
|     |                   |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO    |    |  |
|     | REV               | DESCRIPTION            | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |    |  |
| DOC | CUMENT            | NO.                    | FILE NAME SHEE   | ET |  |
|     |                   | PS-74320-001           | PS74320.LWP 11   |    |  |
|     |                   | ES-40000-3996 REV. A S | SHEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM                     |    |  |





LANGUAGE ENGLISH

2.2.5 Markings

All assemblies will contain circuit identification markings as well as the "Molex" or "Mlx" on the front of the shell. Refer to the appropriate sales drawings for specific marking information.

2.3 Safety Agency Approvals

UL File Number ...... E29179, Volume 10, Section 12

CSA File Number ...... LR19980

- 3.0 Applicable Documents and Specifications
  - 3.1 All documents referenced shall be of the latest revision. The order of precedence detailing requirements of this specification is as follows:
    - 1. Product Drawings 2. This specification
  - 3.2 Reference Documents
    - 3.2.1 EIA RS-364-(06,09,13,17,18,20,21,23,27,28,31,32,41,46,65,67,70,90) Electronic Industries Association, Recommended Standard
    - 3.2.2 IEC-801-2 International Electrotechnical Commission, Electrostatic Discharge Requirements
    - 3.2.3 MIL STD-202: Test methods for electronics and electrical component parts
    - 3.2.4 Molex PS-74320-9999 Application Specification, DVI Plug Cable Assembly
    - 3.2.5 Molex ES-74320-9998 Termination Specification, DVI Cable Assemblies
    - 3.2.6 Molex PS-74320-9997 Cable Assembly Specification
    - 3.2.7 UL 94: Tests for flammability of plastics materials
- 4.0 Ratings
  - 4.1 Voltage

40 Volts AC (RMS)

- 4.2 Current
  - 3.0 Amps per circuit.

30 °C maximum temperature rise and 55 °C maximum ambient per EIA-364-70.

4.3 Temperature

Operating: - 20 °C to + 85 °C

Nonoperating: - 20 °C to + 85 °C

|     | REVISE ON PC ONLY   |              | TITLE MiroCross™ - DVI |                      |                      |        |
|-----|---|--------------|------------------------|----------------------|----------------------|--------|
|     | G   |              |                        | Receptacle<br>System |                      |        |
|     |   |              | _ THIS DOCUMENT        | CONTAINS INFORMATION | I THAT IS PROPRIETAF | RY TO  |
|     | REV   | DESCRIPTION  | MOLEX INC. AND SH      | OULD NOT BE USED WIT | HOUT WRITTEN PERM    | ISSION |
| DOC | CUMENT  | NO.          |                        |                      | FILE NAME            | SHEET  |
|     |   | PS-74320-001 |                        |                      | PS74320.LWP          | 12     |
|     | ES-40000-3996 REV. A SHEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM |              |                        |                      |                      |        |





LANGUAGE ENGLISH

### 5.0 Performance

#### 5.1 Electrical Performance

| ITEM   | TEST CONDITION   | REQUIREMENT   |
|--|--|---|
| Contact Resistance   | Bulk resistance measured between plug solder<br>tails and receptacle solder tails<br>per ANSI/EIA-364-23   | 20 milliohm maximum, initial per contact<br>mated pair<br>10 milliohm maximum change from initial<br>reading per contact mated pair |
| Shell Resistance   | Bulk resistance measured between ground leg<br>on receptacle shield and the plug cable braid.<br>Test current=100mA; Test voltage=5 Volts DC<br>open circuit maximum<br>per ANSI/EIA-364-06A-83  | 50 milliohm maximum initial<br>50 milliohm maximum change from initial<br>reading   |
| Insulation Resistance  | Test voltage = 500 Volts DC +/- 50 V<br>Unmated and Unmounted<br>per ANSI/EIA 364-21, Method C   | 1Gigaohm Minimum between adjacent contacts and contacts and shell   |
| Dielectric Withstanding Voltage  Test voltage = 500 Volts DC +/-50 V  Unmated and Unmounted per ANSI/EIA 364-20, Method C  Barometric pressure of 15 psi |  | No flashover, No sparkover, No excess<br>leakage, No Breakdown  |
| Contact Current Rating   | Maximum ambient = 55 degree C<br>Maximum temperature change = 85 degree C<br>per ANSI/EIA-364-70, TP-70  | 3.0 A maximum   |
| Applied Voltage Rating   |  | 40 Volts AC (rms) continuous maximum, on any signal pin with respect to the shield  |
| Electrostatic Discharge  | Test unmated from 1 kV to 8kV in 1 kV steps using 8mm ball prob per IEC 801-2 Contact discharge to shell Air discharge perpendicular to shell Air discharge at angle to shell  | No evidence of discharge to contacts at 8kV. Discharge to the shell is acceptable.  |
| T.M.D.S. Signals<br>Time Domain<br>Impedance   | Risetime = 330 pS (10%-90%) S:G ratio per DVI pin designation Differential Measurement Specimen Environment Impedance = 100 ohm differential Source-side receptacle connector mounted on a controlled impendance pcb fixture per ANSI/EIA-364-108 draft Proposal | 100 ohms +/-15%   |

|   |              | REVISE ON PC ONLY      | TITLE MiroCross™ - DVI I/O Plug and Receptacle Connector System |                |                      |         |  |
|---|--------------|------------------------|---|----------------|----------------------|---------|--|
|   | G            | SEE SHEET 1            |   |                |                      |         |  |
|   |              |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO       |                |                      |         |  |
|   | REV          | DESCRIPTION            | MOLEX INC. AND SHO  | ULD NOT BE USE | WITHOUT WRITTEN PERI | MISSION |  |
| E | OCUMENT      | NO.                    |   |                | FILE NAME            | SHEET   |  |
|   | PS-74320-001 |                        |   |                | PS74320.LWP          | 13      |  |
|   |              | ES-40000-3996 REV. A S | SHEET 4 95/MAR/10   | EC U5-0926     | DCBRD03.SAM          |         |  |





LANGUAGE ENGLISH

| T.M.D.S. Signals<br>Time Domain<br>Crosstalk:<br>FEXT                | Risetime = 330 pS (10%-90%) S:G ratio per DVI pin designation Differential Measurement Specimen Environment Impedance = 100 ohm differential Source-side receptacle and the load side plug connector are mounted on a controlled impedance pcb fixture (1) Driven pair and (1) victim pair per ANSI/EIA-364-90 Draft Proposal  | 5% Maximum   |
|--|--|--|
| T.M.D.S. Signals<br>Rise Time Degradation                            | S:G ratio per DVI pin designation Differential Measurement Specimen Environment Impedance = 100 ohm differential Source-side receptacle and the load side plug connector are mounted on a controlled impedance pcb fixture per ANSI/EIA-364-102 Draft Proposal   | 160 pS Maximum<br>(Note: Converted bandwidth using<br>BW=0.35/t rise yields 2.2 GHz) |
| Analog RGB<br>Coaxial Signals<br>Time<br>Domain Impedance            | Risetime = 700 pS (10%-90%) S:G ratio per DVI pin designation Single-ended Measurement Specimen Enviroment Impedance = 75 ohm single-ended Source-side receptacle connector mounted on a controlled impedence pcb fixture per ANSI/EIA-364-108 Draft Proposal  | 75 ohms +/-10%   |
| Analog RGB<br>Coaxial Signals<br>Time<br>Domain Crosstalk:<br>(FEXT) | Risetime = 700 pS (10%-90%) S:G ratio per DVI pin designation Single-ended Measurement Specimen Enviroment Impedance = 75 ohm single-ended Source-side receptacle connector is mounted on a controlled impedance pcb fixture and the load side plug connector is terminated to semi-rigid coax. (1) Driven line and (1) victim line per ANSI/EIA-364-90 Draft Proposal | 3% Maximum   |
| Analog RGB<br>Coaxial Signals<br>Rise Time Degradation               | S:G ratio per DVI pin designation Single-ended Measurement Specimen Environment Impedance = 75 ohm single-ended Source-side receptacle connector is mounted on a controlled impedance pcb fixture and the load side plug connector is terminated to semi-rigid coax. per ANSI/EIA-364-102  | 140pS Maximum<br>(Note: Converted bandwidth using<br>BW=0.35/t rise yields 2.5 GHz)  |

|     | REVISE ON PC ONLY |                        | TITLE MiroCross™ - DVI                      |   |                 |      |                  |        |
|-----|-------------------|------------------------|---|---|-----------------|------|------------------|--------|
|     | G                 | SEE SHEET 1            | I/O Plug and Receptacle<br>Connector System |   |                 |      |                  |        |
|     |                   |                        | THIS D                                      | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO |                 |      |                  |        |
|     | REV               | DESCRIPTION            | MOLEX I                                     | NC. AND SHO   | JLD NOT BE USED | WITH | OUT WRITTEN PERM | ISSION |
| DOC | CUMENT            | NO.                    |   |   |                 |      | FILE NAME        | SHEET  |
|     | PS-74320-001      |                        |   |   |                 |      | PS74320.LWP      | 14     |
|     |                   | ES-40000-3996 REV. A S | HEET 4                                      | 95/MAR/10   | EC U5-0926      | DCE  | BRD03.SAM        |        |





LANGUAGE ENGLISH

### 5.2 Mechanical Performance

| ITEM                            | TEST CONDITION   | REQUIREMENT   |
|---------------------------------|--|---|
| Mating Force                    | One pair per ANSI/EIA 364-13<br>Insertion speed: 1inch (25mm) per minute   | 10.0 lbf (4.5 kgf) maximum  |
| Unmating Force                  | Mated pair per ANSI/EIA 364-13<br>Withdraw speed: 1inch (25mm) per minute  | 2.2 lbf (1.0 kgf) minimum<br>8.8 lbf (4.0 kgf) maximum  |
| Receptacle Contact<br>Retention | Individual contact   | 2.0 lbf (0.90 kgf) minimum  |
| Receptacle Key<br>Retention     | Individual key   | 2.0 lbf (0.90 kgf) minimum  |
| Plug Contact Retention          | Push out from mating face; Individual contact  | 10 lbf (4.5 kgf) minimum  |
| Plug Key Retention              | Push out from mating face; Individual key  | 10 lbf (4.5 kgf) minimum  |
| Durability                      | Automatic cycling: 100 cycles<br>per ANSI/EIA 364-09<br>at 100 +/- 50 cycles per hour  | Contact Resistance per EIA 364-23: 10 milliohm maximum change from initial per contact pair All samples to be mated Shell Resistance: 50 milliohm maximum (change from initial reading)                     |
| Vibration                       | 15 minutes / axis<br>per ANSI/EIA 364-28, Method 5A  | No discontinuities at 1 microsecond or longer (each contact) when continuity is tested per EIA-364-46   |
| Shock<br>(Mechanical)           | Per ANSI/EIA 364-27, Condition A (specified pulse)   | No discontinuities at 1 microsecond or longer (each contact) when continuity is tested per EIA-364-46   |
| Cable Pullout Force             | Test for cable strain relief & termination intergrity. Cable subjected to 25.0 lbf (11.3 kgf) static load for one minute while monitoring continuity. Isolate plug & receptacle interface from load. | No discontinuities greater than 1 microsecond   |
| Board Insertion Force           |  | 10.0 lbf (4.5 kgf) maximum  |
| Cable Flex                      | 100 cycles in each of 2 planes<br>Dimension X=3.7x Cable Diameter<br>per ANSI/EIA 364-41, Condition I  | No discontinuities greater than 1 microsecond allowed during flexing on contacts or shields per EIA-364-46 Dielectric Withstanding Voltage and Insulation Resistance tested per requirements of section 5.1 |
| Normal Force                    | For reference only   | .050" pitch terminals: 75 grams typical 90 grams typical Ground Plane: 100 grams typical  |
| Thread Torque                   | Mounted to panel; Test to failure; Tighten jackposts with torque gage until threads are stripped and jackpost turns freely   | 5.0 lbf in (5.76 kgf cm) minimum  |

|     | REVISE ON PC ONLY |                        | TITLE MiroCross™ - DVI                                    |                 |              |            |         |
|-----|-------------------|------------------------|---|-----------------|--------------|------------|---------|
|     | G                 | SEE SHEET 1            | I/O Plug and Receptacle<br>Connector System               |                 |              |            |         |
| ł   |                   |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO |                 |              |            |         |
|     | REV               | DESCRIPTION            | MOLEX INC. AND SH   | OULD NOT BE USE | O WITHOUT WR | ITTEN PERM | IISSION |
| DOC | CUMENT            | NO.                    |   |                 | FILE         | NAME       | SHEET   |
|     |                   | PS-74320-001           |   |                 | PS74         | 320.LWP    | 15      |
|     |                   | ES-40000-3996 REV. A S | HEET 4 95/MAR/10  | EC U5-0926      | DCBRD03.     | SAM        |         |





LANGUAGE ENGLISH

#### 5.3 Environmental Performance

| ITEM                         | TEST CONDITION   | REQUIREMENT  |
|------------------------------|--|--|
| Thermal Shock                | 10 cycles Mated/Unmated per ANSI/EIA 364-32,<br>Condition I                      | Contact Resistance: 10 milliohm maximum change from initial per contact pair All samples to be mated Shell Resistance: 50 milliohm maximum change from initial per EIA-364-23                  |
| Humidity<br>(Cyclic)         | ANSI/EIA 364-31, Conditions A and B<br>Method III, omit 7A and 7B                | Contact Resistance: 10 milliohm maximum change from initial per contact pair All samples to be mated Shell Resistance: 50 milliohm maximum change from initial per EIA-364-23                  |
| Thermal Aging                | 105 °C for 250 hours<br>Mated per ANSI/EIA 364-17, Condition 4,<br>Method A.     | Contact Resistance: 10 milliohm maximum change from initial per contact pair All samples to be mated Shell Resistance: 50 milliohm maximum change from initial per contact pair per EIA-364-23 |
| Temperature Rise             | Per ANSI/EIA 364-70  | 30 °C maximum temperature rise   |
| Resistance to Solder<br>Heat | Dip connector solder tails to board for 10 seconds<br>Solder Temp = 260 +/- 5 °C | No visual damage to insulator  |
| Solderability                | Per MIL-STD-202, Method 208  | 95% minimum coverage   |
| Temperature Rating           | Operating  | -20 degree C to +85 degree C   |
| Temperature Rating           | Non-Operating  | -20 degree C to +85 degree C   |

|     | REVISE ON PC ONLY |                                    | TITLE MiroCross™ - DVI                      |                    |        |  |
|-----|-------------------|------------------------------------|---|--------------------|--------|--|
|     | G                 | SEE SHEET 1                        | I/O Plug and Receptacle<br>Connector System |                    |        |  |
|     |                   | THIS DOCUMENT CONTAINS INFORMATION | N THAT IS PROPRIETAR                        | RY TO              |        |  |
|     | REV               | DESCRIPTION                        | MOLEX INC. AND SHOULD NOT BE USED WIT       | THOUT WRITTEN PERM | ISSION |  |
| DOC | CUMENT            | NO.                                |   | FILE NAME          | SHEET  |  |
|     | PS-74320-001      |                                    |   | PS74320.LWP        | 16     |  |
|     |                   | ES-40000-3996 REV. A SH            | HEET 4 95/MAR/10 EC U5-0926 DO              | CBRD03.SAM         |        |  |





LANGUAGE ENGLISH

6.0 Packaging

6.1 Receptacles:

All receptacles are packaged in trays. For specific packaging information, refer to PK-74320-001 for right angle receptacles and PK-74320-002 for vertical receptacles.

7.0 Other Information

7.1 Test Sequences


|    | REVISE ON PC ONLY   |             | TITLE MiroCross™ - DVI                                    |               |  |
|----|---|-------------|---|---------------|--|
| :  | G   | SEE SHEET 1 | I/O Plug and Receptacle<br>Connector System               |               |  |
|    |   |             | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO |               |  |
|    | REV   | DESCRIPTION | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTE          | EN PERMISSION |  |
| DO | CUMENT  | NO.         | FILE N  | AME SHEET     |  |
|    | PS-74320-001  |             | PS74320   | ).LWP 17      |  |
|    | ES-40000-3996 REV. A SHEET 4 95/MAR/10 EC U5-0926 DCBRD03 SAM |             |   |               |  |





LANGUAGE ENGLISH

#### **Group 1: Mated Environmental**



#### Number of samples

- (5) Receptacle assembled to printed circuit board.
- (5) Cable assemblies with a plug assembled to one end, 10 inch/25.4 cm long


| İ  | G SEE SHEET 1 |                         | TITLE MiroCross <sup>TM</sup> - DVI I/O Plug and Receptacle Connector System |                        |       |
|----|---------------|-------------------------|--|------------------------|-------|
|    |               |                         |  |                        |       |
|    |               |                         | THIS DOCUMENT CONTAINS INFORMATION THA                                       | ION THAT IS PROPRIETAR | RY TO |
|    | REV           | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION                 |                        |       |
| DO | CUMENT N      | 10.                     |  | FILE NAME              | SHEET |
|    | PS-74320-001  |                         |  | PS74320.LWP            | 18    |
|    |               | ES-40000-3996 REV. A SH | HEET 4 95/MAR/10 EC U5-0926  | DCBRD03.SAM            |       |





LANGUAGE ENGLISH

Group 2: Mated Mechanical



#### **Number of Samples:**

- (2) Receptacles, assembled to printed circuit board.
- (2) Cable assemblies with a plug assembled to one end, 10 inch/25.4 cm long.

<u>Note:</u> Connector is to be mounted on a fixture that simulates the typical application. The receptacle connector shall be mounted to a panel, per the receptacle panel cutout shown in Figure 12, which is permanently affixed to the fixture. The plug shall be mated to the receptacle with jackscrews fully engaged and the other end of the cable shall be permanently clamped to the fixture, 3 inches from connector face.


|    | REVISE ON PC ONLY |   | TITLE MiroCross™ - DVI |                 |                      |        |
|----|-------------------|---|------------------------|-----------------|----------------------|--------|
|    | G SEE SHEET 1     | I/O Plug and Receptacle<br>Connector System               |                        |                 |                      |        |
|    |                   | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO |                        |                 |                      |        |
|    | REV               | DESCRIPTION   | MOLEX INC. AND SHOU    | JLD NOT BE USED | WITHOUT WRITTEN PERM | ISSION |
| DO | CUMENT            | NO.   |                        |                 | FILE NAME            | SHEET  |
|    | PS-74320-001      |   |                        |                 | PS74320.LWP          | 19     |
|    |                   | ES-40000-3996 REV. A SI                                   | HEET 4 95/MAR/10       | EC U5-0926      | DCBRD03.SAM          |        |





LANGUAGE ENGLISH

#### Group 3: Mated Mechanical



### **Number of Samples:**

- (2) Receptacles, assembled to printed circuit board.
- (2) Cable assemblies with a plug assembled to one end, 10 inch/25.4 cm long.


|     | REVISE ON PC ONLY |                         | TITLE MiroCross™ - DVI                                    |       |  |
|-----|-------------------|-------------------------|---|-------|--|
| ;   | G                 | SEE SHEET 1             | I/O Plug and Receptacle<br>Connector System               |       |  |
|     |                   |                         | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY T  | го    |  |
|     | REV               | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISS | ION   |  |
| DOC | CUMENT            | NO.                     | FILE NAME S   | SHEET |  |
|     | PS-74320-001      |                         | PS74320.LWP   | 20    |  |
|     |                   | ES-40000-3996 REV. A SH | HEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM                   |       |  |





LANGUAGE ENGLISH

### Group 4: Insulator Intergrity



### **Number of Samples:**

- (2) Receptacles, assembled to printed circuit board.
- (2) Cable assemblies with a plug assembled to one end, 10 inch/25.4 cm long


|     | G SEE SHEET 1 |                         | TITLE MiroCross™ - DVI                                       |   |  |  |
|-----|---------------|-------------------------|--|---|--|--|
|     |               |                         | I/O Plug and Receptacle<br>Connector System                  |   |  |  |
|     |               |                         | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO    |   |  |  |
|     | REV           | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |   |  |  |
| DOC | CUMENT        | NO.                     | FILE NAME SHEET  | Γ |  |  |
|     | PS-74320-001  |                         | PS74320.LWP 21   |   |  |  |
|     |               | ES-40000-3996 REV. A SI | SHEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM                     |   |  |  |





LANGUAGE ENGLISH

Group 5: Cable Flexing



Number of Samples: (2) Cable assemblies

Group 6: Electrostatic Discharge

ELECTROSTATIC DISCHARGE

Number of Samples: (1) Receptacle connector

|     |               | REVISE ON PC ONLY       |   | ss™ - DVI             |        |  |
|-----|---------------|-------------------------|---|-----------------------|--------|--|
|     | G SEE SHEET 1 |                         | I/O Plug and Receptacle<br>Connector System |                       |        |  |
| ľ   |               |                         | THIS DOCUMENT CONTAINS INFORMATI            | ON THAT IS PROPRIETAR | RY TO  |  |
|     | REV           | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED V         | VITHOUT WRITTEN PERM  | ISSION |  |
| DOC | CUMENT        | NO.                     |   | FILE NAME             | SHEET  |  |
|     |               | PS-74320-001            |   | PS74320.LWP           | 22     |  |
|     |               | ES-40000-3996 REV. A SH | EET 4 95/MAR/10 EC U5-0926                  | DCBRD03.SAM           |        |  |





LANGUAGE

**English** 

#### Scope

This specification details the requirements for composite cables which are used in typical Analog (RGB) and Digital (TMDS) cable assemblies. These cables are typically used with Molex Microcross DVI and P&D, 1.27mm I/O, Milligrid, and VGA connector products.

A common set of components is used to construct all of these cables. The components which a particular cable contains is determined by which signals the cable assembly is required to support.

The information in this document is organized in the following order:

- General information
   Standard Molex Cables
- 3. Component information
- 4. Additional requirements

#### **Defined Cable Types**

- 11 Conductor 30/28 AWG Composite Cable for RGB Analog: Supports analog video and DDC.
- 13 Conductor 30/28 AWG Composite Cable for TMDS Digital Single Link: Supports DDC and 1 TMDS link of digital video.
- 19 Conductor 28 AWG Composite Cable for TMDS Digital Dual Link: Supports DDC and 2 TMDS links of digital video.
- 19 Conductor 30/28 AWG Composite Cable for RGB Analog &TMDS Digital Single Link: Supports DDC, analog video, and 1 TMDS link of digital video.
- All cables support a Hot Plug Detect line.

#### **Molex Cable Part Numbers**

|                         | Jacket (        | Color      |
|-------------------------|-----------------|------------|
| Cable Name              | Parchment White | Black      |
| DVI Analog              | 74411-0001      | 74411-0002 |
| DVI Single Link (7.0mm) | 74411-0003      | 74411-0004 |
| DVI Dual Link           | 74411-0005      | 74411-0006 |
| DVI Analog & Digital    | 74411-0007      | 74411-0008 |
| DVI Single Link (5.5mm) | 74411-0009      | 74411-0010 |

|    | REV    | D    | D     | D     | D    | D                   | D    | D  | D    | D     | D      | D     | D     | D     | D     | D    |      |      |       |       |          |        |      |    |
|----|--------|------|-------|-------|------|---------------------|------|----|------|-------|--------|-------|-------|-------|-------|------|------|------|-------|-------|----------|--------|------|----|
|    | SHT    | 1    | 2     | 3     | 4    | 5                   | 6    | 7  | 8    | 9     | 10     | 11    | 12    | 13    | 14    | 15   |      |      |       |       |          |        |      |    |
|    |        | REV  | ISE ( | ON F  | CO   | NLY                 |      |    | TIT  | LE    |        |       |       |       |       |      |      |      |       |       |          |        |      |    |
|    | D      | Р    |       | EC# ( |      | ED<br>2001<br>20/08 |      | 4  |      |       |        |       | V     | IDE(  | O CA  | BLE  | SPE  | ECII | FICA  | 1OIT. | ١        |        |      |    |
|    |        |      |       |       |      |                     |      |    |      |       |        |       |       |       |       |      |      |      |       |       |          | ARY T  |      |    |
|    | REV    |      |       | DESC  | RIP  | TION                | 1    | _  | MOL  | EX IN | IC. AI | ND SH | IOULI | O NO. | TBE   | USED | WITI | HOU  | IT WR | RITTE | N PE     | RMISS  | ION  |    |
|    | DESI   | GN C | CONT  | ΓRΟΙ  | _    | S                   | ΓΑΤ  | JS | WRI  | TTEN  | BY:    | CHE   | CKED  | BY:   | API   | PROV | ED B | Y:   | DA    | TE: Y | 'R/N     | 10 / D | AY   |    |
|    |        | UD   | T     |       |      |                     | M    |    | TM   | cCLE  | ELL    | RN    | ELS   | ИС    | R     | NEL  | SON  |      |       | 9     | 9 / 1    | 0 / 22 | 2    |    |
| DO | CUMENT | NO.  |       |       |      |                     |      |    |      |       |        |       |       |       | -     |      |      |      | FIL   | E NA  | ME       | SH     | IT N | О. |
|    |        | PS-  | 7441  | 1-00  | )1   |                     |      |    |      |       |        |       |       |       |       |      |      |      | PS    | 3744° | 11       | 1 C    | )F   | 15 |
|    |        | ES   | 3-400 | 000-3 | 3996 | RE                  | V. A | Sŀ | IEET | 3 9   | 95/M   | AR/1  | 0     | EC l  | J5-09 | 926  | DC   | CBF  | RD03  | .SAN  | <u>/</u> |        |      |    |





LANGUAGE

**English** 

# **Cable Markings**

All cables must be marked in light gray ink and contain the following information:

Manufacturer identification
Underwriters Symbol
AWM Style Number
Temperature rating
Voltage rating
Text "DVI" and cable description

Example: Molex AWM STYLE 20276 60°C 30V VW-1 --- DVI ANALOG

# **Individual Wire Color Coding**

| Comp.  | Comp.    |                  | Conductor | r Jacket Color     |              | Signal         |
|--------|----------|------------------|-----------|--------------------|--------------|----------------|
| Number | Type     | #1               | #2        | #1<br>(5.5mm O.D.) | #2<br>(5.5   | Assignment     |
| 1      | <u> </u> | D1 1             |           | (5.5mm O.D.)       | (5.5mm O.D.) |                |
| 1      | A        | Blue 1           |           |                    |              | Blue Video     |
| 2      | A        | Red <sup>1</sup> |           |                    |              | Red Video      |
| 3      | A        | Green 1          |           |                    |              | Green Video    |
| 4      | В        | Yellow           | Black     | Yellow             | Black        | +5V/DDC Return |
| 5      | C        | Red              |           |                    |              | H Svnc         |
| 6      | C        | Orange / Black   |           | Violet             |              | DDC Data       |
| 7      | C        | Brown/Yellow     |           | Red                |              | DDC Clock      |
| 8      | C        | Green            |           |                    |              | Svnc Return    |
| 9      | C        | Brown            |           |                    |              | V Svnc         |
| 10     | C        | White            |           | White              |              | Sense          |
| 11     | D        | Red / White      | Red       | White              | Red          | TMDS Data 2    |
| 12     | D        | Green / White    | Green     | White              | Green        | TMDS Data 1    |
| 13     | D        | Blue / White     | Blue      | White              | Blue         | TMDS Data 0    |
| 14     | D        | Brown / White    | Brown     | White              | Brown        | TMDS Clock     |
| 15     | E        | Orange / White   | Orange    |                    |              | TMDS Data 5    |
| 16     | E        | Violet / White   | Violet    |                    |              | TMDS Data 4    |
| 17     | E        | Grav / White     | Grav      |                    |              | TMDS Data 3    |
| 18     | E        | Red / White      | Red       |                    |              | TMDS Data 2    |
| 19     | E        | Green / White    | Green     |                    |              | TMDS Data 1    |
| 20     | E        | Blue / White     | Blue      |                    |              | TMDS Data 0    |
| 21     | E        | Brown / White    | Brown     |                    |              | TMDS Clock     |

Notes: 1 Coax lines can either be the solid color or be stripped with the color listed.


|     |        | REVISE ON PC ONLY      | TITLE   |            |       |
|-----|--------|------------------------|---|------------|-------|
|     | D      | SEE SHEET 1            | VIDEO CABLE SPE   | CIFICATION |       |
|     | REV    | DESCRIPTION            | THIS DOCUMENT CONTAINS INFORMATION MOLEX INC. AND SHOULD NOT BE USED WITH |            | 1     |
| DOC | CUMENT | NO.                    |   | FILE NAME  | SHEET |
|     |        | PS-74411-001           |   | PS74411    | 2     |
|     |        | ES-40000-3996 REV. A S | SHEET 4 95/MAR/10 EC U5-0926 DC   | BRD03.SAM  |       |





LANGUAGE **English** 

**DVI ANALOG** 



# Cable Construction:

- 3 Component A (#1 #3), 1 Component B (#4), and 6 Component C (#5 #10) cabled together Inner Shield (Type A)
  Outer Shield
  Jacket

|     |        | REVISE ON PC ONLY       | TITLE                                |                    |         |
|-----|--------|-------------------------|--------------------------------------|--------------------|---------|
|     | D      | SEE SHEET 1             | VIDEO CABLE SF                       | PECIFICATION       |         |
|     |        |                         | THIS DOCUMENT CONTAINS INFORMATIO    |                    |         |
| Ĺ   | REV    | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WI | THOUT WRITTEN PERM | IISSION |
| DOC | CUMENT | NO.                     |                                      | FILE NAME          | SHEET   |
|     |        | PS-74411-001            |                                      | PS74411            | 3       |
|     |        | ES-40000-3996 REV. A SI | HEET 4 95/MAR/10 EC U5-0926 D        | CBRD03.SAM         |         |






LANGUAGE

**English** 

# DVI SINGLE LINK (7.0mm O.D.)



#### Cable Construction:

- 1. 1 Component B (#4), 3 Component C (#6, #7, #10), and 4 Component D (#11 #14) cabled together around a core of filler material
   2. Inner Shield (Type B)
   3. Outer Shield
   4. Jacket


|     |        | REVISE ON PC ONLY       | TITLE   |                        |       |
|-----|--------|-------------------------|---|------------------------|-------|
|     | D      | SEE SHEET 1             | VIDEO CABLE   | SPECIFICATION          |       |
|     | REV    | DESCRIPTION             | THIS DOCUMENT CONTAINS INFORMAT MOLEX INC. AND SHOULD NOT BE USED |                        |       |
|     | IVEV   | DESCRIPTION             | INCLES INC. THE CHOOLE NOT BE COLD                                | WITHOUT WITH EITH EITH |       |
| DOC | CUMENT | NO.                     |   | FILE NAME              | SHEET |
|     |        | PS-74411-001            |   | PS74411                | 4     |
|     |        | ES-40000-3996 REV. A SI | HEET 4 95/MAR/10 EC U5-0926                                       | DCBRD03.SAM            | •     |





**LANGUAGE** English

# **DVI SINGLE LINK (5.5mm O.D.)**



#### Cable Construction:

- 1. 1 Component B (#4), 3 Component C (#6, #7, #10), and 4 Component D (#11 #14) cabled together with filler material
   2. Inner Shield (Type B)
   3. Outer Shield
   4. Jacket


|     | F        | REVISE ON PC ONLY      | TITLE   |          |
|-----|----------|------------------------|---|----------|
|     | D        | SEE SHEET 1            | VIDEO CABLE SPECIFICATION   |          |
|     | REV      | DESCRIPTION            | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPI<br>MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN |          |
| DOC | CUMENT N | 10.                    | FILE NAM  | IE SHEET |
|     |          | PS-74411-001           | PS7441  | 1 5      |
|     |          | ES-40000-3996 REV. A S | HEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM   |          |





**LANGUAGE English** 

#### **DVI DUAL LINK**



## Cable Construction:

1 Component B (#4) cabled together with filler material to form core 3 Component C (#6, #7, #10) and 7 Component E (#15 - #21) cabled around core Inner Shield (Type B)
Outer Shield
Jacket

|     |        | REVISE ON PC ONLY       | TITLE                                  |                  |         |
|-----|--------|-------------------------|--|------------------|---------|
|     | D      | SEE SHEET 1             | VIDEO CABLE SPE                        | CIFICATION       |         |
| :   |        |                         | THIS DOCUMENT CONTAINS INFORMATION     |                  |         |
|     | REV    | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITH | OUT WRITTEN PERM | IISSION |
| DOC | CUMENT | NO.                     |  | FILE NAME        | SHEET   |
|     |        | PS-74411-001            |  | PS74411          | 6       |
|     |        | ES-40000-3996 REV. A SI | HEET 4 95/MAR/10 EC U5-0926 DC         | BRD03.SAM        |         |






**LANGUAGE** 

English

### **DVI ANALOG & DIGITAL**



#### Cable Construction:

1 Component D (#11) and 4 Component C (#5, #8 - #10) cabled together to form core 3 Component A (#1 - #3), 1 Component B (#4), 3 Component D (#12 - #14), and 2 Component C (#6, #7) cabled around core Inner Shield (Type A) Outer Shield Jacket

|     |        | REVISE ON PC ONLY      | TITLE   |             |       |
|-----|--------|------------------------|---|-------------|-------|
|     | D      | SEE SHEET 1            | VIDEO CABLE SPE   | ECIFICATION |       |
|     | REV    | DESCRIPTION            | THIS DOCUMENT CONTAINS INFORMATION MOLEX INC. AND SHOULD NOT BE USED WITH |             |       |
| DOC | CUMENT | NO.                    |   | FILE NAME   | SHEET |
|     |        | PS-74411-001           |   | PS74411     | 7     |
|     |        | ES-40000-3996 REV. A S | HEET 4 95/MAR/10 EC U5-0926 DC  | BRD03.SAM   |       |





LANGUAGE

English

#### **Cable Sizes**

The outer diameter of all DVI cables must meet the following two requirements:

The outer diameter tolerance shall not be greater than  $\pm$  .015" ( $\pm$  0.38) for any cable. The entire tolerance range must fall within one of the ranges shown below: (i.e. it should not straddle two ranges)

| Cable Types          | Acceptable Cable Range O.D. |             |  |  |
|----------------------|-----------------------------|-------------|--|--|
|                      | Inch                        | mm          |  |  |
| DVI Analog           | .255285                     | 6.48 - 7.24 |  |  |
| DVI Single Link      | .260290                     | 6.60 - 7.37 |  |  |
| DVI Single Link      | .209224                     | 5.31 - 5.69 |  |  |
| DVI Dual Link        | .315345                     | 8.00 - 8.76 |  |  |
| DVI Analog & Digital | .330360                     | 8.38 - 9.14 |  |  |

### Miscellaneous

| Cable Types                  | Minimum Bend Radius Inch (mm) |
|------------------------------|-------------------------------|
| DVI Analog                   | 1.0 (25.4)                    |
| DVI Single Link (7.0mm O.D.) | 1.0 (25.4)                    |
| DVI Single Link (5.5mm O.D.) | .75 (19.05)                   |
| DVI Dual Link                | 1.2 (30.48)                   |
| DVI Analog & Digital         | 1.3 (30.02)                   |

# **Component Construction**

# Component A - Coax

| Item       | Material   | Size                                    | O.D.                                  |
|------------|--|---|---------------------------------------|
| Conductor  | Tin Plated Copper                                    | 30 AWG (7/38)                           | .012" (0.30) Nom.                     |
| Insulation | Foamed Polypropylene or<br>High Density Polyethylene | .0195" (0.50)<br>Min. average thickness | .051" (1.30) Typ.                     |
| Shield     | Tin Plated Copper                                    | 36 AWG                                  |                                       |
|            | Braid Con  | struction. 90% Min. Coverage            | · · · · · · · · · · · · · · · · · · · |
| Jacket     | PVC  | .009" (0.229) thick<br>Min.             | .089" (2.26) Typ.                     |

|     | REVISE ON PC ONLY |                        | TITLE  |                     |         |
|-----|-------------------|------------------------|--|---------------------|---------|
|     | D                 | SEE SHEET 1            | VIDEO CABLE S  | SPECIFICATION       |         |
|     | REV               | DESCRIPTION            | THIS DOCUMENT CONTAINS INFORMATION MOLEX INC. AND SHOULD NOT BE USED W |                     |         |
|     | NE V              | DESCRIPTION            | INGLEX ING. FIND OFFICEED NOT BE COLD IN                               | MINOSI WIGHTERN ERG | MOGICIA |
| DOC | CUMENT            | NO.                    |  | FILE NAME           | SHEET   |
|     |                   | PS-74411-001           |  | PS74411             | 8       |
|     |                   | ES-40000-3996 REV. A S | HEET 4 95/MAR/10 EC U5-0926  | DCBRD03.SAM         |         |





**LANGUAGE English** 

# **Component Construction (Continued)**

### Component B - Pair

| ltem       | Material          | Size                                   | O.D.              |
|------------|-------------------|--|-------------------|
| Conductor  | Tin Plated Copper | 28 AWG (7/36)                          | .015" (0.38) Nom. |
| Insulation | Semi-Rigid PVC    | .006" (0.15)<br>Min. average thickness | .027" (0.69) Typ. |
| Pair       | Two ins           | sulated conductors twisted toget       | her               |

## Component B - Pair (5.5mm O.D.)

| Item       | Material                                  | Size                           | O.D.                 |  |
|------------|---|--------------------------------|----------------------|--|
| Conductor  | Tin Plated Copper                         | 30 AWG (7/38)                  | .012" (0.31) Nom.    |  |
| Insulation | Polypropylene                             | .005" (0.12)<br>Nom. thickness | .020022" (0.52-0.56) |  |
| Pair       | Two insulated conductors twisted together |                                |                      |  |

#### Component C - Single

| Item       | Material  | Size                                   | O.D.              |
|------------|---|--|-------------------|
| Conductor  | Tin Plated Copper                                 | 28 AWG (7/36)                          | .015" (0.38) Nom. |
| Insulation | Foamed Polypropylene or High Density Polyethylene | .006" (0.15)<br>Min. average thickness | .027" (0.69) Typ. |

### Component C- Single (5.5mm O.D.)

| Item       | Material          | Size                           | O.D.                 |
|------------|-------------------|--------------------------------|----------------------|
| Conductor  | Tin Plated Copper | 28 AWG (7/36)                  | .015" (0.38) Nom.    |
| Insulation | Polyethylene      | .004" (0.11)<br>Nom. thickness | .023024" (0.58-0.62) |

Additional Requirements: DDC: Consists of components #4, #6, #7. The twisted pair (Component B) must lay between the two single wires (#6 and #7).

H/V Sync: Consists of components #5, #8, #9. These three wires must be bundled together inside the cable with the sync return (#8) in the middle most position.

|     |                         | REVISE ON PC ONLY | TITLE  |            |       |
|-----|-------------------------|-------------------|--|------------|-------|
|     | D                       | SEE SHEET 1       | VIDEO CABLE SPE  | CIFICATION |       |
|     | REV                     | DESCRIPTION       | THIS DOCUMENT CONTAINS INFORMATION T<br>MOLEX INC. AND SHOULD NOT BE USED WITH |            |       |
| DOC | UMENT                   | NO.               |  | FILE NAME  | SHEET |
|     |                         | PS-74411-001      |  | PS74411    | 9     |
|     | ES-40000-3996 REV. A SH |                   | HEET 4 95/MAR/10 EC U5-0926 DC   | BRD03.SAM  | 1     |





LANGUAGE English

# **Component Construction (Continued)**

# Component D & E - Shielded Pairs (Standard Construction)

| Item       | Material   | Size                                    | O.D.              |
|------------|--|---|-------------------|
| Conductor  | Tin Plated Copper  | 28 AWG (7/36)                           | .015" (0.38) Nom. |
| Insulation | Foamed Polypropylene or High Density Polyethylene                                | .0125" (0.32)<br>Min. average thickness | .040" (1.02) Typ. |
| Shield     | Aluminum/Polyester Tape with Foil-Free edge, aluminum side facing in 25% overlap |   |                   |
| Pair       | Two insulated conductors twisted together  |   |                   |
| Drain Wire | Tin Plated Copper  | 28 AWG (7/36)                           | .015" (0.38) Nom. |

# Component D & E - Shielded Pairs (5.5mm O.D.)

| Item       | Material   | Size                                   | O.D.              |  |
|------------|--|--|-------------------|--|
| Conductor  | Tin Plated Copper  | 30 AWG (7/38)                          | .012" (0.31) Nom. |  |
| Insulation | Foamed Polypropylene or High Density Polyethylene                                | .010" (0.25)<br>Min. average thickness | .031" (0.80) Typ. |  |
| Shield     | Aluminum/Polyester Tape with Foil-Free edge, aluminum side facing in 25% overlap |  |                   |  |
| Pair       | Two insulated conductors twisted together  |  |                   |  |
| Drain Wire | Tin Plated Copper  | 30 AWG (7/38)                          | .012" (0.31) Nom. |  |

|    |   | REVISE ON PC ONLY | TITLE   |           |       |
|----|---|-------------------|---|-----------|-------|
|    | D SEE SHEET 1   |                   | VIDEO CABLE SPECIFICATION   |           |       |
|    | REV   | DESCRIPTION       | THIS DOCUMENT CONTAINS INFORMATION MOLEX INC. AND SHOULD NOT BE USED WITH |           |       |
| DO | DOCUMENT NO.  |                   |   | FILE NAME | SHEET |
|    |   | PS-74411-001      |   | PS74411   | 10    |
|    | ES-40000-3996 REV. A SHEET 4 95/MAR/10 EC U5-0926 DCBRD03.SAM |                   |   |           |       |





LANGUAGE English

# Filler -Used as required to maintain concentricity of cable

| Material | Polypropylene Fibers |
|----------|----------------------|
|----------|----------------------|

# Inner Shield (Type A)

| Material  | Aluminum / Polyester Tape             |  |  |
|-----------|---------------------------------------|--|--|
| Thickness | .00035" / .001" (.009 / .025) typical |  |  |
| Direction | Aluminum side facing in               |  |  |
| Coverage  | 25 % Overlap                          |  |  |

# Inner Shield (Type B)

| Material Aluminum (optional) / Polvester / Aluminum Tape |  |  |  |  |
|--|--|--|--|--|
| Thickness  | .00035" / .001" / .00035" (.009 / .025 / .009) typical |  |  |  |
| Coverage   | 25 % Overlap   |  |  |  |

# Outer Shield - For all cables

| Type     | Braid             |  |
|----------|-------------------|--|
| Material | Tin Plated Copper |  |
| AWG      | 36                |  |
| Coverage | 80% Minimum       |  |

## Outer Jacket - For all cables

| Material       | Super Flexible PVC                   |
|----------------|--------------------------------------|
| Thickness      | $.030 \pm .005$ " (0.76 $\pm 0.13$ ) |
| Outer Diameter | See section titled Cable Sizes       |

|    | REVISE ON PC ONLY |                      |         | TITLE  |            |     |           |       |  |
|----|-------------------|----------------------|---------|--|------------|-----|-----------|-------|--|
|    | D SEE SHEET 1     |                      |         | VIDEO CABLE SPECIFICATION  |            |     |           |       |  |
|    | REV               | DESCRIPTION          |         | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOLEX INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION |            |     |           |       |  |
| DO | DOCUMENT NO.      |                      |         |  |            |     | FILE NAME | SHEET |  |
|    | PS-74411-001      |                      |         |  |            |     | PS74411   | 11    |  |
|    |                   | ES-40000-3996 REV. A | SHEET 4 | 95/MAR/10  | EC U5-0926 | DCI | BRD03 SAM | •     |  |





LANGUAGE English

# **Electrical Requirements**

| Item                      | Units                 | Components    | Reau         | irement                                 |
|---------------------------|-----------------------|---------------|--------------|---|
| Dielectric Strength       | VDC                   | All           | 500          | For 1 minute                            |
| Insulation                | M Ω- 1000 ft          | A (Coax)      | 3300/(1000)  | Minimum                                 |
| Resistance                | $(M \Omega - km)$     | В-Е           | 50/(15)      | Minimum                                 |
| Conductor DC              | Ω/ft                  | A             | .100 (.328)  | Typical @20°C                           |
| Resistance                | $(\Omega/\mathrm{m})$ | B - E         | .065 (.213)  | Typical @20°C                           |
| Current Rating            | Amps                  | (30 & 28 AWG) | 1.5          | Minimum                                 |
| Impedance                 | Ω                     | A             | 75 ± 5       | Typical @ TDR                           |
| Differential<br>Impedance | Ω                     | D & E         | $100 \pm 5$  | @ TDR                                   |
| Capacitance               | pF/ft<br>(pF/m)       | A             | 18.0 (59.1)  | Typical                                 |
| Mutual Capacitance        | pF/ft<br>(pF/m)       | D & E         | 14.0 (45.9)  | Typical                                 |
| Time Delay                | ns/ft                 | A             | 1.30 (4.27)  | Typical                                 |
| I mile Delay              | (ns/m)                | D             | 1.43 (4.69)  | Typical                                 |
| Time Delay Skew           | ns/ft                 | D & E         | 0.026 (.085) | Maximum between pairs                   |
|                           | (ns/m)                |               | 0.010 (.033) | Maximum within a pair                   |
| Far End Crosstalk         | %                     | D & E         | 1.0          | Maximum in 10 meters @ 300 ps rise-time |

# Component Key:

A - Coax B - Twisted Pair C - Single D & E - Shield Twisted Pair

|     |        | REVISE ON PC ONLY       | TITLE                                  |                    |         |
|-----|--------|-------------------------|--|--------------------|---------|
|     | D      | SEE SHEET 1             | VIDEO CABLE SPE                        | ECIFICATION        |         |
| 1   |        |                         | THIS DOCUMENT CONTAINS INFORMATION     | THAT IS PROPRIETAR | RY TO   |
|     | REV    | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITH | HOUT WRITTEN PERM  | IISSION |
| DOC | CUMENT | NO.                     |  | FILE NAME          | SHEET   |
|     |        | PS-74411-001            |  | PS74411            | 12      |
|     |        | ES-40000-3996 REV. A SH | HEET 4 95/MAR/10 EC U5-0926 DC         | CBRD03.SAM         |         |





LANGUAGE

English

# **Electrical Requirements (Continued)**

Attenuation: Component A - Standard Construction

| Frequency | Maximum A | Attenuation |
|-----------|-----------|-------------|
| MHz       | dB/100 ft | dB/100 m    |
| 1         | 0.8       | 2.6         |
| 10        | 2.6       | 8.5         |
| 50        | 5.8       | 19.0        |
| 100       | 8.2       | 26.9        |
| 200       | 12.0      | 39.4        |
| 400       | 17.0      | 55.8        |
| 700       | 24.0      | 78.7        |
| 900       | 28.0      | 91.9        |
| 1000      | 30.0      | 98.4        |

Differential Attenuation: Component D & E - Standard Construction

| Frequency | Maximum A | Attenuation |
|-----------|-----------|-------------|
| MHz       | dB/100 ft | dB/100 m    |
| 1         | 1.00      | 3.30        |
| 10        | 4.00      | 13.10       |
| 50        | 8.00      | 26.20       |
| 100       | 10.00     | 32.80       |
| 200       | 15.00     | 49.20       |
| 400       | 21.00     | 68.90       |
| 600       | 26.00     | 85.30       |
| 800       | 30.00     | 98.40       |

|    |        | REVISE ON PC ONLY      | TITLE   |            |       |
|----|--------|------------------------|---|------------|-------|
|    | D      | SEE SHEET 1            | VIDEO CABLE SPE   | CIFICATION | į.    |
|    | REV    | DESCRIPTION            | THIS DOCUMENT CONTAINS INFORMATION MOLEX INC. AND SHOULD NOT BE USED WITH |            |       |
| DO | CUMENT | NO.                    |   | FILE NAME  | SHEET |
|    |        | PS-74411-001           |   | PS74411    | 13    |
|    |        | ES-40000-3996 REV. A S | HEET 4 95/MAR/10 EC U5-0926 DC  | BRD03.SAM  | •     |





LANGUAGE

English

# **Electrical Requirements (Continued)**

Attenuation: Component A - 5.5mm O.D.

| Frequency | Maximum A | Attenuation |
|-----------|-----------|-------------|
| MHz       | dB/100 ft | dB/100 m    |
| 1         | 0.9       | 3.0         |
| 10        | 3.0       | 9.8         |
| 50        | 6.7       | 21.9        |
| 100       | 9.4       | 30.9        |
| 200       | 13.8      | 45.3        |
| 400       | 19.6      | 64.2        |
| 700       | 27.6      | 90.5        |
| 900       | 32.2      | 105.7       |
| 1000      | 34.5      | 113.2       |

Differential Attenuation: Component D & E - 5.5mm O.D.

| Frequency | Maximum A | Attenuation |
|-----------|-----------|-------------|
| MHz       | dB/100 ft | dB/100 m    |
| 1         | 1.20      | 3.90        |
| 10        | 4.60      | 15.10       |
| 50        | 9.20      | 30.20       |
| 100       | 11.50     | 37.70       |
| 200       | 17.30     | 56.80       |
| 400       | 24.20     | 79.40       |
| 600       | 29.90     | 98.10       |
| 800       | 34.50     | 113.20      |

|     |        | REVISE ON PC ONLY      | TITLE                                  |                   |         |
|-----|--------|------------------------|--|-------------------|---------|
|     | D      | SEE SHEET 1            | VIDEO CABLE SPE                        | CIFICATION        | į       |
|     |        |                        | THIS DOCUMENT CONTAINS INFORMATION     |                   |         |
|     | REV    | DESCRIPTION            | MOLEX INC. AND SHOULD NOT BE USED WITH | IOUT WRITTEN PERM | IISSION |
| DOC | CUMENT | NO.                    |  | FILE NAME         | SHEET   |
|     |        | PS-74411-001           |  | PS74411           | 14      |
|     |        | ES-40000-3996 REV. A S | HEET 4 95/MAR/10 EC U5-0926 DC         | BRD03.SAM         |         |





**LANGUAGE** English

# Safety Requirements

UL Listing: AWM Style 20276 60 °C (minimum) 30 Volts (minimum) VW-1

# **Polystyrene Migration Test Requirements**

Polystyrene Migration testing is required for the outer jacket of all cables according to the following parameters.

| Test Parameters            |   |  |  |  |  |  |
|----------------------------|---|--|--|--|--|--|
| Temperature $50 \pm 1$ °C  |   |  |  |  |  |  |
| Weight                     | $500 \pm 25 \text{ grams}$  |  |  |  |  |  |
| Time                       | 24 ± 1 hours  |  |  |  |  |  |
| Material                   | ABS   |  |  |  |  |  |
| Visual Inspection Criteria | No staining of the ABS material should be visible when viewed by the unaided eve. |  |  |  |  |  |

## **Supplier Approval Requirements**

New Supplier Qualification:
Prior to initial approval, the supplier must submit the following items to Molex Lisle:
1. Supplier Specifications
2. Sample Cable
3. Electrical Test Data
4. Polystyrene Migration Test Data

Approval of a new cable configuration from an approved supplier: The following should be submitted to Molex for approval of a new cable.

1. Supplier Specifications - Of the new cable.

2. Sample Cable - Contact Molex to determine whether a sample of the new cable is required.

Supplier Requested Revisions:

Prior to a revision of these specifications, a supplier must submit the following to Molex Lisle before the

changes are implemented:

1. Revised Supplier Specifications - Along with an attached cover sheet clearly identifying all proposed changes.

Sample Cable - This is to be provided if any changes in material or construction are requested. Electrical Test Data - This is to be provided for all affected components Polystyrene Migration Test Data - This is to be provided if any changes to the outer jacket are proposed.

Approval Responsibility:
This specification is created and maintained by Molex Lisle. As a result, only Molex Lisle can grant final approval for a new supplier, cable configuration, or change in cable construction.

|     |        | REVISE ON PC ONLY       | TITLE                                  | OUTION             |         |
|-----|--------|-------------------------|--|--------------------|---------|
|     | D      | SEE SHEET 1             | VIDEO CABLE SPE                        | :CIFICATION        |         |
|     |        |                         | THIS DOCUMENT CONTAINS INFORMATION     | THAT IS PROPRIETAI | RY TO   |
|     | REV    | DESCRIPTION             | MOLEX INC. AND SHOULD NOT BE USED WITH | OUT WRITTEN PERM   | MISSION |
| DOC | CUMENT | NO.                     |  | FILE NAME          | SHEET   |
|     |        | PS-74411-001            |  | PS74411            | 15      |
|     |        | ES-40000-3996 REV. A SI | HEET 4 95/MAR/10 EC U5-0926 DC         | BRD03.SAM          | •       |





LANGUAGE English

# 1.0 SCOPE

This specification covers the requirements of solder and weld terminations for Digital Visual Interface (DVI) cable assemblies.

## 2.0 REFERENCE DOCUMENTS

PS-74320-001

**DVI Product Specification** 

PS-74411-001

Video Cable Specification

| REV  | Α    | Α    | Α     | Α    | Α   | Α     | Α    | Α    | Α    | Α    |      | •     |     |      |      |      |     |     |      |      |       |       |    |
|--|------|------|-------|------|-----|-------|------|------|------|------|------|-------|-----|------|------|------|-----|-----|------|------|-------|-------|----|
| SHT  | 1    | 2    | 3     | 4    | 5   | 6     | 7    | 8    | 9    | 10   |      | • • • |     |      |      |      |     |     |      |      |       |       |    |
| <br>   | REV  | ISE  | ON F  | >C C | NLY | ,     |      | TIT  | LE   |      |      |       |     |      |      |      |     |     |      |      |       |       |    |
| INITIAL RELEASE A PER EC #UDT2000-0945 DSCHMIDG 00/03/22  TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES |      |      |       |      |     |       |      |      |      |      |      |       |     |      |      |      |     |     |      |      |       |       |    |
| REV  |      |      | DES   | CRIF | TIO | N     |      | THIS |      |      |      |       |     |      |      |      |     |     |      |      | RY TO | – – 1 |    |
| DES  | GN ( | CON  | ITRC  | )L   | S   | TAT   | US   | WRI  | TTEN | IBY: | CHE  | CKEC  | BY: | API  | PROV | ED B | Y:  | DA  | TE:  | YR / | MO /  | DAY   |    |
|  | UE   | T    |       |      |     | М     |      | DSC  | СНМ  | IDG  | N    | ELSC  | NC  | ١    | NELS | SON  |     |     |      | 00/  | 03/22 | .     | .  |
| DOCUMENT NO.   |      |      |       |      |     |       |      |      |      |      |      |       |     |      |      | FIL  | E N | AME | SI   | HT N | 10.   |       |    |
|  | ES-  | 7432 | 20-00 | )2   |     |       |      |      |      |      |      |       |     |      |      |      |     | ES7 | 4320 | LWP  | 1 (   | OF    | 10 |
|  | E    | S-40 | 000-  | 3996 | RE  | EV. A | \ SI | HEE" | Γ5   | 95/N | IAR/ | 10    | EC  | U5-( | 0926 |      | CB  | RDC | 5.S/ | λM   |       |       |    |





LANGUAGE English

## 3.0 CABLE PINOUTS

| Pin | Signal Assignment       | Pin | Signal Assignment        | Pin | Signal Assignment        |
|-----|-------------------------|-----|--------------------------|-----|--------------------------|
| 1   | T.M.D.S. Data2-         | 9   | T.M.D.S. Data1-          | 17  | T.M.D.S. Data 0-         |
| 2   | T.M.D.S. Data2+         | 10  | T.M.D.S. Data1+          | 18  | T.M.D.S. Data 0+         |
| 3   | T.M.D.S. Data2/4 Shield | 11  | T.M.D.S. Data 1/3 Shield | 19  | T.M.D.S. Data 0/5 Shield |
| 4   | T.M.D.S. Data 4-        | 12  | T.M.D.S. Data 3-         | 20  | T.M.D.S. Data 5-         |
| 5   | T.M.D.S. Data 4+        | 13  | T.M.D.S. 3+              | 21  | T.M.D.S. Data 5+         |
| 6   | DDC Clock               | 14  | +5 V Power               | 22  | T.M.D.S. Clock Shield    |
| 7   | DDC Data                | 15  | Ground (for +5V)         | 23  | T.M.D.S. Clock+          |
| 8   | No Connect              | 16  | Hot Plug Detect          | 24  | T.M.D.S. Clock-          |

# Digital-Only Connector Pin Assignments

| Pin | Signal Assignment        | Pin | Signal Assignment        | Pin | Signal Assignment        |
|-----|--------------------------|-----|--------------------------|-----|--------------------------|
| 1   | T.M.D.S. Data 2-         | 9   | T.M.D.S. Data 1-         | 17  | T.M.D.S. Data 0-         |
| 2   | T.M.D.S. Data 2+         | 10  | T.M.D.S. Data 1+         | 18  | T.M.D.S. Data 0+         |
| 3   | T.M.D.S. Data 2/4 Shield | 11  | T.M.D.S. Data 1/3 Shield | 19  | T.M.D.S. Data 0/5 Shield |
| 4   | T.M.D.S. Data 4-         | 12  | T.M.D.S. Data 3-         | 20  | T.M.D.S. Data 5-         |
| 5   | T.M.D.S. Data 4+         | 13  | T.M.D.S. Data 3+         | 21  | T.M.D.S. Data 5+         |
| 6   | DDC Clock                | 14  | +5V Power                | 22  | T.M.D.S. Clock Shield    |
| 7   | DDC Data                 | 15  | Ground                   | 23  | T.M.D.S. Clock+          |
| 8   | Analog Vertical Sync     | 16  | Hot Plug Detect          | 24  | T.M.D.S. Clock-          |
| C1  | Analog Red               | C2  | Analog Green             | C3  | Analog Blue              |
| C4  | Analog Horizontal Sync   | C5  | Analog Ground            |     |                          |

# Combined Analog and Digital Connector Pin Assignments

| REVISE ON PC ONLY |                        | TITLE  |                    |        |  |
|-------------------|------------------------|--|--------------------|--------|--|
| A                 | SEE SHEET 1            | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES |                    |        |  |
|                   |                        | THIS DOCUMENT CONTAINS INFORMATION TH          | IAT IS PROPRIETARY | ГО МОЦ |  |
| REV               | DESCRIPTION            | INC. AND SHOULD NOT BE USED WITHOU             | JT WRITTEN PERMISS | ION    |  |
|                   | OCUMENT NO.            |  | FILE NAME          | SHEET  |  |
|                   | ES-74320 -002          |  | ES74320.LWP        | 2      |  |
|                   | ES-40000-3996 REV. A S | HEET 6 95/MAR/10 EC U5-0926 D                  | CBRD05.SAM         |        |  |






LANGUAGE English

#### 4.0 TERMINATION PROCEDURES

- 4.1 Wire Strip Lengths
  - 4.1.1 TMDS Shield Strip Length




## Dim A.

For DVI-D = .630 (16.0)

For DVI-I = .906 (23.0)

Foil shield must remain tightly wound after stripping.

4.1.2 Insulation Strip Length for All Wires



Conductors must remain tightly wound after wire stripping. Nicking of conductors is NOT acceptable.

|  | REVISE ON PC ONLY |                        | TITLE   |  |                 |     |                   |     |    |
|--|-------------------|------------------------|---|--|-----------------|-----|-------------------|-----|----|
|  | Α                 | SEE SHEET 1            |   | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES |                 |     |                   |     |    |
|  |                   |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOL |  |                 |     |                   |     |    |
|  | REV               | DESCRIPTION            | INC   | C. AND SHOULD                                  | NOT BE USED WIT | HOU | T WRITTEN PERMISS | ION |    |
|  |                   | OCUMENT NO.            |   |  |                 |     | FILE NAME         | SHE | ET |
|  |                   | ES-74320 -002          |   |  |                 |     | ES74320.LWP       | 3   |    |
|  |                   | ES-40000-3996 REV. A S | SHEET 6   | 95/MAR/10                                      | EC U5-0926      | DC  | CBRD05.SAM        |     |    |






LANGUAGE English

### 4.2 Shrink Tubing

A minimum of two pieces of shrink tubing is required per TMDS pair. One piece is used to cover the exposed drain wire. The other piece must cover the cut edge of the foil shield and extend to within Dim. B of the contact tails as shown below.



Dim. B

For DVI-D = .354 (9.0)

For DVI-I = .630 (16.0)

|   | REVISE ON PC ONLY |                     | TITLE   |  |                    |       |  |
|---|-------------------|---------------------|---|--|--------------------|-------|--|
|   | A                 | SEE SHEET 1         | · · · · · · · · · · · · · · · · · ·                           | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES |                    |       |  |
| l |                   |                     | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOL |  |                    |       |  |
|   | REV               | DESCRIPTION         | INC. AND SHOULD NOT BE USE                                    | D WITHO  | UT WRITTEN PERMISS | ION   |  |
|   |                   | OCUMENT NO.         |   |  | FILE NAME          | SHEET |  |
|   |                   | ES-74320 -002       |   |  | ES74320.LWP        | 4     |  |
|   |                   | ES-40000-3996 RFV A | SHEET 6 95/MAR/10 FC U5-09                                    | 926 F  | CBRD05 SAM         |       |  |






LANGUAGE

English

#### 4.3 Termination Detail

Individual wires can be either soldered or welded to the contact tails.



|  | REVISE ON PC ONLY |                        | TITLE   |                    |       |
|--|-------------------|------------------------|---|--------------------|-------|
|  | А                 | SEE SHEET 1            | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES                |                    |       |
|  |                   |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOL |                    |       |
|  | REV               | DESCRIPTION            | INC. AND SHOULD NOT BE USED WITHO                             | UT WRITTEN PERMISS | ION   |
|  |                   | OCUMENT NO.            |   | FILE NAME          | SHEET |
|  |                   | ES-74320 -002          |   | ES74320.LWP        | 5     |
|  |                   | ES-40000-3996 REV. A S | SHEET 6 95/MAR/10 EC U5-0926 D                                | CBRD05.SAM         |       |






LANGUAGE

English

#### 4.4 Coaxial Termination Detail

Individual wires can be either soldered or welded to the contact tails.

Tin Jacket Shield prior to solder reflow process to ensure solder flows along the areas indicated.



|   | REVISE ON PC ONLY |                        | TITLE   |            |             |       |  |
|---|-------------------|------------------------|---|------------|-------------|-------|--|
| _ | A                 | SEE SHEET 1            | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES                |            |             |       |  |
|   |                   |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOL |            |             |       |  |
|   | REV               | DESCRIPTION            | INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION        |            |             | ION   |  |
|   |                   | DOCUMENT NO.           |   |            | FILE NAME   | SHEET |  |
|   |                   | ES-74320 -002          |   |            | ES74320.LWP | 6     |  |
|   |                   | ES-40000-3996 REV. A S | SHEET 6 95/MAR/10   | EC U5-0926 | DCBRD05.SAM |       |  |






LANGUAGE


English

#### 5.0 SOLDER INSPECTION CRITERIA

## 5.1 Acceptable Solder Joint Characteristics



# 5.2 Unacceptable Solder Joint Characteristics



|  | REVISE ON PC ONLY |               | TITLE  | TITLE                                       |   |            |                      |       |
|--|-------------------|---------------|--------|---|---|------------|----------------------|-------|
|  | Α                 | SEE SHEET 1   |        |   | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES                |            |                      |       |
|  |                   |               |        |   | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOL |            |                      |       |
|  | REV               | DESCRIPT      | ΓΙΟΝ   | ON INC. AND SHOULD NOT BE USED WITHOUT WRIT |   |            | HOUT WRITTEN PERMISS | SION  |
|  |                   | OCUMENT NO.   |        |   |   |            | FILE NAME            | SHEET |
|  |                   | ES-74320 -002 |        |   |   |            | ES74320.LWP          | 7     |
|  |                   | ES-40000-3996 | REV. A | SHEET 6                                     | 95/MAR/10   | EC U5-0926 | DCBRD05.SAM          |       |






LANGUAGE English

Note: The list of examples shown here is not all inconclusive.

#### 6.0 WELD INSPECTION CRITERIA

- 6.1 Weld Inspection Details
  - 1 There must be no visible separation between the conductors and the contacts.
  - 2 The conductor must be centered on the contacts. Alignment between the conductor and the contact must be within 10°. Any portion of the conductors extending beyond



a .005" (0.13mm) boundary of each edge of the contact is cause for rejection.

- 3 The conductor must not be smashed onto the contact. The overall diameter of the conductor bundle after termination should be at least 60% of the original diameter.
- 4 The finished weld should be free of deep electrode indentations, electrode deposits, pits, cracks, strand separation or abnormal discoloration around the weld. Note:

  Surface appearance is not always a good indicator of weld quality. Insufficient

|   | REVISE ON PC ONLY |                       | TITLE   |                     |       |  |
|---|-------------------|-----------------------|---|---------------------|-------|--|
| _ | A SEE SHEET 1     |                       | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES                |                     |       |  |
|   |                   |                       | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOL |                     |       |  |
|   | REV               | DESCRIPTION           | INC. AND SHOULD NOT BE USED WITH                              | OUT WRITTEN PERMISS | ION   |  |
|   | D                 | OCUMENT NO.           |   | FILE NAME           | SHEET |  |
|   |                   | ES-74320 -002         |   | ES74320.LWP         | 8     |  |
|   |                   | ES-40000-3996 REV A S | SHEET 6 95/MAR/10 EC U5-0926                                  | DCBRD05 SAM         |       |  |





LANGUAGE English

heating or inadequate penetration, for example, usually leave no visible effects on the work piece.

- 5 Cracks, spitting (forcible ejection of material from the weld), and voids are not permitted.
- 6 Spikes on the top surface of the wire (evidence of "tip pickup" or welding of the electrode) are cause for rejection.
- 7 The peel strength of each conductor bundle must be greater than 65% of the tensile strength of the undisturbed bundle according to the following equation.

$$A_p - (3 \times S_d) \ge 0.65 \times T_w$$

where:

 $A_p$  = the average peel test value

 $S_d$  = the standard deviation of these values

 $T_w$  = the tensile strength of the wire

i.e. The mean tensile strength of the samples must be at least 3 standard deviations greater than 65% of the wire's original tensile strength.

|   | REVISE ON PC ONLY |                        | TITLE  |                 |                       |       |
|---|-------------------|------------------------|--|-----------------|-----------------------|-------|
| _ | Α                 | SEE SHEET 1            | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES |                 |                       |       |
|   |                   |                        | <b>–</b>                                       |                 | THAT IS PROPRIETARY 1 |       |
| L | REV               | DESCRIPTION            | INC. AND SHOULD                                | NOT BE USED WIT | HOUT WRITTEN PERMISS  | ION   |
|   | D                 | OCUMENT NO.            |  |                 | FILE NAME             | SHEET |
|   |                   | ES-74320 -002          |  |                 | ES74320.LWP           | 9     |
|   |                   | ES-40000-3996 REV. A S | SHEET 6 95/MAR/10                              | EC U5-0926      | DCBRD05.SAM           |       |





LANGUAGE

English


|  | REVISE ON PC ONLY |                        | TITLE   |            |             |       |
|--|-------------------|------------------------|---|------------|-------------|-------|
|  | А                 | SEE SHEET 1            | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES                |            |             |       |
|  |                   |                        | THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOL |            |             |       |
|  | REV               | DESCRIPTION            | INC. AND SHOULD NOT BE USED WITHOUT WRITTEN PERMISSION        |            |             | ION   |
|  |                   | DOCUMENT NO.           |   |            | FILE NAME   | SHEET |
|  |                   | ES-74320 -002          |   |            | ES74320.LWP | 10    |
|  |                   | ES-40000-3996 REV. A S | HEET 6 95/MAR/10  | EC U5-0926 | DCBRD05.SAM |       |






LANGUAGE English

# 6.2 Acceptable Weld Characteristics



# 6.3 Unacceptable Weld Characteristics



Note: The list of examples shown here is not all inconclusive.

|   |     | REVISE ON PC ONLY      | TITLE   |                 |                      |       |
|---|-----|------------------------|---|-----------------|----------------------|-------|
| - | A   | SEE SHEET 1            | TERMINATION SPECIFICATION DVI CABLE ASSEMBLIES  THIS DOCUMENT CONTAINS INFORMATION THAT IS PROPRIETARY TO MOL |                 |                      |       |
|   |     |                        |   |                 |                      |       |
|   | REV | DESCRIPTION            | INC. AND SHOULD   | NOT BE USED WIT | HOUT WRITTEN PERMISS | ION   |
|   |     | DOCUMENT NO.           |   |                 | FILE NAME            | SHEET |
|   |     | ES-74320 -002          |   |                 | ES74320.LWP          | 11    |
|   |     | ES-40000-3996 REV. A S | SHEET 6 95/MAR/10   | FC U5-0926      | DCBRD05.SAM          |       |

# **APPENDIX B**

# **TERMS AND CONDITIONS**

| LEASE NEW         | B-3 |
|-------------------|-----|
| BUY NEW           | B-5 |
| LEASE REFURBISHED | B-6 |
| BUY REFURBISHED   | B-8 |

Molex distributes their Harness Assembly Tools and Machines through several different plans:

- 1. Lease New ----- The customer may lease a new machine or tool for a prearranged period of time:
- 2. Buy New ----- The customer may purchase a new machine or tool outright;
- 3. Lease Refurbished------ If available, a customer may lease a completely refurbished machine or tool for a prearranged period of time.
- 4. Buy Refurbished ----- Again if available, a customer may purchase a completely refurbished machine or tool outright.

The terms and conditions, including warranties, vary with each plan. The following pages list the generic parts of these four (4) plans.

NOTE: Not all tooling is available through all four (4) plans. i.e.: Some tooling is purchase only and some is lease only. Contact your local Molex Sales Engineer for additional information.

## MOLEX EQUIPMENT LEASE TERMS AND CONDITIONS

#### ARTICLE I OWNERSHIP OF EQUIPMENT

1.01 ALL EQUIPMENT is owned by LESSOR. No right, title or interest in the EQUIPMENT shall pass to LESSEE other than, conditioned upon LESSEE'S performance hereunder, the right to maintain possession and use of the EQUIPMENT.

#### ARTICLE II SERVICE OF EQUIPMENT

- 2.01 LESSOR will provide LESSEE with instructions as to the set up, operation and maintenance of the equipment and, at LESSEE'S expense, an inventory of recommended perishable tooling.
- 2.02 LESSOR will service the EQUIPMENT (except for minor repairs and/or maintenance) to the extent provided for in the succeeding paragraphs.
- 2.03 If, during the first ninety (90) days after LESSEE received possession of the EQUIPMENT, the EQUIPMENT fails to perform in a satisfactory manner (except by reason of LESSEE'S misuse or negligence), LESSOR will repair the EQUIPMENT, at no cost for parts and labor, as soon as possible after notification.
- After the first ninety (90) days of LESSEE'S possession, should the EQUIPMENT fail to operate satisfactorily (except by reason of LESSEE'S misuse or negligence), LESSOR will supply LESSEE with all the required perishable parts at the current standard selling price as soon as possible after notification. Spare parts will continue to be provided on a no-charge basis throughout the term of the lease. Should LESSEE be unable to repair the equipment, LESSOR will repair the inoperable equipment as soon as possible after notification.
- 2.05 By definition, perishable parts are those items that come in contact with the product media during the termination process. The media, normally, would be terminals, wire, connectors, cable, and the like. Examples of perishable parts are: punches, anvils, insertion blades, connector/terminal guides, etc. Where-in examples of spare parts are: motors, solenoids, valves, cylinders, et al.
- 2.06 If LESSOR cannot repair the EQUIPMENT as stated in paragraphs 2.03 and 2.04 hereof, LESSOR will replace the EQUIPMENT or any portion thereof, as soon as possible.
- 2.07 LESSOR cannot be responsible for the quality of connectors or terminals other than those of LESSOR. Accordingly, notwithstanding paragraphs 2.03 and 2.04 and/or 2.06 hereof, LESSOR reserves the right to charge LESSEE the cost of labor and/or parts for repairing EQUIPMENT which is applying connectors or terminals other than LESSOR's.
- 2.08 LESSOR cannot be responsible for any modifications performed by LESSEE on the EQUIPMENT or the performance of the EQUIPMENT when used in association with machine components not supplied by LESSOR. Accordingly, notwithstanding paragraphs 2.03, 2.04 and/or 2.06 hereof, LESSOR reserves the right to charge LESSEE the cost of labor, and/or parts for the repairing the EQUIPMENT modified by LESSEE or used in association with machine components not supplied by LESSOR.

#### ARTICLE III WARRANTIES AND REMEDIES

- 3.0 In case of breach of warranty by LESSOR, LESSEE'S sole remedy shall be repair, or, at LESSOR's option, replacement of the EQUIPMENT.
- 3.02 Under no circumstances shall LESSEE be entitled to any special or consequential damages for any action or non-action taken by LESSOR in connection with furnishing or servicing the EQUIPMENT.

#### ARTICLE IV LESSEE'S OBLIGATIONS

4.01 General - LESSEE shall use the EQUIPMENT in a careful manner, shall comply with all the laws relating to its possession, use, and maintenance and shall be responsible for keeping the EQUIPMENT in good repair, condition and working order and will not modify the EQUIPMENT without the prior written consent of LESSOR.

# ARTICLE IV LESSEE'S OBLIGATIONS (Continued)

- 4.02 Inspection LESSEE shall permit LESSOR to inspect the EQUIPMENT and any pertinent records concerning the EQUIPMENT during LESSEE'S business hours.
- 4.03 Insurance LESSEE shall provide, maintain, and pay for insurance against loss, theft, damage, and destruction of the EQUIPMENT. LESSEE shall also provide, maintain, and pay for public liability insurance, both personal injury and property damage, covering the EQUIPMENT in form and amount satisfactory to LESSOR.
- 4.04 Liens LESSEE shall keep the EQUIPMENT free and clear of all levies, liens and encumbrances caused by LESSEE and shall not permit the EQUIPMENT to become a fixture on any premises.
- 4.05 Taxes LESSEE shall pay all charges and taxes, which may now or hereafter be imposed upon the leasing, rental, possession or use of the EQUIPMENT. LESSOR shall have the right to invoice LESSEE any such taxes that it has paid.
- 4.06 Risk of loss LESSEE assumes and shall bear the entire risk of loss, theft, destruction, and damage to the EQUIPMENT from any and every cause whatsoever from the date of delivery until return of the EQUIPMENT to LESSOR's plant excepting only that damage directly attributable to LESSOR's negligence. In the event of damage, LESSEE shall, as soon as possible, replace of repair the EQUIPMENT.
- 4.07 Indemnification LESSEE shall indemnify, hold harmless, and (at LESSOR's option but at LESSEE'S expense) defend LESSOR against any and all claims, actions, liabilities, losses, damages, and expenses including attorney's fees, arising out of LESSEE'S breach of its obligations under this Agreement.

#### ARTICLE V TERMINATION

- 5.01 Either party hereto may terminate this Agreement for nonperformance under any provision hereof within 10 days after the complaining party has made written demand therefore.
- 5.02 Lessor, at its sole discretion, may terminate this Agreement in the event of LESSEE'S bankruptcy, receivership, insolvency, assignment for the benefit of creditors or similar action or condition relating to LESSEE or LESSOR's property.
- 5.03 Upon termination of this Agreement for any reason except LESSOR's breach, LESSEE, at its expense, will return the EQUIPMENT in as good condition as received less normal wear, tear and depreciation to one of LESSOR's facilities situated in Illinois that shall be designated by LESSOR.

#### ARTICLE VI MISCELLANEOUS

- All notices hereunder shall be in writing and mailed to the respective parties, by registered or certified mail, at the address set forth in the preamble on the face of this Agreement.
- This Agreement cannot be varied except by a writing signed by authorized agents of the parties. The definition of EQUIPMENT may be enlarged with the written consent of the parties. Any additional items which become EQUIPMENT shall be fully governed by this Lease Agreement.
- 6.03 This Agreement shall be governed by the Laws of the State of Illinois.
- Any provision herein held unenforceable by a court of competent jurisdiction shall not affect any other provision herein and may be modified by such court so that it becomes reasonable and enforceable and, as modified, will be enforced as any other provision.

#### MOLEX EQUIPMENT SALES TERMS & CONDITIONS

# ARTICLE 1 SERVICE OF EQUIPMENT

- 1.01 SELLER will provide BUYER instructions as to the setup, operation and maintenance of the EQUIPMENT and an inventory of suggested perishable tooling, if ordered, at BUYER'S expense.
- 1.02 SELLER will service the EQUIPMENT (except for minor repairs and/or maintenance) to the extent provided for in the succeeding paragraphs.
- 1.03 If, during the first thirty (30) days after BUYER received possession of the EQUIPMENT, the EQUIPMENT fails to perform in a satisfactory manner (except by reason of BUYER'S misuse or negligence), SELLER will repair the EQUIPMENT, at no cost for parts and labor, as soon as possible after notification.
- 1.04 If, during the first year after BUYER received possession of the EQUIPMENT, the EQUIPMENT fails to perform in a satisfactory manner (except by reason of the BUYER'S misuse or negligence), SELLER will repair the EQUIPMENT, at no cost for spare parts and labor, as soon as possible after notification. The replacement of perishable parts during the remaining eleven (11) months of the warranty is the responsibility of the BUYER.
- 1.05 By definition, perishable parts are those that come into contact with the product media during the termination process. The media, normally, would be terminals, wire, connectors, cable and the like. Examples of perishable parts are: punches, anvils, insertion blades, connector/terminal guides, etc. Wherein examples of spare parts are: motors, solenoids, valves, cylinders, et. al.
- 1.06 If SELLER cannot repair the EQUIPMENT as stated in Paragraphs 1.03 and 1.04 hereof, SELLER will replace the EQUIPMENT, or any portion thereof, still under warranty.
- 1.07 After the first year of BUYER'S possession, should EQUIPMENT fail to operate satisfactorily, SELLER will supply BUYER with all the required parts at the current standard selling price, as soon as possible after notification. Should BUYER be unable to repair the EQUIPMENT, SELLER will repair the inoperable EQUIPMENT, as soon as possible after notification. at then current service charges.
- 1.08 SELLER cannot be responsible for the quality of the connectors or terminals other than those of the SELLER. Accordingly, notwithstanding Paragraphs 1.03, 1.04, 1.06, and/ or 1.07 herein, SELLER reserves the right to charge BUYER the cost of labor and/or parts for repairing EQUIPMENT which is applying connectors or terminals other than SELLER'S.
- 1.09 SELLER cannot be responsible for any modifications performed by the BUYER on the EQUIPMENT or the performance of the EQUIPMENT when used in association with machine components not supplied by the SELLER, Accordingly, notwithstanding Paragraphs 1.03, 1.04, 1.06 and/or 1.07 hereof, SELLER reserves the right to charge BUYER the cost of labor and/or parts for repairing the EQUIPMENT modified by the BUYER or used in association with machine components not supplied by SELLER.

# ARTICLE 11 WARRANTIES AND REMEDIES

- 2.01 In case of breach of warranty by SELLER, BUYER'S sole remedy shall be repair, or at SELLER'S option, replacement of the EQUIPMENT.
- 2.02 Under no circumstances shall BUYER be entitled to any special or consequential damages for any action or non-action taken by SELLER in connection with furnishing or servicing the EQUIPMENT.

# MOLEX EQUIPMENT LEASE TERMS AND CONDITIONS FOR REFURBISHED EQUIPMENT

#### ARTCLE I OWNERSHIP OF EQUIPMENT

1.01 ALL EQUIPMENT is owned by LESSOR. No right, title or interest in the EQUIPMENT shall pass to LESSEE other than, conditioned upon LESSEE'S due to performance hereunder, the right to maintain possession and use of the EQUIPMENT.

#### ARTICLE II SERVICE OF EQUIPMENT

- 2.01 LESSOR will provide LESSEE with instructions as to the set up, operation and maintenance of the equipment and, at LESSEE'S expense, an inventory of recommended perishable tooling.
- 2.02 LESSOR will service the EQUIPMENT (except for minor repairs and/or maintenance) to the extent provided for in the succeeding paragraphs.
- 2.03 If, during the first thirty (30) days after LESSEE received possession of the EQUIPMENT, the EQUIPMENT fails to perform in a satisfactory manner (except by reason of LESSEE'S misuse or negligence), LESSOR will repair the EQUIPMENT, at no cost for parts and labor, as soon as possible after notification.
- After the first thirty (30) days of LESSEE'S possession, should the EQUIPMENT fail to operate satisfactorily (except by reason of LESSEE'S misuse or negligence), LESSOR will supply LESSEE with all the required perishable parts at the current standard selling price as soon as possible after notification. Spare parts will continue to be provided on a no-charge basis throughout the term of the lease. Should LESSEE be unable to repair the equipment, LESSOR will repair the inoperable equipment as soon as possible after notification.
- 2.05 By definition, perishable parts are those items that come in contact with the product media during the termination process. The media, normally, would be terminals, wire, connectors, cable, and the like. Examples of perishable parts are: punches, anvils, insertion blades, connector/terminal guides, etc. Where-in examples of spare parts are: motors, solenoids, valves, cylinders, et al.
- 2.06 If LESSOR cannot repair the EQUIPMENT as stated in paragraphs 2.03 and 2.04 hereof, LESSOR will replace the EQUIPMENT or any portion thereof, as soon as possible.
- 2.07 LESSOR cannot be responsible for the quality of connectors or terminals other than those of LESSOR. Accordingly, notwithstanding paragraphs 2.03 and 2.04 and/or 2.06 hereof, LESSOR reserves the right to charge LESSEE the cost of labor and/or parts for repairing EQUIPMENT which is applying connectors or terminals other than LESSOR'S.
- LESSOR cannot be responsible for any modifications performed by LESSEE on the EQUIPMENT or the performance of the EQUIPMENT when used in association with machine components not supplied by LESSOR. Accordingly, notwithstanding paragraphs 2.03, 2.04 and/or 2.06 hereof, LESSOR reserves the right to charge LESSEE the cost of labor, and/or parts for the repairing the EQUIPMENT modified by LESSEE or used in association with machine components not supplied by LESSOR.

#### ARTICLE III WARRANTIES AND REMEDIES

- 3.01 In case of breach of warranty by LESSOR, LESSEE'S sole remedy shall be repair, or, at LESSOR'S option, replacement of the EOUIPMENT.
- 3.02 Under no circumstances shall LESSEE be entitled to any special or consequential damages for any action or non-action taken by LESSOR in connection with furnishing or servicing the EQUIPMENT.

#### ARTICLE IV LESSEE'S OBLIGATIONS

- 4.01 General LESSEE shall use the EQUIPMENT in a careful manner, shall comply with all the laws relating to its possession, use or maintenance and shall be responsible for keeping the EQUIPMENT in good repair, condition and working order and will not modify the EQUIPMENT without the prior written consent of LESSOR.
- 4.02 Inspection LESSEE shall permit LESSOR to inspect the EQUIPMENT and any pertinent records concerning the EQUIPMENT during LESSEE'S business hours.
- 4.03 Insurance LESSEE shall provide, maintain, and pay for insurance against loss, theft, damage, or destruction of the EQUIPMENT. LESSEE shall also provide, maintain, and pay for public liability insurance, both personal injury and property damage, covering the EQUIPMENT in form and amount satisfactory to LESSOR.
- 4.04 Liens LESSEE shall keep the EQUIPMENT free and clear of all levies, liens and encumbrances caused by LESSEE and shall not permit the EQUIPMENT to become a fixture on any premises.
- 4.05 Taxes LESSEE shall pay all charges and taxes, which may now or hereafter be imposed upon the leasing, rental, possession or use of the EQUIPMENT. LESSOR shall have the right to invoice LESSEE any such taxes that it has paid.
- 4.06 Risk of loss LESSEE assumes and shall bear the entire risk of loss, theft, destruction, or damages to the EQUIPMENT from any and every cause whatsoever from the date of delivery until return of the EQUIPMENT to LESSOR'S plant excepting only that damage directly attributable to LESSOR'S negligence. In the event of damage, LESSEE shall, as soon as possible, replace of repair the EQUIPMENT.
- 4.07 Indemnification LESSEE shall indemnify, hold harmless, and (at LESSOR'S option but at LESSEE'S expense) defend LESSOR against any and all claims, actions, liabilities, losses, damages, and expenses including attorney's fees, arising out of LESSEE'S breach of its obligations under this Agreement.

#### ARTICLE V TERMINATION

- 5.01 Either party hereto may terminate this Agreement for nonperformance under any provision hereof within 10 days after the complaining party has made written demand therefore.
- Lessor, at its sole discretion, may terminate this Agreement in the event of LESSEE'S bankruptcy, receivership, insolvency, assignment for the benefit of creditors or similar action or condition relating to LESSEE or LESSOR'S property.
- 5.03 Upon termination of this Agreement for any reason except LESSOR'S breach, LESSEE, at its expense, will return the EQUIPMENT in as good condition as received less normal wear, tear and depreciation to one of LESSOR'S plants situated in Illinois that shall be designated by LESSOR.

#### ARTICLE VI MISCELLANEOUS

- 6.01 All notices hereunder shall be in writing and mailed to the respective parties, by registered or certified mail, at the address set forth in the preamble on the face of this Agreement.
- This Agreement cannot be varied except by a writing signed by authorized agents of the parties. The definition of EQUIPMENT may be enlarged with the written consent of the parties. Any additional items which become EQUIPMENT shall be fully governed by this Lease Agreement.
- 6.03 This Agreement shall be governed by the Laws of the State of Illinois.
- Any provision herein held unenforceable by a court of competent jurisdiction shall not affect any other provision herein and may be modified by such court so that it becomes reasonable and enforceable and, as modified, will be enforced as any other provision.

# MOLEX SALES TERMS & CONDITIONS FOR REFURBISHED EQUIPMENT

#### ARTICLE 1 SERVICE OF EQUIPMENT

- 1.01 SELLER will provide BUYER instructions as to the setup, operation and maintenance of the EQUIPMENT and an inventory of suggested perishable tooling, if ordered, at BUYER'S expense.
- 1.02 SELLER will service the EQUIPMENT (except for minor repairs and/or maintenance) to the extent provided for in the succeeding paragraphs.
- 1.03 If, during the first thirty (30) days after BUYER received possession of the EQUIPMENT, the EQUIPMENT fails to perform in a satisfactory manner (except by reason of BUYER'S misuse or negligence), SELLER will repair the EQUIPMENT, at no cost for parts and labor, as soon as possible after notification.
- 1.04 If, during the first six (6) months after BUYER received possession of the EQUIPMENT, the EQUIPMENT fails to perform in a satisfactory manner (except by reason of the BUYER'S misuse or negligence), SELLER will repair the EQUIPMENT, at no cost for spare parts and labor, as soon as possible after notification. The replacement of perishable parts during the remaining five (5) months of the warranty is the responsibility of the BUYER.
- 1.05 By definition, perishable parts are those that come into contact with the product media during the termination process. The media, normally, would be terminals, wire, connectors, cable and the like. Examples of perishable parts are: punches, anvils, insertion blades, connector/terminal guides, etc. Wherein examples of spare parts are: motors, solenoids, valves, cylinders, et. al.
- 1.06 If SELLER cannot repair the EQUIPMENT as stated in Paragraphs 1.03 and 1.04 hereof, SELLER will replace the EQUIPMENT, or any portion thereof, still under warranty.
- 1.07 After the first year of BUYER'S possession, should EQUIPMENT fail to operate satisfactorily, SELLER will supply BUYER with all the required parts at the current standard selling price, as soon as possible after notification. Should BUYER be unable to repair the EQUIPMENT, SELLER will repair the inoperable EQUIPMENT, as soon as possible after notification. at then current service charges.
- 1.08 SELLER cannot be responsible for the quality of the connectors or terminals other than those of the SELLER. Accordingly, notwithstanding Paragraphs 1.03, 1.04, 1.06, and/ or 1.07 herein, SELLER reserves the right to charge BUYER the cost of labor and/or parts for repairing EQUIPMENT which is applying connectors or terminals other than SELLER'S.
- 1.09 SELLER cannot be responsible for any modifications performed by the BUYER on the EQUIPMENT or the performance of the EQUIPMENT when used in association with machine components not supplied by the SELLER, Accordingly, notwithstanding Paragraphs 1.03, 1.04, 1.06 and/or 1.07 hereof, SELLER reserves the right to charge BUYER the cost of labor and/or parts for repairing the EQUIPMENT modified by the BUYER or used in association with machine components not supplied by SELLER.

# ARTICLE 11 WARRANTIES AND REMEDIES

- 2.01 In case of breach of warranty by SELLER, BUYER'S sole remedy shall be repair, or at SELLER'S option, replacement of the EQUIPMENT.
- 2.02 Under no circumstances shall BUYER be entitled to any special or consequential damages for any action or non-action taken by SELLER in connection with furnishing or servicing the EOUIPMENT.